SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT
21865 Copley Drive, Diamond Bar, CA 91765

Title Page	
Facility ID:	800267
Revision #:	8
Date:	November 18, 2010

FACILITY PERMIT TO OPERATE

TRIUMPH PROCESSING, INC.
2605 INDUSTRY WAY
LYNWOOD, CA 90262

NOTICE

IN ACCORDANCE WITH RULE 206, THIS PERMIT TO OPERATE OR A COPY THEREOF MUST BE KEPT AT THE LOCATION FOR WHICH IT IS ISSUED.

THIS PERMIT DOES NOT AUTHORIZE THE EMISSION OF AIR CONTAMINANTS IN EXCESS OF THOSE ALLOWED BY DIVISION 26 OF THE HEALTH AND SAFETY CODE OF THE STATE OF CALIFORNIA OR THE RULES OF THE SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT. THIS PERMIT SHALL NOT BE CONSTRUED AS PERMISSION TO VIOLATE EXISTING LAWS, ORDINANCES, REGULATIONS OR STATUTES OF ANY OTHER FEDERAL, STATE OR LOCAL GOVERNMENTAL AGENCIES.

Barry R. Wallerstein, D. Env.
EXECUTIVE OFFICER

By _____ FOR
Mohsen Nazemi, P.E.
Deputy Executive Officer
Engineering & Compliance

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

TABLE OF CONTENTS

Section	Description	Revision #	Date Issued
A	Facility Information	1	03/26/2006
B	RECLAIM Annual Emission Allocation	1	03/26/2006
C	Facility Plot Plan	TO BE DEVELOPED	
D	Facility Description and Equipment Specific Conditions	5	03/26/2006
E	Administrative Conditions	1	03/26/2006
F	RECLAIM Monitoring and Source Testing Requirements	1	03/26/2006
G	Recordkeeping and Reporting Requirements for RECLAIM Sources	1	03/26/2006
H	Permit To Construct and Temporary Permit to Operate	6	11/18/2010
I	Compliance Plans & Schedules	1	03/26/2006
J	Air Toxics	1	03/26/2006
K	Title V Administration	1	03/26/2006
Appendix			
A	NOx and SOx Emitting Equipment Exempt From Written Permit Pursuant to Rule 219	1	03/26/2006
B	Rule Emission Limits	1	03/26/2006

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

Equipment	ID No.	Connected To	RECLAIM Source Type/ Monitoring Unit	Emissions* And Requirements	Conditions
Process 1: SPRAY COATING AND DRYING					
OVEN, CURING, NO. 4, BEATTIE, NATURAL GAS, MAXON CYCLOMAX, LOW NOX, 1.15 MMBTU/HR A/N: 514316 Permit to Construct Issued: 11/18/10	D6			**CO**: 2000 PPMV (5) [**RULE 407, 4-2-1982**]; **NOX**: 30 PPMV NATURAL GAS (5) [RULE 1147, 12-5-2008]; **PM**: (9) [**RULE 404, 2-7-1986**]; **PM**: 0.1 GRAINS/SCF (5) [**RULE 409, 8-7-1981**]	D182.3, D323.1, H23.7
OVEN, CURING, NO. 1, BEATTIE, NATURAL GAS, MAXON, CYCLOMAX, LOW NOX, 1.5 MMBTU/HR A/N: 514317 Permit to Construct Issued: 11/18/10	D7			**CO**: 2000 PPMV (5) [**RULE 407, 4-2-1982**]; **NOX**: 30 PPMV NATURAL GAS (5) [RULE 1147, 12-5-2008]; **PM**: (9) [**RULE 404, 2-7-1986**]; **PM**: 0.1 GRAINS/SCF (5) [**RULE 409, 8-7-1981**]	D182.3, D323.1, H23.7
OVEN, CURING, NO. 2, BEATTIE, NATURAL GAS, MAXON, CYCLOMAX, LOW NOX, 1 MMBTU/HR A/N: 514318 Permit to Construct Issued: 11/18/10	D9			**CO**: 2000 PPMV (5) [**RULE 407, 4-2-1982**]; **NOX**: 30 PPMV NATURAL GAS (5) [RULE 1147, 12-5-2008]; **PM**: (9) [**RULE 404, 2-7-1986**]; **PM**: 0.1 GRAINS/SCF (5) [**RULE 409, 8-7-1981**]	D182.3, D323.1, H23.7
Process 2: SURFACE PREPARATION					
System 1: Anodizing Line No. A3					
PROCESS TANK, HEATED, AIR SPARGED, NO. 60, CLEANING, ALKALINE SOAP SOLUTION, AIR SPARGED, WIDTH: 2 FT 6 IN; HEIGHT: 6 FT ; LENGTH: 62 FT A/N: 494828 Permit to Construct Issued: 11/18/09	D13				

* (1) (1A) (1B) Denotes RECLAIM emission factor
(2) (2A) (2B) Denotes RECLAIM emission rate
(3) Denotes RECLAIM concentration limit
(4) Denotes BACT emission limit
(5) (5A) (5B) Denotes command and control emission limit
(6) Denotes air toxic control rule limit
(7) Denotes NSR applicability limit
(8) (8A) (8B) Denotes 40 CFR limit (e.g. NSPS, NESHAPS, etc.)
(9) See App B for Emission Limits
(10) See section J for NESHAP/MACT requirements

** Refer to section F and G of this permit to determine the monitoring, recordkeeping and reporting requirements for this device.

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

Equipment	ID No.	Connected To	RECLAIM Source Type/ Monitoring Unit	Emissions* And Requirements	Conditions
Process 2: SURFACE PREPARATION					
PROCESS TANK, ETCHING, HEATED, AIR SPARGED, NO. 62, SODIUM HYDROXIDE, WIDTH: 2 FT 6 IN; HEIGHT: 6 FT ; LENGTH: 62 FT A/N: 494828 Permit to Construct Issued: 11/18/09	D14				
PROCESS TANK, UNHEATED, NO. 63, CLEANING, CHROMIC ACID, HYDROCHLORIC ACID, WIDTH: 2 FT 6 IN; HEIGHT: 6 FT ; LENGTH: 62 FT A/N: 494828 Permit to Construct Issued: 11/18/09	D15				
PROCESS TANK, UNHEATED, NO. 65, CONVERSION COATING, ALODINE, WIDTH: 2 FT 6 IN; HEIGHT: 6 FT ; LENGTH: 62 FT A/N: 494828 Permit to Construct Issued: 11/18/09	D16				
PROCESS TANK, CHROMIC ACID ANODIZING, HEATED, RECTIFIED-8,000 AMPS, NO. 67, CHROMIC ACID, WITH WATER SEALED COVER WITH 6 SUBMICRON MEMBRANE FILTERS, WIDTH: 3 FT ; HEIGHT: 6 FT ; LENGTH: 62 FT A/N: 494828 Permit to Construct Issued: 11/18/09	D17				D182.2, E193.1, E193.3, E193.4, E448.2, H23.6, K48.1
PROCESS TANK, UNHEATED, NO. 69, HOLDING TANK, WIDTH: 2 FT 6 IN; HEIGHT: 6 FT ; LENGTH: 62 FT A/N: 494828 Permit to Construct Issued: 11/18/09	D39				

* (1) (1A) (1B) Denotes RECLAIM emission factor
(2) (2A) (2B) Denotes RECLAIM emission rate
(3) Denotes RECLAIM concentration limit
(4) Denotes BACT emission limit
(5) (5A) (5B) Denotes command and control emission limit
(6) Denotes air toxic control rule limit
(7) Denotes NSR applicability limit
(8) (8A) (8B) Denotes 40 CFR limit (e.g. NSPS, NESHAPS, etc.)
(9) See App B for Emission Limits
(10) See section J for NESHAP/MACT requirements

** Refer to section F and G of this permit to determine the monitoring, recordkeeping and reporting requirements for this device.

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

Equipment	ID No.	Connected To	RECLAIM Source Type/ Monitoring Unit	Emissions* And Requirements	Conditions
Process 2: SURFACE PREPARATION					
PROCESS TANK, ANODIZING, UNHEATED, RECTIFIED, AIR SPARGED, NO. 70, SULFURIC ACID, WIDTH: 3 FT ; HEIGHT: 6 FT ; LENGTH: 62 FT A/N: 494828 Permit to Construct Issued: 11/18/09	D18				
PROCESS TANK, HEATED, NO. 72, SEALING, SODIUM CHROMATE, CHROMIC ACID, WIDTH: 2 FT 6 IN; HEIGHT: 6 FT ; LENGTH: 62 FT A/N: 494828 Permit to Construct Issued: 11/18/09	D62				
PROCESS TANK, HEATED, NO. 74, SEALING, SODIUM CHROMATE, CHROMIC ACID, WIDTH: 2 FT 6 IN; HEIGHT: 6 FT ; LENGTH: 62 FT A/N: 494828 Permit to Construct Issued: 11/18/09	D19				
System 2: Anodizing Line No. A1					
PROCESS TANK, HEATED, AIR SPARGED, NO. 1, CLEANING, ALKALINE SOAP SOLUTION, WIDTH: 3 FT ; HEIGHT: 9 FT ; LENGTH: 62 FT A/N: 494830 Permit to Construct Issued: 11/18/09	D81				
PROCESS TANK, ETCHING, HEATED, AIR SPARGED, NO. 3, SODIUM HYDROXIDE, WIDTH: 3 FT ; HEIGHT: 9 FT ; LENGTH: 26 FT A/N: 494830 Permit to Construct Issued: 11/18/09	D20	C43			

* (1) (1A) (1B) Denotes RECLAIM emission factor
(2) (2A) (2B) Denotes RECLAIM emission rate
(3) Denotes RECLAIM concentration limit
(4) Denotes BACT emission limit
(5) (5A) (5B) Denotes command and control emission limit
(6) Denotes air toxic control rule limit
(7) Denotes NSR applicability limit
(8) (8A) (8B) Denotes 40 CFR limit (e.g. NSPS, NESHAPS, etc.)
(9) See App B for Emission Limits
(10) See section J for NESHAP/MACT requirements

** Refer to section F and G of this permit to determine the monitoring, recordkeeping and reporting requirements for this device.

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

Equipment	ID No.	Connected To	RECLAIM Source Type/ Monitoring Unit	Emissions* And Requirements	Conditions
Process 2: SURFACE PREPARATION					
PROCESS TANK, UNHEATED, NO. 5, CLEANING, HYDROFLUORIC ACID, CHROMIC ACID, WIDTH: 3 FT ; HEIGHT: 9 FT ; LENGTH: 26 FT A/N: 494830 Permit to Construct Issued: 11/18/09	D21				
PROCESS TANK, UNHEATED, NO. 7, CONVERSION COATING, ALODINE, WIDTH: 3 FT ; HEIGHT: 9 FT ; LENGTH: 26 FT A/N: 494830 Permit to Construct Issued: 11/18/09	D22				
PROCESS TANK, CHROMIC ACID ANODIZING, HEATED, RECTIFIED-6,000 AMPS, NO. 9, CHROMIC ACID, WITH WATER SEALED COVER WITH 3 SUBMICRON MEMBRANE FILTERS, WIDTH: 5 FT ; HEIGHT: 10 FT ; LENGTH: 27 FT A/N: 494830 Permit to Construct Issued: 11/18/09	D23			**TOTAL CR**: (9) [**RULE 1469, #4, 10-9-1998**]	D182.2, E193.1, E193.3, E193.4, E448.2, H23.6, K48.1
PROCESS TANK, ANODIZING, UNHEATED, RECTIFIED, AIR SPARGED, NO. 11, SULFURIC ACID, WIDTH: 6 FT ; HEIGHT: 10 FT ; LENGTH: 26 FT A/N: 494830 Permit to Construct Issued: 11/18/09	D24				

* (1) (1A) (1B) Denotes RECLAIM emission factor
(2) (2A) (2B) Denotes RECLAIM emission rate
(3) Denotes RECLAIM concentration limit
(4) Denotes BACT emission limit
(5) (5A) (5B) Denotes command and control emission limit
(6) Denotes air toxic control rule limit
(7) Denotes NSR applicability limit
(8) (8A) (8B) Denotes 40 CFR limit (e.g. NSPS, NESHAPS, etc.)
(9) See App B for Emission Limits
(10) See section J for NESHAP/MACT requirements

** Refer to section F and G of this permit to determine the monitoring, recordkeeping and reporting requirements for this device.

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

Equipment	ID No.	Connected To	RECLAIM Source Type/ Monitoring Unit	Emissions* And Requirements	Conditions
Process 2: SURFACE PREPARATION					
PROCESS TANK, UNHEATED, AIR SPARGED, NO. 13, CONVERSION COATING, TRISODIUM PHOSPHATE, POTASSIUM FLUORIDE, WIDTH: 3 FT ; HEIGHT: 7 FT ; LENGTH: 26 FT A/N: 494830 Permit to Construct Issued: 11/18/09	D25				
PROCESS TANK, UNHEATED, AIR SPARGED, NO. 14, CLEANING, NITRIC ACID, WIDTH: 3 FT ; HEIGHT: 7 FT ; LENGTH: 26 FT A/N: 494830 Permit to Construct Issued: 11/18/09	D26				
PROCESS TANK, UNHEATED, AIR SPARGED, NO. 16, ETCHING, NITRIC ACID, AMMONIUM BIFLUORIDE, WIDTH: 3 FT ; HEIGHT: 7 FT ; LENGTH: 26 FT A/N: 494830 Permit to Construct Issued: 11/18/09	D27	C44			
PROCESS TANK, HEATED, NO. 19, SEALING, SODIUM CHROMATE, CHROMIC ACID, WIDTH: 3 FT ; HEIGHT: 9 FT ; LENGTH: 26 FT A/N: 494830 Permit to Construct Issued: 11/18/09	D28				
PROCESS TANK, HEATED, NO. 21, CONVERSION COATING, ALODINE, WIDTH: 3 FT ; HEIGHT: 9 FT ; LENGTH: 26 FT A/N: 494830 Permit to Construct Issued: 11/18/09	D29				

* (1) (1A) (1B) Denotes RECLAIM emission factor
(2) (2A) (2B) Denotes RECLAIM emission rate
(3) Denotes RECLAIM concentration limit
(4) Denotes BACT emission limit
(5) (5A) (5B) Denotes command and control emission limit
(6) Denotes air toxic control rule limit
(7) Denotes NSR applicability limit
(8) (8A) (8B) Denotes 40 CFR limit (e.g. NSPS, NESHAPS, etc.)
(9) See App B for Emission Limits
(10) See section J for NESHAP/MACT requirements

** Refer to section F and G of this permit to determine the monitoring, recordkeeping and reporting requirements for this device.

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: DEVICE ID INDEX

The following sub-section provides an index to the devices that make up the facility description sorted by device ID.

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: DEVICE ID INDEX

Device Index For Section H			
Device ID	**Section H Page No.**	**Process**	**System**
D6	1	1	0
D7	1	1	0
D9	1	1	0
D13	1	2	1
D14	2	2	1
D15	2	2	1
D16	2	2	1
D17	2	2	1
D18	3	2	1
D19	3	2	1
D20	3	2	2
D21	4	2	2
D22	4	2	2
D23	4	2	2
D24	4	2	2
D25	5	2	2
D26	5	2	2
D27	5	2	2
D28	5	2	2
D29	5	2	2
D39	2	2	1
D62	3	2	1
D81	3	2	2

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

FACILITY CONDITIONS

F2.1 The operator shall limit emissions from this facility as follows:

CONTAMINANT	EMISSIONS LIMIT
Single Volatile Hazardous Air Pollutant (VHAP)	Less than 10 TONS IN ANY ONE YEAR
Combination of Volatile Hazardous Air Pollutants (VHAPs)	Less than 25 TONS IN ANY ONE YEAR

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

To maintain exemption from the National Emission Standards for Hazardous Air Polutants (NESHAP) requirements, the operator shall comply with the Volatile Hazardous Air Pollutant (VHAP) emission limits of this condition.

To ensure compliance with the monthly and annual emission caps of this condition, the facility operator shall:

(a) In addition to the recordkeeping requirements of Rule 109, keep adequate records for this equipment and this facility to verify the monthly HAP emissions in pounds and the HAP content of each material as applied (including water and exempt compounds). The records shall be prepared in a format which is acceptable to the District.

(b) Within 14 calendar days after the end of each month, total and record HAP emissions for the month from all equipment and operations that are required to have written permits or are exempt from written permits pursuant to Rule 219. The record shall include any procedures used to account for control device efficiencies and/or waste disposal. It shall be signed and certified for accuracy by the highest ranking individual responsible for compliance with District rules.

(c) Maintain a single list which includes only the name and address of each person from whom the facility acquired HAP-containing material regulated by the District that was used or stored at the facility during the preceding 12 months.

(d) Retain all purchase invoices for all HAP-containing material used or stored at the facility, and all waste manifests for all waste HAP-containing material removed from the facility, for five years.

(e) All records required by this permit shall be prepared in a format which is acceptable to the District, retained at the facility for five years, and made available to any District representative upon request.

[**40CFR 63 Subpart GG, 12-8-2000**]

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

F9.1 Except for open abrasive blasting operations, the operator shall not discharge into the atmosphere from any single source of emissions whatsoever any air contaminant for a period or periods aggregating more than three minutes in any one hour which is:

(a) As dark or darker in shade as that designated No.1 on the Ringelmann Chart, as published by the United States Bureau of Mines; or

(b) Of such opacity as to obscure an observer's view to a degree equal to or greater than does smoke described in subparagraph (a) of this condition.

[**RULE 401, 3-2-1984;** RULE 401, 11-9-2001]

F14.1 The operator shall not use fuel oil containing sulfur compounds in excess of 0.05 percent by weight.

[**RULE 431.2, 5-4-1990;** RULE 431.2, 9-15-2000]

F14.2 The operator shall not purchase diesel fuel containing sulfur compounds in excess of 15 ppm by weight as supplied by the supplier.

[RULE 431.2, 9-15-2000]

DEVICE CONDITIONS

D. Monitoring/Testing Requirements

D182.2 The operator shall test this equipment in accordance with the following specifications:

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

The test shall be conducted according to the District approved protocol. A written report shall be submitted to the District within 30 days after the test is completed. The report shall include items as listed in ST-1 & ST-2 Form.

The test shall be conducted The test shall be conducted within thirty (30) days of the permit issuance date or within thirty (30) days of the start of operation of the equipment after the filter membrane cover is installed..

The test of D17 and D23 shall determine the total emission rate of hexavalent chromium and total chromium at the outlet of the membranes and in the head space in mg/amp-hr.

The test of D17 & D23 shall determine the seal integrity of the water-sealed cover pursuant to Rule 1469.

The District engineer identified on this conditional permit to construct shall be notified of the date and time of the test at least 10 days prior to the test.

The cover of Device Nos. D17 & D23 shall remained closed at all times, except when loading and unloading of parts.

[**RULE 1469, 10-9-1998;** RULE 1469, 5-2-2003; RULE 1469, 12-5-2008]

[Devices subject to this condition : D17, D23]

D182.3 The operator shall test this equipment in accordance with the following specifications:

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

A. The source test shall be conducted no later than 180 days after the initial start-up of this equipment unless otherwise approved in writing by the District.

B. A source test protocol shall be submitted to the District no later than 60 days after the initial start-up of this equipment unless otherwise approved in writing by the District. The test protocol shall be approved in writing by the District before the test commences.

C. The test protocol shall include the proposed operating conditions of the equipment during the test, the identity of the testing laboratory, a statement from the testing laboratory certifying that it meets the criteria in District Rule 304(k), and a description of the sampling and analytical procedures to be used.

D. The source tests shall consist of, but may not be limited to, testing of the dryer NOx and CO emissions, referenced at 3 percent volume stack gas oxygen on a dry basis, during as-found operating conditions of each dryer.

E. The source tests shall consist of, but may not be limited to, testing of the dryer NOx and CO emissions, referenced at 3 percent volume stack gas oxygen on a dry basis, while the dryer is operated below 25% of the maximum rated input heat capacity.

F. NOx and CO Emission determination shall be averaged over a period of at least 15 and no more than 60 consecutive minutes, and at least 15 minutes after unit start-up.

G. A written notice of the source tests shall be submitted to the District at least 14 days prior to the source testing date so that an observer from the District may be present.

H. Two complete copies of the source test report shall be submitted to the District within 45 days after source testing date unless otherwise approved in writing by the District. The source test report shall include, but may not be limited to, all testing data required by this condition.

I. A testing laboratory certified by the California Air Resources Board in the

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

required test methods for the criteria pollutants to be measured, and in compliance with District Rule 304 (no conflict of interest) shall conduct the test.

J. Sampling facilities shall comply with the District guidelines for construction of sampling and testing facilities, pursuant to Rule 217.

[RULE 1147, 12-5-2008]

[Devices subject to this condition : D6, D7, D9]

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

D323.1 The operator shall conduct an inspection for visible emissions from all stacks and other emission points of this equipment whenever there is a public complaint of visible emissions, whenever visible emissions are observed, and on a semi-annual basis, at least, unless the equipment did not operate during the entire semi-annual period. The routine semi-annual inspection shall be conducted while the equipment is in operation and during daylight hours.

If any visible emissions (not including condensed water vapor) are detected that last more than three minutes in any one hour, the operator shall verify and certify within 24 hours that the equipment causing the emission and any associated air pollution control equipment are operating normally according to their design and standard procedures and under the same conditions under which compliance was achieved in the past, and either:

1). Take corrective action(s) that eliminates the visible emissions within 24 hours and report the visible emissions as a potential deviation in accordance with the reporting requirements in Section K of this permit; or

2). Have a CARB-certified smoke reader determine compliance with the opacity standard, using EPA Method 9 or the procedures in the CARB manual "Visible Emission Evaluation", within three business days and report any deviations to AQMD.

The operator shall keep the records in accordance with the recordkeeping requirements in Section K of this permit and the following records:

1). Stack or emission point identification;

2). Description of any corrective actions taken to abate visible emissions;

3). Date and time visible emission was abated; and

4). All visible emission observation records by operator or a certified smoke reader.

[**RULE 3004(a)(4)-Periodic Monitoring, 12-12-1997**]

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

[Devices subject to this condition : D6, D7, D9]

E. Equipment Operation/Construction Requirements

E193.1 The operator shall construct, operate, and maintain this equipment according to the following requirements:

This tank shall be equipped with a continuous recording, non-resettable, ampere-hour meter that operates on the electrical power lines and measures the amount of electrical current applied to the tank or rectifier. A separate meter shall be hard-wired for each rectifier. The meters shall be mounted in a location such that they are easily readable. The operator shall inspect and maintain the ampere-hour meter(s) according to the manufacturer's recommendations.

An identification tag or label shall be affixed to all rectifiers in a permanent and conspicuous position. The identification marker shall be maintained in legible condition and contain the rectifier identification number, maximum rectifier amperage and identification numbers of tanks utilizing the rectifier.

Record the actual cumulative rectifier usage of this anodizing tank used during each calendar month of the reporting period, and the total capacity used to date for each calendar year.

A log concerning the operation of this equipment shall be kept on file for a minimum of 5 years. The past 2 years' records shall be kept on site & shall be made available to any District representative upon request. This log shall contain: A) The records required by the conditions in this permit B) At least once per month, the total ampere-hours applied to this tank & the cumulative total of amp-hours applied to this tank to date for the current calendar year

The operator shall maintain records of any exceedances of the parameter limits contained in this permit. The records shall include the date of the occurrence, the duration, cause (if known), and, where possible, the magnitude of any exceedance.

[**RULE 1303(a)(1)-BACT, 5-10-1996;** RULE 1303(a)(1)-BACT, 12-6-2002; RULE 1401, 5-3-2002]

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

[Devices subject to this condition : D17, D23]

E193.3 The operator shall operate and maintain this equipment according to the following requirements:

Each tank shall be clearly identified with the appropriate tank numbers as designated in the Section D equipment description. The identification and/or labeling of each tank shall be directly affixed to each tank and be easily readable.

An ongoing compliance status report for the preceding calendar year shall be completed annually, by February 1 of each year. The report shall contain the information identified in Appendix 3 of Rule 1469. The report shall be made available to AQMD personnel upon request.

Material safety data sheets (MSDS) for all materials charged to each process tank at this facility shall be kept on site and made available to any District representative upon request.

[**RULE 1469, 10-9-1998**]

[Devices subject to this condition : D17, D23]

E193.4 The operator shall operate and maintain this equipment according to the following requirements:

(1) The water sealed cover shall remain closed at all times, except when loading and unloading parts.

(2) The operator shall inspect all membrane filters on a weekly basis to ensure that there is no chromic acid buildup and no evidence of chemical attack that affects the structural integrity of the membranes.

(3) The operator shall not conduct any mechanical agitation, solution sparging, or air sparging in this equipment.

[RULE 1469, 12-5-2008]

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

[Devices subject to this condition : D17, D23]

E448.2 The operator shall comply with the following requirements:

The visible emission standards of AQMD Rule 401.

Report breakdowns as required by District Rule 430, and maintain records of the occurrence, duration, and causes (if known) and action taken on each breakdown.

[RULE 1469, 12-5-2008]

[Devices subject to this condition : D17, D23]

H. Applicable Rules

H23.6 This equipment is subject to the applicable requirements of the following rules or regulations:

Contaminant	Rule	CR
Chromium, Hexavalent	District Rule	1469

[RULE 1469, 12-5-2008]

[Devices subject to this condition : D17, D23]

H23.7 This equipment is subject to the applicable requirements of the following rules or regulations:

Contaminant	Rule	Rule/Subpart
NOX	District Rule	1147

[RULE 1147, 12-5-2008]

[Devices subject to this condition : D6, D7, D9]

FACILITY PERMIT TO OPERATE
TRIUMPH PROCESSING, INC.

SECTION H: PERMIT TO CONSTRUCT AND TEMPORARY PERMIT TO OPERATE

The operator shall comply with the terms and conditions set forth below:

K. Record Keeping/Reporting

K48.1 The operator shall maintain records in a manner approved by the District, to demonstrate compliance with the following condition number(s):

Condition Number K 193- 1

Condition Number K 193- 3

Condition Number K 448- 2

[RULE 1469, 12-5-2008]

[Devices subject to this condition : D17, D23]