

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY REGION 8

1595 Wynkoop Street
DENVER, CO 80202-1129
Phone 800-227-8917
http://www.epa.gov/region08

2009 OCT -7 PM 2: 20

DCT 7 2009

EPA REGION VIII HEARING CLERK

Ref: 8ENF-W

CERTIFIED MAIL LETTER RETURN RECEIPT REQUESTED

James Shepherd, President Sylvan Bay Homeowners Association 238 Venenzio Lane Centerville, UT 84014

Re: Administrative Order Addendum

Docket No. SDWA-08-2009-0037 Sylvan Bay Homeowners Association

PWS ID #WY5601111

Dear Mr. Shepherd:

Pursuant to paragraph 13 of the Administrative Order (AO) issued March 9, 2009 to the Sylvan Bay Homeowners Association, this Addendum to the AO incorporates the schedule for completing system modifications as outlined in the July 29, 2009 email and September 22, 2009 phone call received from Kirk Shepherd on behalf of the Sylvan Bay Homeowners Association to EPA. This letter constitutes the written approval by EPA of that schedule as indicated in the chart below. EPA recognizes that some of the actions have already been completed. Please be advised that Sylvan Bay Homeowners Association must continue to meet the total coliform rule maximum contaminant level (MCI.) requirements and notify EPA within 10 days after all actions required by the plan have been completed as required in paragraph 14 of the AO.

Action	<u>Deadline</u>	Completion
In the short term, disinfect with dissolving chlorinator tablets in a mesh bag near the discharge of both 3,000 gallon tanks.		September 12, 2009
After installation of the chlorine tablets, test for chlorine residual at strategic locations to ensure a detectible residual throughout the system.		September 12, 13, 19, and 20, 2009 and weekly thereafter until system closes for the 2009 season.
Install flow meter.	Within 30 days of opening for the 2010 season.	
Install an Accu-Tab Chlorinator System (or similar system) in the discharge line immediately downstream of the two 3,000 gallon tanks.	Within 30 days of opening for the 2010 season.	

Action	<u>Deadline</u>	Completion
Test for chlorine residual at 3 different locations in the distribution system to ensure a detectable residual (1ppm +/25ppm) throughout the system.	Within 1 week of chlorinator installation and weekly thereafter.	4 weeks of monitoring
Submit chlorine residual results to EPA.	10 days after completing 4 weeks of sampling.	·

Please be advised that the Sylvan Bay Homeowners Association is required to comply with all provisions of the AO. Penalties for failing to comply are set forth in the Order. Please contact Shawn McCaffrey at (303) 312-6515 if you have any questions concerning this Addendum. If you are represented by an attorney, please ask your attorney to call Peggy Livingston at the above 800 number, extension 6858, or at (303) 312-6858.

Sincerely,

Darcy O'Connor, Acting Director Technical Enforcement Program Office of Compliance, Enforcement, and Environmental Justice

David Rochlin, Supervisory Attorney Legal Enforcement Program Office of Enforcement, Compliance and Environmental Justice

David Poell

cc: Tina Artemis, EPA Regional Hearing Clerk
Kirk Shepherd, Operator
Craig Turlock, District Ranger, Pinedale Ranger District
WY DEQ (via email)
WY DOH (via email)