

**EPA Superfund
Record of Decision:**

**FORT ORD
EPA ID: CA7210020676
OU 08
MARINA, CA
07/02/2002**

**Final
Record of Decision
No Action Regarding
Ordnance-Related Investigation
Former Fort Ord, California**

June 19, 2002

United States Department of the Army
HQ, U.S. Army Garrison (Fort Ord)
Fort Ord, California 93941

CONTENTS

1.0	DECLARATION	1
	1.1 Basis and Purpose	1
	1.2 Site Assessment.....	2
	1.3 Description of the Remedy.....	2
	1.4 Statutory Determination.....	2
2.0	DECISION SUMMARY.....	6
	2.1 Site Description.....	6
	2.2 Site History.....	6
	2.3 Enforcement and Regulatory History.....	6
	2.4 Highlights of Community Participation.....	7
	2.5 Scope and Role of No Action.....	7
	2.6 Track 0 Process	7
	2.6.1 Track 0 ROD Process.....	7
	2.6.2 Track 0 “Plug-In” Process.....	8
	2.7 Site Characteristics.....	8
	2.7.1 Definition of Track 0 Areas	8
	2.7.2 Track 0 Area Boundaries	9
	2.7.3 Track 0 “Plug-In” Areas.....	9
	2.7.4 Redefinition of Parcel Boundaries	9
	2.7.5 Definition of Non-Firing Areas.....	10
	2.8 Description of Track 0 Areas	10
	2.8.1 Parcels S4.1.2.1, S4.1.2.2, S4.1.3, S4.1.4, and S4.1.5 – Highway 1 Area	10
	2.8.1.1 Background.....	10
	2.8.1.2 Site Investigation	10
	2.8.1.3 Rationale	11
	2.8.2 Parcel F2.7.2 – Golf Course Maintenance Area.....	11
	2.8.2.1 Background.....	11
	2.8.2.2 Site Investigation	11
	2.8.2.3 Rationale	12
	2.8.3 Parcel L27 – Brostrom Park Area	12
	2.8.3.1 Background.....	12
	2.8.3.2 Site Investigation	12
	2.8.3.3 Rationale	12
	2.8.4 Parcels E2c.1, E4.1.1, E4.2, E4.5, E5a, and a portion of E4.3.1.1 – Patton/Abrams Park Housing Area	13
	2.8.4.1 Background.....	13
	2.8.4.2 Site Investigation	13
	2.8.4.3 Rationale	15
	2.8.5 Parcels E15.1, L33.1, L33.2 and S1.4 – Open Space, Main Entrance Area.....	15
	2.8.5.1 Background.....	15
	2.8.5.2 Site Investigation	16
	2.8.5.3 Rationale	17
	2.8.6 Parcels L1.1, L19.2, L19.3, L19.4, L32.2.1, L32.2.2, L32.3, L32.4.1.1, L32.4.1.2, L32.4.2, L23.6, L36, L37, L15.1, L7.8, L7.9, L2.4.2, L2.4.3.1, L2.4.3.2, S1.3.1 – Surplus II Area.....	17

2.8.6.1	Background.....	17
2.8.6.2	Site Investigation	17
2.8.6.3	Rationale	18
2.8.7	Parcels S2.1.3, S2.1.4.1, S2.1.4.2, L5.1.2, L5.1.3, L5.1.4, L5.1.5, L5.1.6, L5.1.7, L5.1.8, L5.1.9, L5.1.10, L5.2, L5.3, F7.1, F7.2 – Fritzsche Army Airfield Area	19
2.8.7.1	Background.....	19
2.8.7.2	Site Investigation	19
2.8.7.3	Rationale	20
2.8.8	Parcels E11b.1, E11b.2, E11b.3, E11b.4, L20.14.1.2, L20.19.2, L20.20, L20.21.1, L20.21.2, L20.22, L23.3.1, L23.3.2.1, L35.3, L35.6, L35.7, and L35.8 – East Garrison Area.....	21
2.8.8.1	Background.....	21
2.8.8.2	Site Investigation	21
2.8.8.3	Rationale	22
2.8.9	Parcels E2b.1.1.1, E2b.1.2, E2b.1.1.2, E2b.1.3, E2b.1.4, E2b.1.5, E2b.2.1, E2b.2.2, E2b.2.3, E2b.2.4, E2b.2.5, E2b.3.1.1, E2b.3.2, E2c.2, E2c.3.1, E2c.3.2, E2c.3.3, E2c.4.1.1, E2c.4.2.1, E2d.1, E2d.2, E17, L2.1, L12.2.2, L12.2.3, L12.3, L23.1.1, L23.1.2, L23.1.3, L23.1.4, L23.1.5, L35.1, L35.2, L20.16.1, L20.16.2, L20.16.3, S1.5.1.1, S1.5.1.2, S1.5.2, L23.4, L2.2.1, L5.8.1, L5.8.2, L20.17.1 – Main Garrison Area	22
2.8.9.1	Background.....	22
2.8.9.2	Site Investigation	22
2.8.9.3	Rationale	23
2.8.10	Parcels E2e.1, E2e.2, E8a.1.2, E8a.1.3, E8a.1.4, E8a.1.5, S1.3.3, S2.5.1.1, S2.5.1.2, and Portions of Parcels S2.5.2.1 and S2.5.2.2 – OU 2 Landfill Area	24
2.8.10.1	Background.....	24
2.8.10.2	Site Investigation	24
2.8.10.3	Rationale	25
2.8.11	Parcels L5.10, L20.10.1.1, L20.10.1.2, L20.10.2, and L20.10.3 – Reservation Road Area	25
2.8.11.1	Background.....	25
2.8.11.2	Investigation Summary	26
2.8.11.3	Rationale	26
2.9	Documentation of Significant Changes.....	26
2.10	Summary of Site Risks	27
3.0	RESPONSIVENESS SUMMARY	28
3.1	Overview	28
3.2	Background on Community Involvement	28
3.3	Summary of Comments Received During the Public Comment Period and Department of the Army Responses.....	28
3.4	Summary of Comments.....	36
4.0	REFERENCES.....	38

TABLE

1 Track 0 Parcel Groupings

FIGURE

- 1 Track 0 ROD Process and Track 0 Plug-in Process

PLATES

- 1 Location Map – Former Fort Ord
- 2 Track 0 Parcel Map
- 3 Highway 1 Parcels
- 4 Brostrom Park and Golf Course Parcels
- 5 Patton/Abrams Park Housing Area Parcels
- 6 Open Space – Main Entrance Parcels
- 7 Surplus II Parcels
- 8 Fritzsche Army Airfield Parcels
- 9 East Garrison Parcels
- 10 Main Garrison Parcels
- 11 OU2 Landfill Parcels
- 12 Reservation Road Parcels

APPENDIX

- A Track 0 Checklist

TRACK 0 ROD

1.0 DECLARATION

The former Fort Ord is located near Monterey Bay in northwestern Monterey County, California (Plate 1). Since 1917, portions of the former Fort Ord were used by cavalry, field artillery, and infantry units for maneuvers, target ranges, and other purposes. Ordnance and explosives (OE) were fired into, fired upon, or used on the facility in the form of artillery and mortar projectiles, rockets and guided missiles, rifle and hand grenades, land mines, pyrotechnics, bombs, and demolition materials. Both unexploded ordnance (UXO) and OE scrap are present at parts of the former Fort Ord.

This No Action Record of Decision (ROD) addresses areas at the former Fort Ord that contain no evidence of OE and have never been suspected as having been used for OE-related activities of any kind based on current knowledge outlined in the Literature Review (*HLA, 2000a*) and investigated under the basewide Ordnance and Explosives Remedial Investigation/Feasibility Study (OE RI/FS) Program at former Fort Ord. The Track 0 process addresses single or grouped areas of land at the former Fort Ord that have no history of OE-related use and for which No Action is necessary to protect human health and the environment as described in the Track 0 Technical Memorandum (*HLA, 2000b*). A Special Case Track 0 area is also considered for No Action in this ROD. The Special Case area includes a former landfill where OE scrap items were found buried with refuse. No OE-related activities occurred in the area and the OE scrap items and the refuse were entirely removed.

The Track 0 Technical Memorandum provided the area- or parcel-specific rationale for assigning areas to Track 0 and served as the basis for the Track 0 Proposed Plan (*HLA, 2000c*). In response to agency and public comments received on the Proposed Plan, the process by which Track 0 parcels are identified was clarified and the information contained in the Technical Memorandum was expanded and

included in this ROD. These areas consist largely of land that has been developed for military support or residential use throughout Fort Ord's history and areas that have no physical or documented evidence of OE-related training. The No Action determination for these areas is documented through this Track 0 ROD that was prepared subsequent to the Technical Memorandum.

This ROD describes the Track 0 Process for Fort Ord and identifies the "Plug-In" process for identifying and managing the documentation process for future Track 0 (No Action) areas identified during the OE RI/FS. This ROD also identifies the areas to date that have been categorized as Track 0 areas and summarizes the background, site investigation history, and rationale for assigning each area to Track 0.

1.1 Basis and Purpose

This ROD is the decision document that presents the rationale for the selected No Action determination for the Track 0 Areas identified in the Literature Review performed as part of the basewide OE RI/FS Program at the former Fort Ord. No Action was selected for the Track 0 Areas in accordance with the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), as amended by the Superfund Amendment and Reauthorization Act (SARA), and the National Oil and Hazardous Substances Pollution Contingency Plan (NCP). This decision is based on information and reports contained in the Administrative Record for the former Fort Ord.

The United States Environmental Protection Agency (EPA) and the Department of Toxic Substances Control (DTSC), a part of the California Environmental Protection Agency (Cal/EPA), concur with the Army's No Action determination and the "Plug-In" process identified herein.

This decision is undertaken pursuant to the President's authority under CERCLA section 104, as delegated to the Army in accordance with Executive order 12580, and in compliance with the process set out in CERCLA section 120.

1.2 Site Assessment

No current or potential risks to human health and the environment posed by OE are present based on current knowledge outlined in the Literature Review (*HLA, 2000a*) performed as part of the basewide OE RI/FS Program and information obtained from other investigations at the former Fort Ord. The Track 0 process addresses single or grouped areas of land at the former Fort Ord that have no history of OE-related use and for which No Action is necessary to protect human health and the environment.

1.3 Description of the Remedy

Because there are no current or potential risks to human health and the environment posed by OE

at Track 0 areas, no remedial action is necessary in those areas. In the future, should any ordnance-related item be found within any of the areas addressed in this ROD, the Army will take an appropriate immediate action (i.e., removing the found item, recording the incident), and within 90 days of the discovery, submit a plan for appropriate follow-on action to EPA and DTSC for consultation, pursuant to Section 7.7(b) of the Fort Ord Federal Facility Agreement (FFA).

1.4 Statutory Determination

No remedial action is necessary to ensure the protection of human health and the environment.

**RECORD OF DECISION
NO ACTION REGARDING ORDNANCE-RELATED INVESTIGATION
FORMER FORT ORD, CALIFORNIA**


Signature Sheet for the foregoing Record of Decision for no action regarding ordnance-related investigation Former Fort Ord, California among the United States Army, the United States Environmental Protection Agency and the California Environmental Protection Agency Department of Toxic Substances Control



Kevin M. Rice
Colonel U.S. Army
Commander

24 June, 2002

Date



Sally Y. Webb
DRAC Environmental Coordinator
President of Monterey

20 June, 2002

Date

**RECORD OF DECISION
NO ACTION REGARDING ORDNANCE-RELATED INVESTIGATION
FORMER FORT ORD, CALIFORNIA**

Signature Sheet for the foregoing Record of Decision for no action regarding ordnance-related investigation, Former Fort Ord, California, among the United States Army, the United States Environmental Protection Agency, and the California Environmental Protection Agency, Department of Toxic Substances Control


Deborah Jordan
Chief, Federal Facilities and Site Cleanup Branch
U.S. Environmental Protection Agency
Region IX


Date

**RECORD OF DECISION
NO ACTION REGARDING ORDNANCE-RELATED INVESTIGATION
FORMER FORT ORD, CALIFORNIA**

Signature Sheet for the foregoing Record of Decision for no action regarding ordnance-related investigation, Former Fort Ord, California, among the United States Army, the United States Environmental Protection Agency, and the California Environmental Protection Agency, Department of Toxic Substances Control

Signature _____
Anthony J. Landis, P.E.
Chief of Operations
Office of Military Facilities
California Environmental Protection Agency
Department of Toxic Substances Control

Date _____

2.0 DECISION SUMMARY

2.1 Site Description

The Former Fort Ord is located near Monterey Bay in northwestern Monterey County, California, approximately 80 miles south of San Francisco. The base comprises approximately 28,000 acres adjacent to the cities of Seaside, Sand City, Monterey, and Del Rey Oaks to the south and Marina to the north. The Southern Pacific Railroad and Highway 1 pass through the western portion of former Fort Ord, separating the beachfront from the rest of the base. Laguna Seca Recreation Area and Toro Regional Park border former Fort Ord to the south and southeast, respectively, as well as several small communities such as Toro Park Estates and San Benancio.

2.2 Site History

Since the base was selected in 1991 for base realignment and closure (BRAC) and was officially closed in September 1994, site visits, historic and archival investigations, OE sampling, and removal actions have been performed and documented in preparation for transfer and reuse of former Fort Ord property. The Ord Military Community, located within the Main Garrison portion of former Fort Ord, will be retained by the Army. Since base closure in September 1994, lands outside the Ord Military Community have been subjected to the reuse process. Some of the property on the installation has been transferred. A large portion of the Inland Training Ranges was assigned to the Bureau of Land Management (BLM). Other areas on the installation have been or will be transferred to federal, state, local, and private entities through economic development conveyance, public benefit conveyance, negotiated sale, or other means.

2.3 Enforcement and Regulatory History

The reuse of the former Fort Ord following transfer of property increases the possibility of

the public being exposed to explosive hazards. In November 1998, the Army agreed to evaluate OE at former Fort Ord in an OE RI/FS consistent with the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA). A Federal Facility Agreement (FFA) was signed in 1990 by the Army, EPA, and the California Environmental Protection Agency's Department of Toxic Substances control (DTSC; formerly the Department of Health Services or DHS). The FFA established schedules for performing remedial investigations and feasibility studies and requires that remedial actions be completed as expeditiously as possible. In April 2000, an agreement was signed between the Army, EPA and DTSC to evaluate OE at the former Fort Ord subject to the provisions of the Fort Ord FFA.

The Army is preparing the OE RI/FS for Fort Ord to address OE-related hazards, which will include input from the community and require regulatory agency review and approval. The OE RI/FS will review and evaluate past investigative and removal actions, as well as recommend future response actions deemed necessary to protect human health and the environment on the basis of proposed reuses specified in the Fort Ord Reuse Authority (FORA) Reuse Plan.

Information will be gathered and evaluated during the OE RI/FS to categorize all areas of the former Fort Ord according to actions that have been taken or future remedial actions that are identified as necessary to mitigate explosive safety hazards associated with OE. The information will be evaluated with regard to site knowledge, the quality of the available information, work completed, and intended future land uses.

The OE RI/FS for the former Fort Ord will consider all property at the base in terms of past OE-related use and potential future explosive safety hazards as described in the OE RI/FS Work Plan (*USACE, 1999*). The OE RI/FS is organized as a "tracking" process whereby sites

with similar characteristics will be grouped to expedite cleanup, reuse, and/or transfer based on current knowledge.

This No Action ROD addresses areas on the former Fort Ord that have been identified as requiring no OE-related action to protect human health (public safety) and the environment, and are herein referred to as Track 0 areas. Other Track (1 through 3) areas will be addressed separately for the other lands that have or are suspected to have a history of OE-related use. An area is assigned to a specific track according to the level of OE investigation, sampling, or removal conducted to date as described in the OE RI/FS Work Plan (*USACE, 1999*).

OE RI/FS documents have been and will be prepared in cooperation with the regulatory agencies and will be reviewed and approved by the U.S. Environmental Protection Agency (EPA) and California Environmental Protection Agency Department of Toxic Substances Control (Cal/EPA DTSC). The documents also will be available for public review and comment.

2.4 Highlights of Community Participation

In February, 2000 the Army presented the Track 0 Proposed Plan for former Fort Ord to the public for review and comment (*HLA, 2000c*). The Proposed Plan presented the preferred alternative of No Action for each area and summarized information in the Technical Memorandum and other documents in the Administrative Record. These documents are available to the public at the following locations:

- Chamberlin Library, Building 4275, General Jim Moore Boulevard, Ord Military Community (formerly Fort Ord), California
- Seaside Branch Library, 550 Harcourt Street, Seaside, California
- California State University, Monterey Bay, Library Learning Center, 100 Campus Center, Building 12, Seaside, California.

The Administrative Record is available at Building 4463, Gigling Road, Ord Military Community (formerly Fort Ord), California, Monday through Friday from 9:00 a.m. to 3:00 p.m.

Comments on the Proposed Plan were accepted during a 30-day public review-and-comment period beginning on February 4, 2000. At the request of the public the comment period was extended from 30 days to 60 days, ending on April 4, 2000. A public meeting was held on February 16, 2000, at Building 4280 (Post Chapel), General Jim Moore Boulevard, Ord Military Community, California. At that time, the public had the opportunity to ask the Army and regulatory agencies questions and express concerns about the plan. In addition, written comments were accepted during the public comment period. Responses to comments received during the public comment period are included in the Responsiveness Summary presented in Section 3 of this document. Any significant changes to the Proposed Plan are included in Section 2.

2.5 Scope and Role of No Action

This No Action ROD documents that, with respect to OE, any necessary remedial actions consistent with CERCLA have been taken or that remedial action is not necessary for the areas that meet the Track 0 status as defined in Section 2.7. The scope of the No Action process is to identify areas where remedial action, with respect to OE, is not necessary to protect human health and the environment.

2.6 Track 0 Process

This section summarizes the documentation and management procedures for No Action areas identified in Section 2.8 of this ROD (Track 0 ROD process) and for subsequently identified No Action areas (Track 0 "Plug-In" process).

2.6.1 Track 0 ROD Process

Subsequent to the Technical Memorandum, the Track 0 Proposed Plan proposed No Action for

the Track 0 areas as described in the following section (Figure 1). Consistent with the requirements of CERCLA, notification of the proposed decision was published in a major local newspaper and distributed for public review. A 30-day public comment period, extended to 60 days, was provided and a public meeting held. This Track 0 ROD selecting the action, has been prepared by the Army for review and approval by the EPA and DTSC. The ROD identifies specific areas described in Section 2.8, currently meeting the No Action requirements.

2.6.2 Track 0 "Plug-In" Process

The Proposed Plan also proposed the "Plug-In" process for other areas that may be identified in the future for Track 0 (Figure 1). After the ROD is signed, No Action decisions for these future Track 0 areas will be proposed and documented in Approval Memoranda that describe the rationale for Track 0 designation.

The Approval Memorandum for each future Track 0 parcel or group of parcels will include the following:

1. A description of the area
2. A description of the historical use of the area
3. A rationale for the designation of an area as Track 0
4. A checklist summarizing the key elements of Track 0 documentation (see Figure 1 and Appendix A for an example checklist)
5. A map of the area detailing location and any pertinent available OE-related information.

Each Approval Memorandum will be made available for a 30-day public review period. Subsequently, when the Approval Memorandum is approved by regulatory agencies, a public notice will be posted in a local newspaper. Completed and planned No Action site determinations will also be described in the newsletter, the *Advance*, prepared by the Army

for local residents. When approved by the regulatory agencies, an Approval Memorandum for a specific Track 0 area will become the decision document for that area.

The Proposed Plans and RODs for Track 0 and other tracks, and all Approval Memoranda will be placed in the former Fort Ord Administrative Record and the local information repositories.

2.7 Site Characteristics

This section summarizes the Track 0 areas, how they are categorized, and what qualifies them for inclusion in the Track 0 process.

2.7.1 Definition of Track 0 Areas

Track 0 areas at the former Fort Ord are those that contain no evidence of OE and are not suspected as having been used for OE-related activities of any kind. These areas consist largely of land that has been developed for military support or residential use throughout Fort Ord's history and areas that have no physical or documented evidence of OE-related training. The locations of the Track 0 areas described in the Technical Memorandum are listed in Table 1 and shown on Plate 2. All Track 0 areas identified herein will be eliminated from further investigation under the OE RI/FS, on the basis of this ROD.

The decision for entering areas into the Track 0 process was based on the results of the literature review, documents referenced therein, and information obtained from site-specific activities and other activities where available. The main sources of information relied upon in evaluating an area's eligibility for Track 0 status included the following:

- The Literature Review Report (*HLA, 2000a*)
- The Revised Archives Search Report (ASR) (*USAEDH, 1997b*)
- The Community Environmental Response Facilitation Act (CERFA) Report (*Little, 1994*)

- The Basewide Remedial Investigation/Feasibility Study (Basewide RI/FS) (*HLA, 1995d*).

The literature review process included gathering and reviewing files from multiple sources. Previous investigations at the former Fort Ord that documented OE-related activities were reviewed along with historical records. Historical records reviewed included range control files, historical maps, aerial photographs, historical film footage, real estate records, and newspaper articles. Interviews were conducted with retired military personnel, active Corps of Engineers employees, active enlisted and civilian personnel that served at the former Fort Ord, and OE contractors. Other factors considered included physical location of an area, development history, and the results of the remedial investigation and excavation activities at Installation Restoration Program (IRP) sites.

The Archives Search investigation involved extensive records search of the former Fort Ord related ordnance documentation and a visual inspection of ordnance sites identified. Records reviewed included aerial photographs, National Archives records, local government and historical records, and Fort Ord fire department records. The Archives Search also included interviews with current and former employees.

The CERFA investigation included a search of government records, a review of recorded chain of title documents, a review of aerial photographs reflecting prior uses, a visual inspection of the former Fort Ord, physical inspection of and review of information for adjacent properties and interviews with current or former employees.

The Basewide RI/FS included a review of previous investigations at the former Fort Ord and extensive field investigation activities at several of the Track 0 areas. RI/FS documentation was reviewed and utilized in the delineation of the Track 0 areas. A checklist was developed to highlight the main sources of information used in evaluating each of the areas for Track 0 status as shown in Appendix A.

2.7.2 Track 0 Area Boundaries

Because of the base's large size, long history, multiple uses, and myriad of programs under which records have been kept, one of the main goals of the OE RI/FS process has been to assemble information from numerous sources regarding land use. Hundreds of records, maps, and aerial photographs spanning approximately 80 years were consulted regarding the multiple uses of the former Fort Ord lands. From these sources, Track 0 areas were given their current boundaries.

2.7.3 Track 0 "Plug-In" Areas

Other areas or groups of areas may be identified in the future as being eligible for Track 0, after further research has been completed and OE site boundary locations have been clarified in the OE RI/FS. The area(s) will be proposed for Track 0 through a "Plug-In" process by which an Approval Memorandum will be prepared that presents rationale for designating the area(s) as Track 0. When approved by the regulatory agencies, the Approval Memorandum will become the decision document for the specific area(s). Section 2.6 summarizes the documentation and management procedures to be followed during the "Plug-In" process.

Track 0 areas and their boundaries may be redefined under several different scenarios in the future and thereby qualify for inclusion in the "Plug-In" process. Two of these scenarios, Redefinition of Transfer Parcel Boundaries and Definition of Non-Firing Areas, are discussed in the following sections.

2.7.4 Redefinition of Parcel Boundaries

The OE RI/FS process may identify the need for further site reconnaissance in some areas of the former Fort Ord where current data are not adequate for a complete evaluation of explosive safety hazards associated with OE. On the basis of results of future OE-related information that

may be collected, parcels can be subdivided to isolate non-OE areas.

2.7.5 Definition of Non-Firing Areas

The Track 0 process was defined for areas at the former Fort Ord where no OE-related activities were known or suspected to have occurred. The term "OE-related activities" was given an intentionally broad definition to take a conservative approach in evaluating all available information and considering which areas at former Fort Ord may have possibly been used for any military activities where OE could have been used. Some of these areas include non-firing training areas where Army personnel were given preliminary training in the use of weapons, but the weapons were never fired.

These areas will be researched thoroughly in the OE RI/FS for information relating to the occurrence of live fire activities. If site conditions clearly indicate no live fire was conducted at a given area (e.g., buildings are nearby; range fans necessary for safely conducting live fire practice are absent), these areas will be eligible for the Track 0 plug-in process.

2.8 Description of Track 0 Areas

This section provides the background, investigative summaries, and rationale for designation of each area as a Track 0 (No Action) area. Areas were grouped geographically: e.g., all non-OE land in the Main Garrison was grouped and discussed together as one area. The Army subdivided former Fort Ord into parcels of land for the purposes of property transfer. The parcels were assigned numbers for identification. To supplement future property transfer, descriptions of the Track 0 areas include discussions of the parcels that occupy the same geographical areas. A checklist was developed to highlight the main sources of information used in evaluating each of the areas for Track 0 status as shown in Appendix A.

2.8.1 Parcels S4.1.2.1, S4.1.2.2, S4.1.3, S4.1.4, and S4.1.5 – Highway 1 Area

2.8.1.1 Background

These parcels consist of Highway 1 and the associated Highway 1 easements from the northern to southern former Fort Ord boundary. The combined parcel area is approximately 161 acres (Plate 3). Highway 1 and the adjacent rail line have been in roughly the same position since the Army began acquisition of adjacent land in 1917. The land upon which these parcels now lie was purchased by the Army in 1940. Significant construction occurred to the highway with the purchase of the property and included an expansion to 4 lanes and the re-location of the adjacent rail line.

2.8.1.2 Site Investigation

Based on the results of the Archives Search investigation, the Literature Review, the Site 39 Data Summary and Work Plan, the CERFA investigation and information obtained from other activities no OE sites were identified on the parcels. Two potential sites (Sites OE-20 and OE-22) lie immediately adjacent to the Track 0 parcels (Plate 3). Site OE-20 (a recoilless rifle training area), was identified through the archives search. The boundary of the OE site is based on the delineation of the training area on a the former Fort Ord training facilities map from 1957. An OE contractor conducted sampling of the site and no evidence of OE was found (*HFAI, 1994*). Site OE-20 will undergo additional evaluation in the OE RI/FS.

Site OE-22, the Beach Ranges, were small arms ranges located along the former Fort Ord beachfront. Firing at the ranges was toward the west away from the Track 0 parcels. Sampling of Site OE-22 was preformed in 1993-1994. Numerous live small arms and several OE scrap items (fins from a 60mm mortar, an inert training grenade, expended smoke grenade and grenade fuze and a 40mm cartridge case) were found (*HFAI, 1994*). Additional sampling

(Gridstats/Sitestats) was completed in 1997 and one scrap item (unfuzed Japanese-made mortar) was found (*USA, 1999d*). No UXO was found during either sampling effort. Site OE-22 will undergo additional evaluation in the OE RI/FS.

One former training area, a machine gun square, overlaps a portion of Parcel S4.1.2.1 near the former Fort Ord main entrance. No evidence has been found that would support the use of OE at the machine gun squares (*HLA, 2000*). The machine gun squares were located within developed areas of former Fort Ord, adjacent to main roads, military housing, and other military facilities.

2.8.1.3 Rationale

OE is not likely to be present on these parcels for the following reasons:

- Highway 1 and the rail line have been in the same general location since the property was obtained by the Army
- A review of the former Fort Ord ordnance related investigations including the Archives Search Report (ASR), the Literature Review, the Site 39 Data Summary and Work Plan, the HFAI OEW Sampling OEW Removal Action Final Report for Site OE-20, and the Site OE-20 After Action Report, indicates the parcels were not used for ordnance training
- OE sampling at Site OE-20 found no evidence of OE
- Expansion of Highway 1 to four lanes involved significant grading and earth movement, and no record of OE exists
- OE sampling at Site OE-22 identified only OE scrap items.

2.8.2 Parcel F2.7.2 – Golf Course Maintenance Area

2.8.2.1 Background

This parcel consists of approximately 2 acres in the maintenance area of the former Fort Ord golf courses (Plate 4). The property includes two buildings (4110 and 4109) used for general maintenance and storage to support the golf course. The Army purchased the property in 1940, housing was constructed nearby in 1941 and 1942, and the golf course was constructed in 1953. Prior to construction of the golf course the parcel lay on undeveloped land.

2.8.2.2 Site Investigation

No evidence of ordnance use was identified on this parcel during the Archive Search, the Literature Review, the Site 39 Data Summary and Work Plan and the CERFA investigation.

In 1993 the parcel was included in a remedial investigation for pesticides and PCBs related to past activities occurring at the maintenance facility. The investigation included the completion of 8 soil borings to depths of 5 to 10 feet. In 1994 an area within the parcel of approximately 1,870 square feet was excavated to depths ranging from 1 to 41 feet below ground surface (bgs) as part of an underground storage tank (UST) investigation adjacent to Building 4110 (*HLA, 1997d*). Field personnel trained in ordnance recognition supervised the excavation of the former UST site. No evidence of OE was found during the remedial investigation or the UST investigation at this parcel.

Other investigations have involved site walks of the parcel including the Solid Waste Management Unit (SWMU) investigations in 1995 and 1996, and a 1997 site visit supporting the proposed real estate transfer of this parcel in 1997. No evidence of OE was observed during these site visits. Field personnel trained in ordnance recognition performed the site walk for the real estate transfer.

2.8.2.3 Rationale

OE is not likely to be present on this parcel for the following reasons:

- A review of former Fort Ord ordnance related investigations including the ASR, the Literature Review and the Site 39 Data Summary and Work Plan indicates the parcel was not used for ordnance training
- The results of the former Fort Ord CERFA investigation included a site walk, inspection of the buildings on the parcel, and a review of the former Fort Ord related documentation including documents pertaining to ordnance use, and found nothing to indicate the presence of OE
- The property was purchased by the Army in 1940, housing constructed nearby beginning in 1941 and the golf course was built in 1953
- Investigations completed under the Basewide RI/FS and UST programs, which included intrusive activities, found no evidence to indicate the use of ordnance on the parcel
- No evidence of OE use was found during several site walks of the parcel.

2.8.3 Parcel L27 – Brostrom Park Area

2.8.3.1 Background

This parcel, approximately 52 acres, lies in the southwest portion of the former Fort Ord adjacent to the City of Seaside (Plate 4). The parcel currently includes the Brostrom Park housing area. The property was purchased by the Army in 1940. Housing (Ord Village) was constructed on this parcel and on adjacent Army property in 1941 and 1942. The Hayes Park housing area was built immediately north of Parcel L27 in 1952. Based on a review of aerial photographs, Ord village was demolished in the early 1960s and with the exception of the construction of a baseball field in the mid 1960s,

the parcel lay undeveloped until 1984 when the Brostrom Park housing area was constructed. After the demolition of the Ord Village housing area, Seaside High School was constructed on adjacent Army property that had also previously contained a portion of the Ord Village housing area.

2.8.3.2 Site Investigation

No evidence of ordnance use was identified on this parcel during the Archives Search investigation, the Literature Review, the Site 39 Data Summary and Work Plan and the CERFA investigation.

A portion of Parcel L27, IRP Site 37 underwent an investigation related to a reported chemical release, under the Basewide RI/FS program. No evidence of OE was reported during the site investigation activities that included a site walk, soil boring installation and sampling. Additionally, a site walk was performed on Parcel L27 in 1996 in support of the proposed transfer of this parcel. No evidence was found during the site walk that would indicate the use of ordnance on this parcel.

2.8.3.3 Rationale

OE is not likely to be present on this parcel for the following reasons:

- A review of the former Fort Ord ordnance related investigations including the ASR, the Literature Review, and the Site 39 Data Summary and Work Plan indicates that the parcel was not used for ordnance training;
- A housing area, adjacent to the City of Seaside, was constructed on this parcel immediately after purchase of the property by the Army;
- The results of the former Fort Ord CERFA investigation, which included a site walk of the Brostrom Park housing area and a review of Fort Ord related documentation including documents pertaining to ordnance;
- Investigations completed under the former Fort Ord Basewide RI/FS program that

included intrusive activities found no evidence to indicate the use of ordnance on the parcel;

- No evidence of ordnance use was found during several site walks of this parcel.

2.8.4 Parcels E2c.1, E4.1.1, E4.2, E4.5, E5a, and a portion of E4.3.1.1 – Patton/Abrams Park Housing Area

2.8.4.1 Background

These parcels lie in the northwest corner of the former Fort Ord and consist of the Patton Park housing area (Parcels E4.1.1 and E4.2), the Abrams Park housing area (Parcel E4.3.1.1), a water treatment and storage facility (Parcel E4.5), and an adjacent open field (Parcel E5a; Plate 5). These parcels were included in property that was purchased by the Army in 1940. Water supply wells were constructed within Parcel E4.1.1 beginning in 1940. The Patton Park housing area was constructed between 1962 and 1969. The Abrams Park housing area was constructed between 1978 and 1982. A small portion of Parcel E4.3.1.1 was used as sanitary landfill (Area A) from 1956 to 1966 (*HLA, 1990*). The portion of Parcel E4.3.1.1 that was used as a landfill is not included in the Track 0 parcels. The combined parcel area is approximately 460 acres. A review of the former Fort Ord training facilities maps and ordnance related documentation indicates that several non-OE training areas were present within some of the parcels (*HLA, 2000*).

2.8.4.2 Site Investigation

Based on the results of the Archives Search investigation, the Literature Review, the Site 39 Data Summary and Work Plan and the CERFA investigation, three training areas were identified on the parcels. Three potential OE sites, Site OE-1, Site OE-2 and Site OE-13A lie adjacent to Parcels E4.1.1 and E2c.1 and Parcel E4.3.1.1, respectively.

Site OE-13A was identified as a practice mortar range through the Archives Search process. Based on the review of former Fort Ord training facilities maps from the middle to late 1950s, the ASR identified a single point location and a potential area to be investigated. Approximate site boundaries were assigned as part of the ASR and the site was identified as Site OE-13A. In an interview, a former Fort Ord Deputy Director of Logistics (1958 to 1961) stated that the practice mortar range was a non-firing area and no firing of live items would have occurred (*USACE, 2001*).

The boundary of Site OE-13A as identified in the ASR is partially within the current Abrams Park housing area and partially overlies a former landfill (Area A). The earliest housing construction within Abrams Park was completed in 1978 and involved the removal of up to 25 feet of soil and landfill material from various areas (*USACE, 2000*). Construction and grading is evident on 1978 aerial photographs. No evidence of OE was found outside of Area A during construction of Abrams Park (*HLA, 2000*).

As discussed above, Area A was used as a sanitary landfill in the 1960s. Excavation of landfill material within Area A was conducted in 1996 through 1998 as part of the relocation of that portion of the OU 2 landfill. The excavation included the entire limits of Area A, including the overlapping portion of Site OE-13A. During the excavation numerous OE scrap items were found. The items were either removed or destroyed in place (*IT, 1999c*), however no live OE was found. All landfill disposal areas, including land within the OE footprint, have been excavated. The excavated areas have been backfilled and re-graded. Although OE items were found within landfill materials excavated from Area A, the items were related to disposal within these parcels and were not associated with ordnance use at Site OE-13A.

Sampling for OE was conducted at Site OE-13A. An OE contractor completed the initial sampling of the site in 1994 and found no evidence of OE use (*HFAI, 1994*). Based on the

intended future land use of Site OE-13A, the Phase 1 Engineering Evaluation and Cost Analysis (EE/CA) recommended additional confirmatory sampling. In 1997 an OE contractor resurveyed a portion of the 1994 sample grids and the OE site boundary using GPS technology. Two additional confirmatory sample grids were established and sampled. Because twenty grids within the site had already been sampled and the western end of the site (landfill) was being excavated, the two grids were located just outside of the OE site at its eastern end. Two OE scrap items (expended grenade fuze and an expended illuminating signal) were found in one of the two sample grid locations. The two grids were not located in Track 0 areas. As shown on Plate 5, developed land separates Site OE-13A and adjacent Track 0 Parcel E4.3.1.1. Site OE-13A will undergo additional evaluation in the OE RI/FS.

Site OE-1 is located adjacent to Track 0 Parcels E4.1.1 and E2c.1. Site OE-1 was identified as a flame thrower range on Fort Ord training facilities maps from the late 1950s and early 1960s. An OE contractor conducted sampling of Site OE-1 in 1994 and found one inert practice mine (OE scrap) (HFAI, 1994). Eight additional grids were sampled in the area between Site OE-1 and adjacent Site OE-6 and four inert practice mines (OE scrap) were found. In accordance with recommendations in the Phase 1 EE/CA, confirmatory sampling was then conducted. In 1997 the OE contractor resurveyed the Site OE-1 grid locations and the site boundary. In February 1998 three additional grids were sampled and no evidence of OE was found (USA, 1999b). Expanded site boundaries for Site OE-1 were established through the ASR dated 1997, and four additional grids were sampled in open areas within the expanded site. Three OE scrap items, expended practice mine fuzes and an expended flame thrower ignition cartridge, were found. As shown on Plate 5, developed land separates Site OE-1 and adjacent Track 0 Parcels E4.1.1 and E2c.1. Site OE-1 will undergo additional evaluation in the OE RI/FS.

Site OE-2, Pete's Pond is located adjacent to Parcel E4.3.1.1 (Plate 5). Site OE-2 was

identified as a chemical training area and a landmine warfare training area (USAEDH, 1997b). Site OE-2 was sampled for OE in 1994 and two inert OE scrap items were found (HFAI, 1994). Site OE-2 will undergo additional evaluation in the OE RI/FS.

Proficiency Testing Area 2, located within Parcel E4.1.1, was identified on a circa 1954 training facilities map. An interview with a former range control officer indicated that proficiency test areas were used to test a soldier's proficiency in breaking down and setting up weapons. According to the former range control officer, the proficiency test areas were not used for live firing exercises (HLA, 2000). No evidence has been found that supports the use of live ammunition in the proficiency test areas.

A mortar square was located within Parcel E4.1.1. The mortar square was identified on training facilities maps from the 1950s and 1960s. No evidence has been found that would support the use of live ordnance at the mortar squares (HLA, 2000).

The Wire Entanglement Area, a physical training area, was shown on 1945 and 1946 Fort Ord Master Plan maps. The Wire Entanglement Area was located in the northern portion of Parcel E4.2. No further information regarding its use was available.

The three training areas described above were located adjacent to developed areas of former Fort Ord near housing areas and actively used roads. No range fans, typically associated with live fire areas, were shown on the historic maps associated with the three training areas. Additionally, all three training areas are within an area designated on 1945 and 1946 Fort Ord Master Plan Maps as a "Well Area, No Artillery Firing Or Demolitions," and within a "restricted fire area" identified on a 1956 training map.

The Site 39 Data Summary and Work Plan identified an area, 75mm Pack Howitzer Firing Area, which overlaps Track 0 Parcel S4.1.1. The identification of this area is based on the results of an interview with a retired Fort Ord

military engineer (HLA, 1994b). The engineer stated that he had heard that this area was used in the early 1900s by cavalry stationed at the Presidio of Monterey. No evidence to support the use of this area for Howitzer firing was found during the archive search and the literature review. The land was not purchased by the Army until 1940. Two OE Sites (1 and 6) fall within the area delineated as the 75mm Pack Howitzer Firing Area. Field investigations in and around Sites OE-1 and OE-6, which included site walks, a GPS survey of the OE site boundaries and OE sampling, turned up no evidence of 75mm Howitzer use (HFAl, 1994; USACE, 1999).

A suspect training area was identified on a 1949 aerial photo within Parcel E5a (SCS, 1949). None of the previously completed OE historical searches identified a training area in this vicinity at that time. A light vehicle driving course had been established on the eastern side of Parcels E5a by 1961 (USACE, 1961). A site walk of Parcel E5a was completed by a U.S. Army Corps of Engineers (USACE) UXO Safety Specialist and no UXO or OE scrap was found.

2.8.4.3 Rationale

OE is not likely to be present on these parcels for the following reasons:

- A review of former Fort Ord ordnance related investigations including the ASR, the Literature Review, and the Site 39 Data Summary and Work Plan indicates that these parcels were not used for ordnance training
- OE sampling was conducted at Site OE-1 (adjacent) and only OE scrap items were found
- OE sampling at Site OE-13A (adjacent) found no evidence of an impact area
- A former Fort Ord Deputy Director of Logistics stated that Site OE-13A was a non-firing area and no firing of items would have occurred

- Developed land separates the boundaries of Sites OE-1 and OE-13A from nearby Track 0 parcels
- Training areas identified within the parcels were located adjacent to developed areas on former Fort Ord, as well as the nearby City of Marina
- The majority of the area was graded as part of the construction of the housing areas and no evidence of OE was found outside of Area A
- Water supply well construction began within portions of the parcels at the time of initial land purchase in 1940 continuing into the 1950s. Approximately half of the area is located within an area identified on 1945 and 1946 Fort Ord Master Plan maps as a "Well Area, No Artillery Firing Or Demolitions" and the remainder within a "restricted fire area" identified on 1950s training maps
- No UXO or OE scrap was found on Parcel E5a during a site walk completed by a USACE UXO Safety Specialist
- No evidence of OE use was found during the former Fort Ord CERFA investigation, which included a site walk, inspection of the buildings on the parcels, and a review of the former Fort Ord related documentation (including documents pertaining to ordnance use).

2.8.5 Parcels E15.1, L33.1, L33.2 and S1.4 – Open Space, Main Entrance Area

2.8.5.1 Background

These parcels lie in the west-central portion of the former Fort Ord near the former main entrance. The parcels include open space and developed areas that were formerly used as an airstrip, parade grounds, physical training and weapons training areas, and the post engineering facility. The combined parcel acreage is

approximately 201 acres (Plate 6). Initial development on these parcels began at the time of property purchase in 1940 and included the construction of a review field (South Parade Ground) on Parcels L33.1 and L33.2 (*Army, 1940a*). A portion of the South Parade Ground was converted to an airstrip in the late 1940s. Development also included the post engineering facility (Directorate of Engineering and Housing), a motor pool, and maintenance and support buildings (Parcels L33.1 and S1.4) in 1941-43. An athletic stadium was constructed immediately north of the South Parade Grounds in 1951 (*FASI, 1951*).

All four parcels lie within an area designated as a "Well Area, No Artillery Firing Or Demolitions" as shown on the 1945 Fort Ord Training Facilities map (*Army, 1945*). Parcel E15.1 also lies within a "restricted fire area" identified on a 1956 training map. Development continued during the 1960s through the 1980s with the construction of a bank, bowling alley, athletic fields, a running track, and the current main entrance and road. Areas used for weapons training included rifle instruction circles and machine gun squares established in Parcels E15.1 and S1.4.

2.8.5.2 Site Investigation

In 1993, a 100-pound concrete-filled, unfuzed training bomb was found at Site OE-18 approximately 4,000 feet to the east of Parcel S1.4. The training device was found in an area that was used previously for emergency and EOD training (*HLA, 1994b*). Fourteen sample grids were established in and around Parcels S1.4, L33.1, and E15.1 in 1994 to investigate the potential presence of additional bombs related to the former airfield on Parcel L33.1 and L32.2. Nine of the 14 sample grids were located within Track 0 parcels (Plate 6). The grids were sampled, and no evidence of OE was found (*HFAI, 1994*).

Extensive field work including site walks, soil boring investigations, geophysical surveying, trenching and soil excavations at IRP Sites 20, 23, and 24 have taken place within portions of the parcels. These areas were investigated for

the presence of chemical contamination under the Basewide RI/FS program. Trenching activities completed to investigate geophysical anomalies identified through the site characterization of IRP Site 20 were completed within Parcel E15.1 (*HLA, 1995a*). The trenches were excavated by UXO specialists. No evidence of OE was found during this investigation.

The IRP Site 23 investigation focused on the motor pool located in the northern portion of Parcel S1.4. The investigation included site walks and the installation of several soil borings (*HLA, 1997c*). No evidence of OE was found during this investigation.

The IRP Site 24 investigation focused on the former Directorate of Engineering and Housing (DEH) yard and included soil borings, geophysical survey, trenching and soil excavations (*HLA, 1997b*). Trenches excavated to investigate geophysical anomalies identified through the site characterization of IRP Site 24 were completed within Parcels L33.1 and S1.4 (*HLA, 1996c*). The trenches were excavated by UXO specialists. No evidence of OE was found during this investigation. Site characterization activities identified three interim action (IA) areas requiring further investigation. Four soil excavations totaling approximately 13,160 square feet were completed within IRP Site 24 (Parcels L33.1 and S1.4). Field personnel trained in ordnance recognition supervised the completion of the excavations. No evidence of OE was found during this investigation.

Additionally, an approximately 1,980-square-foot excavation located in Parcel L33.1 related to the investigation and remediation of a hydrocarbon release associated with UST 3803 was completed (*HLA, 1997a*). Field personnel trained in ordnance recognition supervised the excavation of the former UST site. No evidence of OE was found during the UST excavation.

Investigations involving the Fort Ord SWMU program and property transfer included site walks of the property. No evidence has been found to indicate the use of ordnance on these parcels.

2.8.5.3 Rationale

OE is not likely to be present on these parcels for the following reasons:

- A review of former Fort Ord OE-related investigations including the ASR, the Literature Review, the Site 39 Data Summary and Work Plan and the OE Sampling, and the HFAI OEW Sampling, OEW Removal Action Final Report, indicates the parcel was not used for ordnance training
- OE sampling on Track 0 Parcels S1.4, L33.1, and E15.1 found no evidence of OE
- Construction/development began on portions of the parcels immediately after purchase of the property by the Army
- The results of the former Fort Ord CERFA investigation included a site walk on the developed portions of the parcels and a review of the former Fort Ord related documentation including documents pertaining to ordnance use, and found nothing to indicate ordnance use
- No evidence of ordnance use was found during several site walks of these parcels
- Investigations completed under the Basewide RI/FS program that included geophysical surveys, trenching and excavations, found no evidence to indicate the use of ordnance on the parcel
- The area has been in use since it was purchased in 1940 and no evidence of OE has been found.

2.8.6 Parcels L1.1, L19.2, L19.3, L19.4, L32.2.1, L32.2.2, L32.3, L32.4.1.1, L32.4.1.2, L32.4.2, L23.6, L36, L37, L15.1, L7.8, L7.9, L2.4.2, L2.4.3.1,

L2.4.3.2, S1.3.1 – Surplus II Area

2.8.6.1 Background

These parcels are located in the central and eastern portion of the Main Garrison (Plate 7). These parcels include former barracks, support facilities, motor pools, and recreational facilities. The combined parcel area is approximately 175 acres. This property was purchased by the Army in 1940. All the parcels appear to lie within an area designated as a “Well Area, No Artillery Firing or Demolitions” as shown on the 1945 Fort Ord Training Facilities map (*Army, 1945*). Development began in the mid 1950s with some buildings dating back to 1954. Review of 1951 aerial photographs indicated that the area was undeveloped prior to the mid 1950s. Review of the 1956 aerial photograph indicated barracks were present in portions of Parcel L32.2.2 and L7.8 and L7.9, along with several other buildings (Parcel L19.4). Construction of the motor pool east of the barracks, Parcel S1.3.1, was also started in 1956. Two training areas, a rifle instructional circle and a machine gun square, were present in the southeastern portion of this area, Parcels L32.2.1 and S1.3.1, in 1956. Review of aerial photographs and training maps from the 1960s and early 1970s (*SCS, 1966; USACE, 1974; Army, 1964, 1967*) indicate that the area west of the barracks was mostly open space and the area east of the barracks (Parcels L32.2.1 and S1.3.1) was used for training. Several areas are labeled as physical training areas on 1960s training maps. Development of this area continued in the 1970s and 1980s with the construction of additional support buildings and recreational facilities.

2.8.6.2 Site Investigation

Four OE sites have been identified in the vicinity of this area, Sites OE-4A, OE-13B, OE-31, and OE-39. Site OE-4A was identified as a Chemical, Biological, and Radiological (CBR) Training Area on historical maps. Sampling of this site resulted in the discovery of 1 rifle grenade, 2 illumination signals, as well as

67 grenade fuzes found in a burial pit. On the basis of the sampling results, the site received a 4-foot-deep removal. One UXO item (illumination signal) was found and removed during the removal action (USA, 1999c). As shown on Plate 7, an undeveloped area separates the northern boundary of Site OE-4A and Track 0 Parcels L2.4.3.1, L2.4.2 and L32.4.1.2.

Site OE-13B was identified in the Archives Search Report (USAEDH, 1997b) as a practice mortar range. The site was identified on training facilities maps in the 1950s. The boundaries of the site were defined and OE sampling was performed. Sampling of the site confirmed that the site had been used extensively as an OE training area. On the basis of the sampling results a removal action over the entire site was performed. UXO items found included pyrotechnics, smoke grenades and projectiles of various sizes. During the removal action two partial Chemical Agent Identification Sets (CAIS) were found. Two cardboard tubes containing intact glass vials were discovered inside of metal canisters buried at depths of 1 and 1.5 feet. The sets were removed by the Technical Escort Unit of Tooele Utah and transferred to their facility (USA, 2000). Based on the presence of established developed areas from the 1950s west of the site, it is expected that any live firing occurring on the site would have been directed toward the east away from the developed area. Site OE-13B is separated from the adjacent Track 0 parcels by a road. Site OE-13B will undergo additional evaluation in the OE RI/FS.

Site OE-31, CSU Footprint, was identified as the result of impending Base Realignment and Closure (BRAC) action and encompasses Sites OE-7, OE-8, OE-4C, OE-18, and a portion of OE-13B. Three and four foot removals have been conducted throughout the OE sites. Although several burial pit caches of ordnance were found and removed, the ordnance actually fired at the CSU Footprint was apparently limited to rifle grenades. UXO items found during the OE removal actions included smoke grenades, fuzes, pyrotechnics (e.g., flares), and practice mines (HFAI, 1994). Based on the presence of established developed areas west of

the site it is expected that any live firing would have been toward the east away from the developed areas. Site OE-31 is separated from the adjacent Track 0 parcels by a road. Site OE-31 will undergo additional evaluation in the OE RI/FS.

Site OE-39 is located to the south of Track 0 Parcel L32.4.1.2. Site OE-39 was identified in the ASR (USAEDH, 1997b) as a mine and booby trap training area. The boundary of the OE site was established based on the delineation of a training area on former Fort Ord training facilities maps from the 1950s. The training area was identified as an area for further investigation. An ordnance removal contractor established sample grids within the site and sampling was performed. No evidence of OE was found and no further action was recommended (USA, 1999a). As shown on Plate 7, developed land separates the Site OE-39 boundary and Track 0 Parcel L32.4.1.2. Site OE-39 will undergo additional evaluation in the OE RI/FS.

Extensive field work including site walks, soil boring investigations and soil excavations at IRP Site 22 has taken place within portions of Parcel S1.3.1. This area was investigated for the presence of chemical contamination under the Fort Ord Basewide RI/FS program. No OE items were encountered during completion of these investigations.

Additionally, an approximately 8,000 square foot excavation located in Parcel S1.3.1 related to the investigation and remediation of hydrocarbon releases associated with UST 4534 and Grease Rack 4532 was completed. Field personnel trained in ordnance recognition supervised the excavation of the former UST site. No evidence of OE was found in the excavation.

2.8.6.3 Rationale

OE is not likely to be present on these parcels for the following reasons:

- A review of former Fort Ord related investigations including the ASR, the

Literature Review, and the Site 39 Data Summary and Work Plan indicates that these areas were not used for ordnance training

- OE sampling at nearby Site OE-39 found no evidence of OE
- OE removal actions have been conducted at nearby Sites OE-4A, OE-13B and OE-31
- Sites OE-4A, OE-13B, OE-31, and OE-39 are separated by roads, open space or developed areas, from the Track 0 parcels
- The areas have been developed since the 1950s and no evidence of OE has been found
- The results of the Fort Ord CERFA investigation which included a site walk on the developed portions of the parcels and review of Fort Ord related documentation including documents pertaining to ordnance use, found nothing to indicate ordnance use
- Investigations completed under the Fort Ord Basewide RI/FS program that included excavations and intrusive activities, found no evidence to indicate the use of ordnance on the parcels.
- No evidence of ordnance was found during several site walks of these parcels.

**2.8.7 Parcels S2.1.3,
S2.1.4.1, S2.1.4.2,
L5.1.2, L5.1.3, L5.1.4,
L5.1.5, L5.1.6, L5.1.7,
L5.1.8, L5.1.9, L5.1.10,
L5.2, L5.3, F7.1, F7.2 –
Fritzsche Army Airfield
Area**

2.8.7.1 Background

These parcels have a combined area of approximately 48 acres (Plate 8). The City of Marina is adjacent to the southeast. With the exception of L5.3, the parcels lie in the northeastern portion of the former Fort Ord, north of Reservation Road and in and around the

former Fritzsche Army Airfield (FAAF). L5.3 lies offsite, about 2 and ½ miles east of the eastern boundary of the East Garrison. The parcels in this group were included in the 1940 land purchase. They include support buildings related to the FAAF, water supply wells, and a former sewage treatment plant.

Historical maps show no structures on the area north of Reservation Road until the late 1960s, when the FAAF airstrip, navigational beacons, and support buildings are evident. Earlier maps show the airfield but no support buildings. In 1946, the area had a practice bazooka and rifle grenade area linked by access road to Reservation Road (then known as New County Road) (*USACE, 1946*). Maps from the 1950s show the area assigned for training by the 41st Signal Battalion (1953) as: (1) a Ranging Area, (2) a Demonstration Area, (3) a Tank Driving Area used by the 759th Tank Battalion (*Army, 1956*), (4) a Basic Driving Area (1957), and (5) a Field Communication, Crewman's Course, and Leased Area (1958). Lack of suitable terrain for tank firing practice, no evidence of tank targets, and no evidence of ordnance use in the area indicate the training in the area was not OE related (*HLA, 2000*).

2.8.7.2 Site Investigation

In 1998, Parcels L5.1.2 through L5.1.10, L5.2, and L5.3 were the subject of a Finding of Suitability to Transfer (FOST) conducted by the Army (*Army, 1998b*). The FOST reviewed the Environmental Baseline Survey (EBS) for the FAAF parcel (January 1995), the final CERFA report (April 1994), EPA Region IX's concurrence with the CERFA report (April 19, 1994), various RI/FS documents, remedial action reports, and subsequent approval memoranda. A site walk was conducted in June 1997. The FOST reported the following information for the parcels as documented in the various sources:

- Parcels L5.1.2, L5.1.4, and L5.1.5 are included in IRP Site 40. The site was the FAAF Defueling Area. L5.1.4 and L5.1.5 are Interim Action (IA) Sites 40C and 40A, respectively. The parcels were subject to IA

investigation activities in June 1996 that included soil excavation, soil sampling, and excavation backfilling. The Site 40 IA Confirmation Report submitted to regulatory agencies in January 1997 was approved by the EPA (January 31, 1997) and DTSC (July 23, 1998). No further remedial action was deemed necessary at the site.

- Parcel L5.1.3 includes a 200-gallon propane tank no longer in use
- Parcel L5.1.6, L5.1.7, L5.1.9, and L5.1.10 are included in IRP Site 34. The parcels are Wash Aprons 534 and Buildings 534 and 538; Wash Apron 525; Wash Apron 512; and Wash Apron 517. The four wash aprons were used for cleaning vehicles on the property. The buildings on these parcels were used by the Army for aviation operations and navigation. Investigations on the property include a 1993 asbestos survey conducted on Buildings 534 and 538 (Parcel L5.1.6).
- Parcel L5.1.8 is IRP Site 36 (FAAF sewage treatment plant and Building 550C). This building has been used to house navigational equipment for Marina Municipal Airport. Building 550C was investigated during the facility-wide asbestos survey in 1993. The building was also the site of a former UST, which was removed in March 1996 and granted Monterey County Department of Health (MCDOH) closure in a letter dated April 6, 1994.
- Parcels L5.2 and L5.3 are former aviation navigational beacons. Parcel L5.2 also contains Building 550B, which was investigated during a facility-wide asbestos survey in 1993. The building was also the site of a former UST, which was removed in April 1992 and granted MCDOH closure in a letter dated January 6, 1996.

The FOST indicated no OE or evidence of OE use in any of the above parcels. The FOST did find evidence of OE use in adjacent Parcel L5.1.1, identified from a 1946 facilities training map as a practice bazooka and rifle grenade area (USACE, 1946).

The remaining parcels, S2.1.3, S2.1.4.1, and S2.1.4.2, have been investigated as follows:

- Parcel S2.1.3 is IRP Site 35, the FAAF Aircraft Cannibalization Yard, which underwent site characterization from 1993 to 1995 (HLA, 1995c). Activities for the investigation included clearing sampling locations for sensitive habitats, conducting a soil gas survey, and drilling three soil borings. No evidence of OE was found during these activities.
- Parcels S2.1.4.1 and S2.1.4.2 are included in IRP Site 34, in an area that encompasses Wash Apron 516 and Building 509. The parcels underwent soil investigations for IA activities conducted between 1995 and 1997 (Uribe & Associates, 1998). No evidence of OE was found during these activities.

One OE site, OE-34, is near the parcels for this group. Site OE-34 is approximately 100 feet northwest of L5.1.8 and 800 feet northeast of L5.1.4. In 1994, a removal action was conducted at Site OE-34. The deepest penetrating item found on Site OE-34 was a 2.36-inch rocket (HLA, 2000). In 1999, the EPA geophysically resurveyed 7 acres of Site OE-34 using an EM61 and 1.5 acres using a G-858 magnetometer. Subsequently in 1999, the Army also resurveyed the entire limits of Site OE-34 using an EM61. No UXO was found during the 1999 surveys. As shown on Plate 8, developed and undeveloped land separates the boundary of Site OE-34 and the Track 0 parcels. Site OE-34 will undergo additional evaluation in the OE RI/FS.

2.8.7.3 Rationale

OE is not likely to be present on the parcels for the following reasons:

- A review of Fort Ord related investigations including the Revised ASR, the Literature Review and the Site 39 Data Summary and Work Plan indicates the parcels were not used for ordnance training

- Developed and undeveloped land separates the boundary of Site OE-34 and the Track 0 parcels
- All parcels lie within an area with no evidence of OE use or history of OE related items identified in incident reports. An adjacent OE site, Site OE-34, has undergone complete OE removal and confirmation
- The Fort Ord CERFA investigation found no evidence of ordnance use on these parcels
- No evidence of OE was found during a site walk performed in support of the real estate transfer of these parcels
- Investigations completed under the Fort Ord Basewide RI/FS program that included excavations and intrusive activities, found no evidence of ordnance use on the parcels.

2.8.8 Parcels E11b.1, E11b.2, E11b.3, E11b.4, L20.14.1.2, L20.19.2, L20.20, L20.21.1, L20.21.2, L20.22, L23.3.1, L23.3.2.1, L35.3, L35.6, L35.7, and L35.8 – East Garrison Area

2.8.8.1 Background

These parcels are within the earliest developed portions of former Fort Ord and include the East Garrison (including buildings and infrastructure), the East Garrison sewage treatment plant, a former skeet range, a small family cemetery and some undeveloped property. The combined parcel area is approximately 226 acres (Plate 9). The property was purchased by the Army in 1917 and was used as an encampment for artillery and cavalry units stationed at the Presidio of Monterey. Construction of permanent facilities began in 1940 and included mess halls and latrines (Parcel L23.3.2.1), a mule corral and sewage treatment facility (Parcels E11b.2 and E11b.3, respectively), a truck and gun parking area

(Parcels L23.3.1 and E11b.1), and storage buildings (Parcels L23.3.1 and L23.3.2.1) (*TSCRRC, 1993*). Little development has occurred on these parcels since this time. The Leadership Reaction Course (LRC) was established in 1960s in the southern portion of Parcel L23.3.2.1.

2.8.8.2 Site Investigation

The LRC was used to test and evaluate leader practices and problem solving (*Army, 1992*). According to a former Range Control Officer, the LRC was an obstacle course and no live firing of any kind was allowed (*Stickler, 1999*). A skeet range was established in the southern half of Parcel L23.3.1 sometime after 1964 and prior to 1968 (*HLA, 1994c*). A heavy vehicle driver training course was built within the northern portion of Parcel L23.3.1 in 1971. An area utilized for the storage of hazardous waste prior to disposal or recycling, was established within in Parcel L23.3.2.1 by the Fort Ord Defense Reutilization and Marketing Office (DRMO) in the early 1970s (*HLA, 1994a*).

The only training involving the use of weapons in the immediate area occurred within nearby small arms ranges located on adjacent parcels. Firing at the small arms ranges was toward the south away from the East Garrison (*Army, 1940b*). The northern boundary of Site OE-5 is located to the south of the East Garrison area. Site OE-5, south of East Garrison, was established as the result of the finding of a scrap 3.5" rocket motor in the branches of an oak tree in the area (*USAEDH, 1997b*). No known range for rocket firing was located in this area. An ordnance removal contractor sampled this site and did not find evidence of ordnance use (*HFAI, 1994*). As shown on Plate 9, undeveloped land separates the northern boundary of Site OE-5 and Track 0 Parcels L20.20, L20.21.1, L20.21.2, L23.3.1, L23.3.2.1, L35.6 and E11b.1. Site OE-5 will undergo additional evaluation in the OE RI/FS.

A USACE UXO Safety Specialist completed a site walk of Parcel E11b.1 and no UXO or OE scrap was found.

Extensive field work including site walks, soil boring investigations, trenching and soil excavations at IRP Sites 29, 30, 32 and 39A have taken place within the developed and undeveloped portions of most of the parcels. These areas were investigated for the presence of chemical contamination under the Basewide RI/FS program. No OE was encountered during any of the IRP investigations.

2.8.8.3 Rationale

OE is not likely to be present on these parcels for the following reasons:

- A review of former Fort Ord ordnance related investigations including the ASR, the Literature Review, the Site 39 Data Summary and Work Plan and the Site OE-5 Sampling and Removal Action Final Report, indicates that the parcels were not used for ordnance training
- OE sampling at nearby Site OE-5 found no evidence of OE
- Site OE-5 is separated by undeveloped land from the Track 0 parcels
- This area was the one of the first to be established and developed as a troop encampment at Fort Ord
- No UXO or OE scrap was found on Parcel E11b.1 during a site walk completed by a USACE UXO Safety Specialist
- No evidence of OE use was found during the Fort Ord CERFA investigation, which included site walks of the developed and undeveloped parcels and a review of Fort Ord related documentation
- Investigations completed under the Fort Ord Basewide RI/FS and UST programs, which included intrusive activities, found no evidence to indicate the use of ordnance on the parcels
- No evidence of OE use was found during several site walks of the parcels.

2.8.9 Parcels E2b.1.1.1, E2b.1.2, E2b.1.1.2, E2b.1.3, E2b.1.4, E2b.1.5, E2b.2.1, E2b.2.2, E2b.2.3, E2b.2.4, E2b.2.5, E2b.3.1.1, E2b.3.2, E2c.2, E2c.3.1, E2c.3.2, E2c.3.3, E2c.4.1.1, E2c.4.2.1, E2d.1, E2d.2, E17, L2.1, L12.2.2, L12.2.3, L12.3, L23.1.1, L23.1.2, L23.1.3, L23.1.4, L23.1.5, L35.1, L35.2, L20.16.1, L20.16.2, L20.16.3, S1.5.1.1, S1.5.1.2, S1.5.2, L23.4, L2.2.1, L5.8.1, L5.8.2, L20.17.1 – Main Garrison Area

2.8.9.1 Background

These parcels are within the former Fort Ord Main Garrison and include the earliest and most heavily developed portions of the former Fort Ord. Most of the property containing these parcels was purchased in 1940, however, these parcels also include land originally purchased by the Army in 1917 (*Little, 1994*). The majority of the development on these parcels occurred in 1940 and 1941 and included the construction of troop barracks, motor pools, horse stables and corrals, support and maintenance facilities, a hospital and recreation areas and the installation of water supply wells (*Army, 1940a*). The combined area includes 44 parcels that encompass approximately 568 acres (Plate 10).

2.8.9.2 Site Investigation

A few locations within these parcels were utilized for weapons training and include a mortar square location and rifle instruction circles. The mortar square was formerly located on Parcel S1.5.1.1 within a motor pool

(Army, circa 1954). As discussed previously, mortar squares were used for the practice of setting up and aiming of weapons or dry fire (HLA, 2000). The former locations of three rifle instruction circles were identified on these parcels. Two of three former locations lie on Parcel S1.5.1.1 in an area that had previously contained as horse corrals (U.S. Engineer Office, 1946). The third rifle instruction circle was located in an open area partially within the boundary of Parcel S1.5.2 (FASI, 1951). All of the Main Garrison Track 0 parcels lie within an area identified on a 1945 Training Facilities map as a "Well Area, No Artillery Firing Or Demolitions" (Army, 1945). In 1993 an inert land mine was found in a storage yard within Parcel L35.1. The device was apparently left at the location and was not related to any training activities in this area (HLA, 1994b).

One potential OE site is adjacent to these parcels. Site OE-2, Pete's Pond is located adjacent to Parcels S1.5.1.1, S1.5.1.2, and L5.8.1 and a portion of Site OE-2 overlies Parcel L5.8.2 (Plate 10). Site OE-2 was identified as a chemical training area and a landmine warfare training area (USAEDH, 1997b). Site OE-2 was sampled for OE in 1994 and two inert OE scrap items were found (HFAI, 1994). A portion of Site OE-2 overlaps IRP Site 16 (Parcel L5.8.2) and is adjacent to IRP Site 17 (Parcel S1.5.1.2). During the investigation and remediation of IRP Sites 16 and 17, 468 2.36-inch inert practice rockets were removed from burial pits located in former landfill areas within Parcels L5.8.2 and S1.5.1.2 (IT, 2000) (Plate 10). Landfill areas within Parcels S1.5.1.2 and L5.8.2 were fully excavated in 1997. This area is considered a Special Case Track 0 area. Although ordnance was found on Parcels S1.5.1.2 and L5.8.2, the items were buried in disposal pits within these parcels and were not associated with ordnance use in these areas. The land within the OE footprint has been excavated, backfilled and re-graded. Any ordnance that might not have been located through excavation would most likely have been found during the re-grading process. Site OE-2 will undergo additional evaluation in the OE RI/FS.

A USACE UXO Safety Specialist completed a site walk around two groups of barracks on Parcel E2b.3.1.1. The inspection involved walking around the outside of the buildings and looking under the building where openings in the building skirt allowed a view into the crawl space. No UXO or OE scrap was found during the site walk.

Several other investigations related to the potential presence of chemical contamination occurred on these parcels. The investigations were performed under the former Fort Ord Basewide RI/FS program. Investigations occurred at IRP Sites 12, 13, 14, 15, 18, 19, 28, and 38. These investigations included literature reviews, site walks and monitoring well and soil boring installation. Additional intrusive activities (trenching and excavating) occurred at IRP Sites 12, 14, and 15. The investigation at IRP Site 12 (Parcel E2b.2.1) included the excavation and removal of contaminated soil at two locations, including the removal of debris within a large disposal area. No evidence of ordnance was found during the excavation of the two areas associated with IRP Site 12 (IT, 1999b). The investigation at IRP Site 14 (Motor Pool) included the excavation of contaminated soil associated with grease racks located on Parcels L5.8.1, S1.5.1.1 and S1.5.2. Four small excavations were completed and no evidence of ordnance was found (HLA, 1996a). The investigation at IRP Site 15 (Directorate of Engineering and Housing Yard) included the excavation of contaminated soil adjacent to Building 4913 located on Parcel L20.17.1 (HLA, 1996d).

Site walks of these parcels have occurred in support of proposed real estate transfers of these parcels. No evidence of ordnance use was observed during these site walks (HLA, 1997e).

2.8.9.3 Rationale

OE is not likely to be present on these parcels for the following reasons:

- A review of former Fort Ord ordnance related investigations including the ASR, the Literature Review, the Site 39 Data

Summary and Work Plan, indicates that the parcel was not used for ordnance training

- Construction/development began on most of the parcels immediately after purchase of the property by the Army
- OE sampling at adjacent Site OE-2 only identified two OE scrap items
- A USACE UXO Safety Specialist completed a site walk around two groups of barracks on Parcel E2b.3.1.1. No UXO or OE scrap was found during the site walk
- The results of the Fort Ord CERFA investigation which included a site walk on the developed portions of the parcels and a review of Fort Ord related documentation including documents pertaining to ordnance use, found nothing to indicate ordnance use
- Investigations completed under the former Fort Ord Basewide RI/FS program that included trenching and excavations, found no evidence to indicate the use of ordnance on the parcel
- The landfill areas within Parcels S1.5.1.2, L5.8.2 and L20.17.1 that were found to contain buried inert rockets were fully excavated. Additionally, the remaining non-landfill areas of Parcels L5.8.2 and L20.17.1 that lie within the Site OE-2 boundary were completely re-graded
- No evidence of ordnance use was found during several site walks of these parcels.

2.8.10 Parcels E2e.1, E2e.2, E8a.1.2, E8a.1.3, E8a.1.4, E8a.1.5, S1.3.3, S2.5.1.1, S2.5.1.2, and Portions of Parcels S2.5.2.1 and S2.5.2.2 – OU 2 Landfill Area

2.8.10.1 Background

These parcels lie in the north central portion of the former Fort Ord and include undeveloped land adjacent to, but excluding, areas overlying the former Fort Ord landfill, a portion of Inter-Garrison Road, the 8th Avenue Cut-Off, 6th Street between the 8th Avenue Cut-Off and Imjin Road and their associated right of ways (ROWS). The parcels in this group were included in the 1940 land purchase. The parcels include several roads used to access the landfill. The combined parcel area is approximately 156 acres (Plate 11).

2.8.10.2 Site Investigation

Portions of these parcels were used for various non-ordnance training activities from 1940 until approximately 1987. Non OE training activities occurring on the parcels included a camouflage area, obstacle course and Field Communication Course. No training areas are shown on these parcels on former Fort Ord training facilities maps dated after 1987. Construction of a landfill began adjacent to Parcels E8a.1.2, E8a.1.3, E8a.1.4, and E8a.1.5 in 1960 and remained active into the late 1980s (*HLA, 1990*). Housing was constructed (Fredricks Park and Schoonover Park) on adjacent property beginning in 1981. Housing and recreation areas were developed to the north of the parcels in the late 1970s (*Little, 1994*).

Two potential and one known or suspected ordnance sites are located adjacent to the parcels. Sites OE-2, OE-13A, and OE-31. Site OE-2, Pete's Pond, was identified as a chemical training area (*USAEDH, 1997b*). Site OE-2 was sampled for OE in 1994 and two OE scrap items were found (*HFAI, 1994*). Four hundred sixty-eight 2.36-inch inert practice rockets have been removed from disposal pits located in former landfill areas within Parcels S1 5.1.2 and L5 8.2. Results of the ASR indicate that Site OE-2 was not an impact area. Site OE-2 will undergo additional evaluation in the OE RI/FS.

Site OE-13A was identified in the ASR as a practice mortar range and it is believed that

practice mortars, inert training devices, were used here (*USAEDH, 1997b*). No evidence of mortar firing was found during OE sampling activities at Site OE-13A (*HFAI, 1994*). The practice mortar range is shown on Fort Ord Training and Facilities maps dating from 1954 to 1958. On the basis of the location of the bleachers located at Site OE-13A, firing of practice mortars at this site would have been toward the northeast roughly parallel to Imjin Road (Plate 11). Site OE-13A will undergo additional evaluation in the OE RI/FS.

Site OE-31, CSU Footprint, was identified by the BRAC office as a disposal parcel. The site boundary is based upon transfer parcel delineation and not on evidence of OE. Several OE sites lie within the Site OE-31 boundary including Sites OE-4C, OE-7, OE-8 and OE-18. Three and four foot OE removal have been conducted throughout the site. Although several burial pit caches of ordnance were found and removed, the ordnance actually fired at the OE site was apparently limited to rifle grenades. The type of training activities that occurred at nearby Sites OE-4C, OE-7, OE-8 and OE-18 would not have impacted the Landfill parcels (*USAEDH, 1997b*). UXO items found during the OE removal actions at Sites OE-4C, OE-7, OE-8, and OE-18 included smoke grenades, fuzes, pyrotechnics (e.g., flares), and practice mines (*HFAI, 1994*). Site OE-31 will undergo additional evaluation in the OE RI/FS.

Site walks of Parcels S2.5.1.1 and S2.5.2.1 were completed by a USACE UXO Safety Specialist and no UXO or OE scrap was found.

2.8.10.3 Rationale

OE is not likely to be present on these parcels for the following reasons:

- A review of former Fort Ord ordnance related investigations including the ASR, the Literature Review and the Site 39 Data Summary and Work Plan, indicates that the parcels were not used for ordnance training
- OE removal action was conducted at adjacent Site OE-31

- OE sampling was conducted at Sites OE-2 and OE-13A and only OE scrap was found
- No OE was identified in Parcel S2.5.1.1 during remediation activities conducted at Sites 16/17 and OU2
- Land adjacent to the Parcels was used as a sanitary landfill beginning in 1960. Housing was constructed immediately to the north of the parcels in the late 1970s and to the immediate east in 1981. There were no reports of OE being found during construction
- No UXO or OE scrap was found on Parcels S2.5.1.1 and S2.5.2.1 during a site walk completed by a USACE UXO Safety Specialist
- Inter-Garrison Road (Parcels E2e.2 and S1.3.3) has been in its present location since at least 1943.

2.8.11 Parcels L5.10, L20.10.1.1, L20.10.1.2, L20.10.2, and L20.10.3 – Reservation Road Area

2.8.11.1 Background

These five parcels are rectilinear areas that extend along and include Reservation Road in the northeastern portion of the former Fort Ord. The road lies southwest of and runs roughly parallel to the Salinas River from Highway 1 through the former Fort Ord to the East Garrison area. Parcel L5.10 is the farthest west of the four parcels along the road, followed by L20.10.1.1, L20.10.1.2, L20.10.2, and L20.10.3 in respective order moving southeast (Plate 12). Portions of the road between the parcels are excluded from consideration in this ROD because they are not on the former Fort Ord property. This parcel group area totals approximately 55 acres.

Historical maps of the area dating from as early as 1913 show sections of the road as part of an unnamed, unimproved track. Maps dating from

the 1940s and 1950s show the road as New County Road or County Road (*USACE, 1946; Army, 1956*). Later the road was improved, widened, and renamed Reservation Road (*USACE, 1976*).

Parcel L5.10 and a portion of Parcel L20.10.1.1 lie within lands acquired by the Army in 1940. The remainder of Parcel L20.10.1.1, as well as Parcels L20.10.1.2, L20.10.2, and L20.10.3 lie within lands acquired by the Army in 1917. The parcels border Parcels E5, E11.b.2, F7.2, L23.3.2.1, and S2.1.4.1, also included in this ROD based on their non-OE histories. Areas that do not border the aforementioned parcels, with the exception of L20.10.3, lie in an area with no evidence of OE use or history of UXO items identified in incident reports (*HLA, 2000*). Parcel L20.10.3 borders a non-OE area as well, except for adjacent Site OE-33 (OE Cache), that has undergone complete OE removal (*HLA, 2000*).

2.8.11.2 Investigation Summary

In 1998, the parcels were the subject of a FOST conducted by the Army (*Army, 1998b*). The FOST reviewed the final CERFA report (April 1994), EPA Region IX's concurrence to the CERFA report (April 19, 1994), various RI/FS documents, remedial action reports, and subsequent Approval Memoranda. No evidence of OE was reported during the FOST investigation, which included a site walk conducted on January 27, 1997 (*Army, 1998b*). Field personnel trained in ordnance recognition performed the site walk. No evidence of OE was found during the site walk.

Site OE-33 lies adjacent to Track 0 Parcel L20.10.3. Site OE-33 (OE Cache) was identified by the Fort Ord Federal Police (*UXB, 1995*). The Federal Police located a foxhole containing small arms ammunition a live practice 40mm cartridge and five live 40mm smoke cartridges. A 4-foot removal was performed and additional small arms and 40mm cartridges were removed. Site OE-33 will undergo additional evaluation in the OE RI/FS.

2.8.11.3 Rationale

OE is not likely to be present on these parcels for the following reasons:

- A review of the former Fort Ord ordnance related investigations including the ASR, the Literature Review, the Site 39 Data Summary and Work Plan, and the UXB Removal Action Report for Site OE-33 indicates the parcels were not used for ordnance training
- All parcels except one lie within and adjacent to areas with no evidence of OE use or history of UXO items identified in incident reports. The exception is L20.10.3, which borders Site OE-33, the OE Cache, a site that has undergone complete OE removal
- According to historical records, the roadways and shoulders have been used since at least 1913 for vehicular traffic
- The Fort Ord CERFA investigation found no evidence of ordnance use on these parcels
- No evidence of ordnance was found during a site walk performed in support of the proposed real estate transfer of this parcel.

2.9 Documentation of Significant Changes

The Track 0 Proposed Plan was released for public comment in February 2000. The Proposed Plan identified 118 parcels or portions of parcels as meeting Track 0 status at the time. The Army reviewed all written and verbal comments submitted during the public comment period. It was determined that no significant changes to the remedy (No Action), as originally identified in the Proposed Plan, were necessary or appropriate.

However, based on transfer parcel boundary changes and on additional information discovered since the publication of the Proposed Plan, changes were made to the status of several Track 0 parcels. Parcels S2.1.2, L5.6.1, L5.6.2, and portions of Parcels S2.5.2.1 and S2.5.2.2

have been identified as requiring further evaluation and have been dropped from the No Action determination at this time. Track 0 Parcels L20.10.1, L32.4.1 and E2c3.3 have since been subdivided for the purpose of property transfer. The subdivision of Parcels L20.10.1, L32.4.1, and E2c3.3 created additional Track 0 parcels (L20.10.1.1, L20.10.1.2, L32.4.1.1, L32.4.1.2, and E17).

A portion of former Parcel E4.3.1 was removed from Track 0 consideration because a UXO item was found within an excavation on the parcel. The location of the buried item was adjacent to the Area A landfill. On this basis Parcel E4.3.1 was subdivided into two parcels (E4.3.1.1 and E4.3.1.2). Parcel E4.3.1.1 will remain Track 0 and Parcel E4.3.1.2 is removed from Track 0 consideration at this time.

Additionally, a buffer was placed around the perimeter of the OU 2 landfill cells (approximately 100 feet) to reduce the potential for landfill gas migration to adjoining property. The addition of the buffer resulted in the subdivision of Parcel E8a.1. New Track 0 parcels created from the subdivision of the Track 0 portion of former Parcel E8a.1 include E8a.1.2, E8a.1.3, E8a.1.4, and E8a.1.5 (Plate 6).

And lastly, Parcels E2b.3.2, L20.20, L20.21.1, L20.21.2, L20.22, L20.14.1.2, and L20.19.2 have been added to the Track 0 ROD. Parcel E2b.3.2 is within the Main Garrison Area and is entirely surrounded by Track 0 Parcels. Parcels L20.20, L20.21.1, L20.21.2, L20.22, L20.14.1.2, and L20.19.2 include the roads within the East Garrison. These parcels were left out of the Proposed Plan due to an oversight, however, the parcels meet the Track 0 criteria as defined in the Proposed Plan and this ROD.

Since the Proposed Plan was issued, information concerning several OE incidents associated with some Track 0 areas has been found. These incidents were isolated occurrences, were not indicative of past OE-related use within Track 0 areas and did not present a risk to the public.

Information regarding these OE incidents were submitted to the U.S. EPA and the DTSC under cover letters dated August 8 and November 27, 2001 and June 3, 2002 (*Army, 2001a, 2001b, and 2002*).

2.10 Summary of Site Risks

Track 0 areas at former Fort Ord are those that contain no evidence of OE and have never been suspected as having been used for OE-related activities of any kind. These areas consist largely of land that has been developed for military support or residential use throughout Fort Ord's history, and areas that have no physical or documented evidence of OE-related training. This determination is supported by a Literature Review which consisted of gathering and reviewing information from multiple sources. Historical records reviewed included range control files, historical maps, aerial photographs, historical film footage, real estate records, and newspaper articles. Interviews were conducted with retired military personnel, active Corps of Engineers employees, personnel present as active servicemen at Fort Ord from the 1930s through base closure in 1994, and OE contractors. Other factors considered included physical location of the area, development history, and the results of the remedial investigation and excavation activities at sites with contaminated soil or groundwater.

Special Case areas are also considered for No Action in this ROD, such as areas where OE-related items were found within waste disposed in a landfill, but no OE-related activities occurred at the area, and the waste has been entirely removed.

Track 0 areas pose no known current or potential risk to human health or the environment from previous OE-related activities. The locations and descriptions of the areas proposed for No Action are shown on Plate 2 and are listed on Table 1.

3.0 RESPONSIVENESS SUMMARY

3.1 Overview

At the time of the public review period for the Army's Superfund Proposed Plan: No Action Is Proposed For Selected Areas at Fort Ord, California, dated February 1, 2000, the Army identified no action as the selected alternative for non-OE areas at the former Fort Ord.

Summary of Public Comments

On the basis of the written and verbal comments received, the Army's Proposed Plan was generally accepted by the public. However, several citizens expressed concerns regarding the following issues:

- Property at the former Fort Ord that currently contain housing should be transferred and reused without further delay to provide housing for the local homeless community or conversely, should not be transferred until the OE RI/FS process is completed.
- The no action areas should be evaluated as part of the OE RI/FS and under National Environmental Policy Act (NEPA) and California Environmental Quality Act (CEQA). The areas were reviewed and no action was determined to be necessary based on reviews of documentation, interviews and records searches that some members of the public feel are inconclusive or inadequate.
- There is a need to clarify how continued public education regarding the potential presence of OE, land use controls or notifications would be implemented for Track 0 areas.
- Numerous issues not directly related to the Track 0 Proposed Plan were brought up such as the role of the Restoration Advisory Board (RAB) in the Proposed Plan process; the inclusion of small arms as OE; how property transfer is conducted, etc.

3.2 Background on Community Involvement

In 1991, Fort Ord was added to the BRAC List. The economic impact of Fort Ord's closure has created much community interest relative to the potential economic reuse of portions of the former Fort Ord. Specifically, the Track 0 areas are under consideration for reuse for residential, commercial, and business development by the Fort Ord Reuse Authority (FORA).

Focused community involvement regarding the Proposed Plan has most recently involved the public review of the Army's Proposed Plan for the Track 0 areas. A 30-day public comment period began February 4, 2000 and was extended to 60 days at the request of the public, closing on April 4, 2000.

This responsiveness summary responds to written comments received during the public comment period as well as oral comments expressed during the public meeting conducted on February 16, 2000.

3.3 Summary of Comments Received During the Public Comment Period and Department of the Army Responses

Comments raised during the Track 0 Proposed Plan public comment period are categorized by four topics as summarized below: A) Document Review Issues, B) Regulatory Issues, C) Technical Issues, and D) Property Transfer and Other Issues, and are summarized in Section 3.4.

A. Document Review Issues

Several comments on the Proposed Plan document review process and its relation to

other parallel documents were made as summarized below. In general, the public requested more time to review the Proposed Plan, which was granted during a 30-day extension. In addition, comments regarding information in other documents related to the Proposed Plan were made that would not affect the outcome of the review process.

A1. A 90-day extension to the public comment period for the Superfund "No-action" Proposed Plan was requested by several members of the public. Some members of the public also requested that comments made during the Question and Answer session of the February 16, 2000 public meeting be included by reference as comments on the Proposed Plan and the transcript become part of the Administrative Record. In addition, it was requested that meetings be held in other portions of Monterey County, notice of property transfer be longer than 30 days, members of the public have sufficient information to approve the Proposed Plan, the web site be more accessible, and other ways of participating besides meetings and going to the library be provided. A member of the public observed that community members do not have adequate scientific background to understand the subject nor have sufficient information to approve the Track 0 Proposed Plan. This individual suggested that a third party, unconnected and not funded by the Army, conduct an independent study to validate the Track 0 investigation.

Response: A 30-day public comment period began February 4, 2000 and was extended to 60 days at the request of the public, closing on April 4, 2000. Public meetings are held on a monthly basis at the former Fort Ord in Monterey County. Comments made during the Proposed Plan public meeting are addressed within this responsiveness summary. Regarding the public meeting, it is clear from a review of the transcripts and the agenda that the meeting facilitator reminded the meeting participants numerous times that only comments made during the "public comment period" portion of the meeting will be considered. Information regarding the Track 0 Proposed Plan and the former Fort Ord cleanup in general is available

on the Fort Ord web site (www.fortordcleanup.com) and is distributed at the monthly meetings. Consistent with EPA guidance (*A Guide to Preparing Superfund Proposed Plans, Records of Decision, and Other Remedy Selection Decision Documents*, EPA 540-R-98-031, July 1999) and the National contingency Plan (NCP), public participation on the Track 0 Proposed Plan was accomplished by: (1) publishing a notice in a major local newspaper, (2) providing copies to the public, (3) providing a reasonable opportunity for public comment, (4) conducting a public meeting, (5) maintaining a transcript of the entire public meeting in the Administrative Record, and (6) providing a written summary of significant comments, criticisms and new relevant information. Revisions to the web site have been made to improve accessibility.

Recognizing the importance of community involvement and the need for citizens to be informed, Congress included provisions in Superfund Amendments and Reauthorization Act of 1986 to establish the Technical Assistance Grant (TAG) program. Administered by the U.S. Environmental Protection Agency, the TAG provides funding for a local community organization to hire independent technical advisors to help community members understand and comment on site-related information. Ms. Christine Shirley of Arc Ecology, as contracted through the U.S. EPA's TAG program, commented extensively on the Proposed Plan and other supporting documents.

A2. The Track 0 Technical Memorandum is still undergoing regulatory and public review and is not final. In general, it is invalid or unacceptable because the Army has not conducted an RI/FS and it relies on supporting documents that are incomplete. Comments are not due on the Draft Final Technical Memorandum until February 21, 2000. This important reference document must be finalized before it can be determined whether the proposed action is acceptable.

Response: The *Track 0 Technical Memorandum* was issued on January 21, 2000

and addressed agency comments on the November 1999 draft. Since there were no additional comments, the January 21, 2000 document became final on February 21, 2000. In addition, the public comment period for the Proposed Plan was extended to allow for review and consideration of this document. The Track 0 document process follows EPA guidance for preparing a No Action decision document (*A Guide to Preparing Superfund Proposed Plans, Records of Decision, and Other Remedy Selection Decision Documents, EPA 540-R-98-031, July 1999*), and is conducted in parallel to the OE RI/FS for the entire former Fort Ord. This Proposed Plan is based on review of numerous sources of information as described in the Literature Review and Technical Memorandum.

A3. The Army should not rely on the CERFA Report because the EPA did not entirely concur with it and it provides misleading rationales.

Response: The CERFA Report was only one of many sources of information used in identifying Track 0 areas.

A4. Evidence that the Restoration Advisory Board has evaluated the proposed action, as required by the Ordnance and Explosives Community Relations Plan (1998) or the Federal Facilities Agreement should be provided.

Response: The *Community Relations Plan, Ordnance and Explosives Program, Fort Ord, California* (March 1998) was superseded by the *Community Relations Plan Update Number 1, (May 2000)*, and the *Community Relations Plan Update Number 2 (November 2001)*. The Restoration Advisory Board (RAB) public meeting process was replaced by regularly scheduled community involvement workshops and quarterly Technical Review Committee (TRC) meetings in 1999. Neither the original *Community Relations Plan, Ordnance and Explosives Program (March 1998)*, the *Community Relations Plan Update Number 1 (May 2000)*, the *Community Relations Plan Update Number 2 (November 2001)*, nor the

Federal Facilities Agreement contain a requirement for a RAB evaluation of the Proposed Plan. The Army has met all public involvement requirements stated in the NCP (40CFR 300.430) and specifically EPA guidance (*A Guide to Preparing Superfund Proposed Plans, Records of Decision, and Other Remedy Selection Decision Documents, EPA 540-R-98-031, July 1999, Section 2.2.2*), which includes: (1) publishing a notice in a major local newspaper, (2) making a copy available in the Administrative Record, (3) providing a reasonable opportunity for public comment, (4) providing the opportunity for a public meeting, (5) maintaining a transcript of the public meeting, and (6) providing a written summary of significant comments, criticisms and new relevant information.

A5. The Army's Draft Ordnance and Explosives Remedial Investigation/Feasibility Study program is inconsistent. In the *Draft Literature Review Report* there is a paucity of contacts or interviews, missing records, lack of documentation, inadequate sampling, inadequate site walks, etc. It proves that more interviews, investigation, testing, and action is absolutely necessary for the protection of human health and the environment.

Response: A similar comment was addressed in "Summary Of Public Comments And Responses On The Draft Literature Review Report," included as Appendix E to the *Draft Final Literature Review Report*, dated January 4, 2000. The Army did attempt to locate others who might have information on training at the former Fort Ord through publishing advertisements in both USA Today and the Army Times as part of the Final Engineering Evaluation/Cost Analysis – Phase 1, Former Fort Ord, Monterey California dated September 1997. The advertisements provided a toll free number. A total of 26 telephone responses were received. In addition, a request for information on ordnance use and training at the former Fort Ord was submitted to the Fort Ord Alumni Association. To date, no response has been received. Previous interviews for the Basewide RI/FS were also reviewed for any information related to ordnance use or training.

B. Regulatory Issues

Several comments were received from the public regarding the regulatory requirements under which the Proposed Plan was prepared. In general, the comments were not applicable to the No Action document requirements as summarized below.

B1. The Proposed Plan is incomplete. It is requested that the Army provide alternatives to the proposed remedy in support of the proposed action during the public comment period. The Army is required to perform an analysis of alternatives as part of the Remedial Investigation/Feasibility Study process.

Response: In accordance with the EPA Guidance Document, *A Guide to Preparing Superfund Proposed Plans, Records of Decision, and Other Remedy Selection Decision Documents (EPA 540-R-98-031)* Section 8, the Description of Alternatives and Comparative Analysis of Alternatives are not required when documenting a No Action decision where unacceptable risks will not occur.

B2. Several citizens expressed concern that the Army had not addressed NEPA and CEQA for the Track 0 areas, and one citizen commented that the Army is using its response authority to conduct response actions.

Response: Since the CERCLA/NCP process provides for public involvement in a manner that is functionally equivalent to NEPA requirements, compliance will be achieved by following the NCP procedures. CERCLA specifically seeks to avoid unnecessary duplication of effort. The CERCLA/NCP process addresses, where appropriate, consideration of environmental effects and compliance with applicable legal standards, and the public will be afforded the same opportunity to review and comment that is provided by NEPA. CEQA does not apply to federal decisions. The Army has followed appropriate procedures in evaluating the Track 0 areas and conducting response actions in conjunction with the regulatory agencies.

B3. The Army has repeatedly failed to comply with the laws that are set in place by the U.S. Government and the State of California to protect human health and the environment. Several citizens also expressed concern that the regulatory agencies (i.e., the State and EPA) need to take a more active role in the OE cleanup process at the former Fort Ord.

Response: The environmental cleanup at the former Fort Ord is being conducted in accordance with the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), as amended by the Superfund Amendment and Reauthorization Act (SARA), established by the United States Government. The cleanup is done with active regulatory oversight by the EPA, DTSC, and California Regional Water Quality Control Board (RWQCB).

C. Technical Issues

Several members of the public commented on various technical components of what is required to be included in a No Action document as summarized below.

C1. A summary of an OE baseline risk assessment for these sites is required by CERCLA Section 300.430(4). In addition, a preliminary remediation goal for OE should be established similar to the one used in the No Action evaluation for the chemical RI/FS sites.

Response: The Site Risk section of the Record of Decision provides information to support the determination that no remedial action is necessary. The lead agency in the Proposed Plan and ROD explains the basis for the conclusion that unacceptable exposures to OE will not occur. The Proposed Plan states that "Track 0 areas pose no known current or potential threat to human health and the environment from previous OE-related activities." An evaluation of each area proposed for No Action is provided in the ROD as well as the Track 0 Technical Memorandum issued January 21, 2000. The risk associated with the

potential presence of OE at the former Fort Ord and a preliminary remediation goal cannot be established in the same way as it can be for chemical residue, and is not necessary for Track 0 areas since they pose no known current or potential threat to human health or the environment from previous OE-related activities. A risk approach is under development for the Fort Ord OE RI/FS.

C2. An evaluation of the proposed action according to the "nine criteria" presented in 40 CFR Chapter 1 (7-1-99 Edition), Section 300.430 (e)(9)(iii) is required. In addition, definition of the term "community acceptance," one of the nine criteria, was requested.

Response: An evaluation according to the "nine criteria" is part of the Comparative Analysis of Alternatives Section of a decision document. This section is not required for the No Action decision document as described in the EPA guidance document (*A Guide to Preparing Superfund Proposed Plans, Records of Decision, and Other Remedy Selection Decision Documents, EPA 540-R-98-031, July 1999*). Available public input and reactions to the information presented within the Proposed Plan therefore gauge community acceptance of the Proposed Plan.

C3. An analysis of ARARs (applicable or relevant and appropriate requirements) for the proposed action is required.

Response: Applicable or Relevant and Appropriate Requirements (ARARs) analysis is part of the Statutory Determinations section of decision documents. This section is not required for a No Action decision document as described in the EPA guidance document (*A Guide to Preparing Superfund Proposed Plans, Records of Decision, and Other Remedy Selection Decision Documents, EPA 540-R-98-031, July 1999*).

C4. The Army has failed to interview enough people who served, worked, or lived, or witnessed what happened at Fort Ord. The Army only contacted or interviewed

23 people (of which only 7 were referenced in the Draft OE RI/FS Literature Review Report). Those 23 people were not at Fort Ord from the beginning to the end. They could not have witnessed every incident, accident, authorized burial, unauthorized burial, and dumping that was apparently common on the Superfund Site known as the former Fort Ord.

Response: Interviews and newspapers are not the sole basis for investigating historic uses of the former Fort Ord, but only two of the avenues used in the Literature Review. See Section 6.0 of the *Draft Final Literature Review Report* for the complete list of the references such as the National Archives and Records Administration, the Military History Institute, Presidio of Monterey historian's office, the Monterey County Historical Society, and local newspaper articles. Furthermore, this comment was addressed in the Army "Summary Of Public Comments And Responses On The Draft Literature Review Report," included as Appendix E to the *Draft Final Literature Review Report*, dated January 4, 2000.

C5. The Army and Harding Lawson Associates admit that records have been lost or destroyed. The archive search report is incomplete. Police records were not searched because it "would take too long."

Response: The Army has made a conscientious attempt to search all applicable archives. Based on the review of the Military Police records to date, no significant additional information would be obtained from further review of these records.

C6. The current ordnance removal contractor, USA Environmental, Inc., does not fill out incident reports in response to ordnance finds that they determine are OE scrap. In addition, if practice mines and real ones look the same and practice mines are overlooked during sampling, the Army cannot determine how many more there may be. All OE, OEW, UXO, and OE scrap must be fully documented. If OE scrap is found that proves OE was used in the area.

Response: The comment regarding incident reports was addressed in the Army "Summary Of Public Comments And Responses On The Draft Literature Review Report", included as Appendix E to the *Draft Final Literature Review Report*, dated January 4, 2000. All ordnance finds, whether scrap or live, when reported, are documented. Practice mines are logged during sampling of OE areas. All available OE-related information was reviewed for areas proposed for No Action. This information is provided in *Track 0 Technical Memorandum, Ordnance and Explosives Remedial Investigation/Feasibility Study, Former Fort Ord, California dated January 21, 2000*. The Army considers OE scrap in its evaluation of the presence of unexploded ordnance in any given area.

C7. The Army fails to adequately address the potential for OE to be present in the Monterey Bay. A September 1999 letter from the Monterey Bay National Marine Sanctuary should be responded to. In addition, shells have impacted other areas outside the Fort Ord boundary, which is the responsibility of the Army to address.

Response: The potential presence of OE in the Monterey Bay was addressed by geophysical and sediment sampling as described in the *Southern Monterey Bay Continental Shelf Investigations: Former Fort Ord Restricted Zone - US Geological Survey Open File Report 97-450*. This report is included as an Appendix to the *Final Enhanced Preliminary Assessment of Monterey Bay, Fort Ord California dated January 12, 1999*. The purpose of the investigation was to conduct a comprehensive investigation of the seafloor in the Fort Ord Restricted Zone to identify any suspected features that may be caused by debris related to Army activity. The report concluded that no features were identified that were related to Army or other human activity although many interesting biological features were seen. The Monterey Bay National Marine Sanctuary and other agencies were involved with the planning of this investigation. The Army responded to the September 1999 letter from the Monterey Bay National Marine Sanctuary regarding dissolution of the RAB and coastal

environmental activities at the former Fort Ord with a letter dated December 10, 1999. The Army currently has no evidence that past OE-related activities have occurred outside the former Fort Ord boundary. Should such evidence be discovered, the Army will take appropriate action at that time.

C8. The Army offers the rationale for including parcels in Track 0, but does not adequately discuss what criteria were used to select (or screen) parcels, including the Plug-in Process, which is not described in sufficient detail. The Approval Memorandum process is also not clear. It is requested that the Army systematically evaluate each parcel using a check list provided in the Approval Memorandum and apply a buffer zone of at least 500 feet around the parcels because they lie adjacent to areas of known contamination. In addition, OE sampling of 10% of an area is unacceptable and site walks were not conducted on all Track 0 areas.

Response: Each parcel was systematically evaluated and the Plug-in Process was described as being based on the criteria provided in the Technical Memorandum as summarized in the Proposed Plan. Based on the available information for each Track 0 area, the evaluation indicated no OE-related uses took place. Buffer zones, OE sampling, and additional site walks would not be justified for areas that meet the following criteria: (1) no evidence of OE exists at the area, and (2) the area has never been suspected as having been used for OE-related activities of any kind. While each Track 0 area was systematically evaluated in a manner similar to the checklist suggested in public comments, the Army developed a similar checklist which summarizes the key elements of Track 0 supporting data and which is now included in this ROD as Appendix A.

C9. Definitions related to ordnance and explosives provided in the glossary of the Proposed Plan are misleading, the potential for buried OE to be present in some Track 0 areas is unacceptable. Small arms should be included in the Track 0 analysis.

Response: The definitions are provided to clarify various terms related to OE that are typically used in literature and common practice. There is no evidence of the potential presence of buried OE at any of the Track 0 areas. The potential presence of buried OE at the former Fort Ord will be addressed in the OE RI/FS. Information collected to date from extensive excavation and grading has not identified any evidence of burials in Track 0 areas. Furthermore, there is no evidence to suggest any of the Track 0 parcels were used as small arms ranges.

C10. How will new information be incorporated into the Track 0 process? If OE is found at any Track 0 parcel during redevelopment, then the Army needs to reconsider all Track 0 designations.

Response: The property transfer documents would specify that if the property recipient should discover any ordnance on the property, the Directorate of Law Enforcement at the Presidio of Monterey must be notified and that competent U.S. Army Explosives Ordnance Disposal personnel will be promptly dispatched to dispose of such ordnance properly at no expense to the property recipient. Whenever new information concerning OE-related activities becomes available, the information will be presented to the regulatory agencies and the Army will take an appropriate action.

D. Property Transfer and Other Issues

Several comments were made by members of the public regarding property transfer and other issues not specifically related to the Proposed Plan as summarized below.

D1. The early or "dirty" transfer is not necessary and must not happen. In addition, which areas are being proposed for transfer, how large are they, and what boundaries have shifted? "Job and revenue loss" is a big myth and the Army fails to adequately describe the environmental condition of the property in these documents. *The Track 0 Technical Memorandum, Ordnance and Explosives*

Remedial Investigation/Feasibility Study, Former Fort Ord, California provides a description of the areas proposed for No Action concerning OE and does not address issues related to transfer of property.

Response: Reuse is set by the FORA Reuse Plan. This Proposed Plan is environmental documentation regarding OE that examines if the property is in a condition that is protective of human health and the environment based on the intended reuse. Locations, sizes and boundaries of the Track 0 areas are provided in the Proposed Plan, supporting Technical Memorandum, and reiterated in this ROD.

D2. The housing area properties should be transferred as soon as possible to provide housing for the local homeless community. In general, those citizens and organizations that are interested in reusing property at the former Fort Ord for the homeless felt the environmental review and cleanup of the properties were done in a responsible and reasonable manner.

Response: Comment acknowledged. Reuse is set by the FORA Reuse Plan. The Proposed Plan and ROD are environmental documentation regarding OE that examines if the property is in a condition that is protective of human health and the environment based on the intended reuse.

D3. The Army fails to assess and evaluate these properties and others for (a) hazardous substances and contamination, (b) environmental impacts anticipated from intended use, (c) ordnance and explosives, and (d) the adequacy of use restrictions and notifications. Past and present health concerns need to be addressed, such as transfer of property containing lead paint and small arms.

Response: The Proposed Plan is intended only to address specific areas at former Fort Ord where no evidence of OE exists. Former Fort Ord was evaluated for the potential presence of chemical contamination under the *Basewide Remedial Investigation /Feasibility*

Study, Fort Ord, California. Environmental impacts anticipated from the intended reuse were evaluated in the *Environmental Impact Statement, Fort Ord Disposal and Reuse.*

D4. The future uses of these properties (and others at the former Fort Ord) presents a current and future risk to human health and the environment.

Response: Track 0 areas pose no known current or potential threat to human health or the environment from previous OE-related activities.

D5. The Restoration Advisory Board (RAB) must be reestablished. In addition, the credibility of the Army is a concern. The community must be informed in order to oversee the “cleanup” process. The Army would rather not have the public and community involved, even though it is, and will be, the public and surrounding communities who are and will be suffering if proper cleanup is not implemented. The RAB has found the Army has prepared biased minutes of meetings.

Response: The Comment regarding the RAB is not applicable to this document. The public involvement opportunities required by the NCP and CERCLA have been completed as stated in the community participation section of the ROD.

D6. The citizens of Marina would know very little were it not for EPA’s Technical Assistance Grant recipient, the Fort Ord Toxics Project.

Response: The comment is not applicable to the Proposed Plan.

D7. The surrounding cities and the Fort Ord Reuse Authority (FORA) must not risk the health and safety of humans and the environment with this early or dirty transfer. The Army is known for dumping toxic and dangerous substances and materials. Why is Marina & FORA also willing to harm their citizens and the environment?

Response: Reuse is set by the FORA Reuse Plan. This Proposed Plan is environmental

documentation that examines if the property is in a condition that is protective of human health and the environment for the intended reuse. The comment is not applicable to the Proposed Plan.

D8. The Army fails to adequately describe the environmental condition of the property and to interview adequate numbers of people who served at Fort Ord. The property transfer process should cease because there are few records to adequately characterize the area. In addition, the Army admits to missing or destroying records and a lack of documentation. The Governor, EPA and DTSC must not defer the covenants that are required by law to protect human health, safety, and the environment. “Facts do not cease to exist because they are ignored.”

Response: The Proposed Plan is intended only to address specific areas at the former Fort Ord where no evidence of OE exists. Interviews are not the sole basis for investigating historic uses of the former Fort Ord, but only one source of information used in the Literature Review. The former Fort Ord was evaluated for the potential presence of chemical contamination under the *Basewide Remedial Investigation /Feasibility Study, Fort Ord, California.* Environmental impacts anticipated from the intended reuse were evaluated in the *Environmental Impact Statement, Fort Ord Disposal and Reuse.*

D9. The Army fails to adequately describe the use of chemical weapons materials at Fort Ord and to address small arms as OE. Does the Army have a program for investigating and remediating chemical warfare material at Fort Ord? Is Fort Ord participating in the Army’s non-stockpile chemical material program? If not, why not? If so, has the Army notified the program that CAIS kit and evidence of mustard gas have been recovered at Fort Ord?

Response: The Comment is not applicable to the Proposed Plan. Furthermore, there is no known use of chemical materiel and no evidence of small arms ranges within the Track 0 areas. In addition, soil contamination from small arms use at other parts of the former Fort Ord was

addressed under the Basewide ROD signed in January 1997.

The Non-Stockpile Chemical Warfare Materiel Program oversees the handling and disposal of all types of non-stockpile chemical materiel within Department of Defense. The Non-Stockpile Chemical Warfare Materiel Program conducted a national survey regarding chemical warfare materiel use, which included the former Fort Ord. The survey found no evidence to indicate the use of chemical weapons at the former Fort Ord. The installation did, however, receive chemical warfare materiel training items in the form of "chemical agent identification set" (CAIS) prior to 1974. There has been only one instance of CAIS discovery at former Fort Ord, during an OE removal action at Site OE-13B in 1997. This discovery was properly handled in accordance with protocols established by Non-Stockpile Chemical Warfare Materiel Program. Although it is unlikely, should additional CAIS be discovered at the former Fort Ord, the removal and remediation will follow the Non-Stockpile Chemical Warfare Materiel Program protocol.

On August 27, 1993, environmental cleanup contractors using a backhoe to dig a trench at IRP Site 16 (known as Pete's Pond) within the Main Garrison area, uncovered a drum. A UXO specialist operating the backhoe stopped digging because the shape of the drum was similar to drums designed to store mustard agent, although no markings were observed. The Army chemical team assessed the area of the unearthed drum. Soil samples were collected and analyzed for mustard agent and its degradation products. The sampling results did not identify any mustard agent or mustard agent degradation product. No evidence of mustard gas has ever been found at the former Fort Ord.

D10. The Army should better define the continued public education process, notification and site controls for the Track 0 areas as well as non-Track 0 areas. In addition, how will the Army compensate if someone is harmed by OE after the cleanup is complete?

Response: The public education and community involvement process for the former Fort Ord, including the Track 0 areas, are described in the *Community Relations Plan Update #1*. Fences and signs have been placed around the Multi-Range Area (MRA) to limit access to certain parts of the former Fort Ord, and such security measures will be maintained until the OE sites are in a condition that is safe for unrestricted access. Long term risk management measures will be developed as part of the OE RI/FS to address the possibility of someone being harmed by OE after the cleanup is complete at OE sites.

D11. The Army should describe their Memorandum of Agreement (MOA) regarding property transfer of these areas and provide information on the 5,200 acres proposed for transfer.

Response: The MOA addresses property that will be transferred between the Army and FORA and is not directly applicable to the Track 0 Proposed Plan.

3.4 Summary of Comments

On the basis of the written and verbal comments received, the Army's Proposed Plan was generally accepted by the public. However, several citizens expressed concerns regarding:

1. The need for an extension of the review period for the Proposed Plan, which was extended by 30 days.
2. Areas that currently contain housing should be transferred and reused without further delay to provide housing for the local homeless community or, conversely, should not be transferred until the OE RI/FS process is completed. Reuse is set by the FORA Reuse Plan.
3. Technical and regulatory aspects of what should be included in the Proposed Plan, which are addressed by the No Action process.
4. The need for clarification of how continued public education regarding the potential

presence of OE, land use controls or notifications would be implemented for Track 0 areas, which is addressed in the Community Relations Plan.

5. Numerous issues such as the role or the RAB in the Proposed Plan process; the inclusion of small arms as OE; how property transfer is conducted, etc., which are not relevant to or directly related to the Track 0 Proposed Plan.

4.0 REFERENCES

- Brown, Sargent First Class, 1999. 1st Battalion, 149th Armory. Telephone call with Jeff Fenton, Harding Lawson Associates. July 1.
- Curtis, Sargent First Class, 1999. U.S. Army, Fort Knox, Kentucky. Telephone call with Jeff Fenton, Harding Lawson Associates. July 7.
- Fairchild Aerial Surveys, Inc. (FAI), 1951. Aerial photograph set of Main Garrison, East Garrison, Intergarrison and North-South Road Areas to Inland Ranges. Photographs 2-10, 2-12, 2-14, 2-16, 2-18, 2-20, 2-22, 2-24, 2-26, 2-28, 2-31, 2-33, 2-35, 2-37, 2-39, 2-41, 2-43, 2-45, 2-47, 2-49, 2-51, 2-53 through 2-80, 3-1 through 3-25. June 23 and July 3.
- Harding Lawson Associates (HLA), 1990. *Fort Ord Landfills Preliminary Hydrogeologic Investigation, Fort Ord, California*. April.
- _____, 1994a. *Draft Final Site Characterization, Site 29 – Defense Reutilization and Marketing Office, Fort Ord, California*. April 29.
- _____, 1994b. *Draft Final Data Summary and Work Plan, Site 39 – Inland Ranges, Fort Ord, California*. May 17.
- _____, 1994c. *Draft Work Plan Site Characterization, Site 39A – East Garrison Ranges, Fort Ord, California*. November 3.
- _____, 1995a. *Draft Final Site Characterization, Site 20 – South Parade Ground, 3800 And 519th Motor Pools, Fort Ord, California*. May 1.
- _____, 1995b. *Environmental Baseline Survey, Fritzsche Army Airfield (FAAF) Parcel, Version 2.0*. January 24.
- _____, 1995c. *Draft Final Site Characterization, Site 35 – Fritzsche Army Airfield, Aircraft Cannibalization Yard, Fort Ord, California*. February 14.
- _____, 1995d. *Final Basewide Remedial Investigation/Feasibility Study, Fort Ord, California*. October.
- _____, 1996a. *Confirmation Report, Site 14 – 707th Maintenance Facility, Fort Ord, California*. February 12.
- _____, 1996b. *Interim Action Confirmation Report, Site 22 – 4400/4500 Motor Pool, West Block, Fort Ord, California*. May 22.
- _____, 1996c. *Draft Final Site Characterization, Site 24 – Old DEH Yard, Fort Ord, California*. March 22.
- _____, 1996d. *Confirmation Report Site 15 – Directorate of Engineering and Housing Yard, Fort Ord, California*. August 13.
- _____, 1997a. *Draft Final Site Investigation Report, Buildings 2253, 3803, 4362, and 4534, Former Fort Ord, California*. March 4.
- _____, 1997b. *Interim Action Confirmation Report, Site 24 – Old DEH Yard, Fort Ord, California*. January 23.
- _____, 1997c. *Draft Final Site Characterization, Site 23 – 3700 Motor Pool Complex, Fort Ord, California*. May 16.
- _____, 1997d. *Draft Final Site Investigation Report, Buildings 4107, 4110, and 4590 and Facility 2754, Former Fort Ord, California*. February 27.
- _____, 1997e. *Environmental Baseline Survey, Main Garrison Parcels, Former Fort Ord, California*. September 26.
- _____, 1998a. *Groundwater Well Management Plan Update, Former Fort Ord, California. Volume I – Text, Tables, Plates, and Attachments*. January 16.
- _____, 1998b. *Volume I – Site Investigation, Operable Unit 1 Plume Delineation, Former Fort Ord, California, and Volume II – Draft*

Work Plan for Preliminary Remediation Evaluation, Operable Unit 1 Plume Delineation, Former Fort Ord, California. April 29.

_____, 1999a. *Five-Year Status Report and Effectiveness Evaluation, OU 1 Groundwater Treatment System, Fort Ord, California.* June 29.

_____, 2000a. *Draft Final Literature Review Report, Ordnance and Explosives, Remedial Investigation/Feasibility Study, Former Fort Ord, California.* January 4.

_____, 2000b. *Track 0 Technical Memorandum, Ordnance and Explosives, Remedial Investigation/Feasibility Study, Former Fort Ord, California.* January 21.

_____, 2000c. *Track 0 Proposed Plan, Ordnance and Explosives, Remedial Investigation/Feasibility Study, Former Fort Ord, California.* February 1.

Human Factors Applications, Inc. (HFAI), 1994. *Volume I, OEW Sampling and OEW Removal Action, Fort Ord Final Report, Fort Ord, California.* December 1.

International Technology Corporation (IT), 1999a. *Remedial Action Confirmation Report and Post-Remediation Health Risk Assessment, Sites 16 and 17 Remedial Action, Basewide Remediation Sites, Former Fort Ord, California.* Draft final. April.

_____, 1999b. *Confirmation Report and Post-Remediation Health Risk Assessment, Site 12 Remedial Action, Remediation Sites, Fort Ord, California.* Draft final. June.

_____, 1999c. *Draft Remedial Action Confirmation Report, Area A, Operable Unit 2 Landfills, Former Fort Ord, California.* March.

Little, A.D., 1994. *Community Environmental Response Facilitation Act (CERFA) Report, Fort Ord, Monterey, California.* Prepared for U.S. Army Environmental Center Aberdeen Proving Ground, Maryland. April.

Stickler, L., 1999. Former Range Control Officer, U.S. Department of the Army. Interview with Jeff Fenton, Harding Lawson Associates. July 29.

Tri-Services Cultural Resources Research Center (TSCRRC), 1993. *Historical and Architectural Documentation Reports for Fort Ord, California.* September. (Conducted for the Office of Directorate of Environmental Programs Conservation Division.)

Uribe & Associates, 1998. *Interim Action Confirmation Report, Site 34 – Fritzsche Army Airfield Fueling Facility, Former Fort Ord, California.* September.

USA Environmental Inc. (USA), 1999. *OE Sampling After Action Report Site OE-1, Inland Range Contact, Former Fort Ord, California.* August 26.

U.S. Army Corps of Engineers (USACE), 1946. *Master Plan, Fort Ord, California.* Volume I. Sheet No. 2, Drawing No. 53-1-9: Reservation Boundary and Land Use Map. U.S. Engineer Office: San Francisco.

_____, 1961. *Master Plan, Fort Ord, California.* Drawing No. 2B: Map of Basic Information, Training Facilities. June 30.

_____, 1968. *Master Plan, Basic Information Maps.* Sheet 5 of 5, Drawing No. 18-02-27: Training Facilities Map. March.

_____, 1974. Aerial photograph set of portion of Fritzsche Army Airfield, Intergarrison Area, Main Garrison, and Inland Ranges. Photograph 186-1 through -17 and 186-1 through -4. May 10 and October 18.

_____, 1976. *Master Plan, Future Development Plans, Training Facility Plan.* Drawing No. 18-04-128. December 1.

_____, 2000. *Ordnance and Explosives, Remedial Investigation/Feasibility Study Work Plan, Former Fort Ord, Monterey County, California.* Draft Final May 15.

- _____, 2000. Memorandum Describing Landfill Related OE Finds. July 31.
- _____, 2001. Support Documentation, Potential OE Issues, Parcel E4.3.1, Finding of Suitability for Early Transfer, Housing Areas and Former Garrison Parcels, Former Fort Ord, California. May.
- U.S. Army Engineer Division, Huntsville (USAEDH), 1997a. *Engineering Evaluation/Cost Analysis—Phase 1, Former Fort Ord, Monterey County, California*. Final. September.
- _____, 1997b. *Revised Archives Search Report, Former Fort Ord, California, Monterey County, California*. Prepared by U.S. Army Corps of Engineers St. Louis District.
- U.S. Department of Agriculture, Soil Conservation Service (SCS), 1949. Aerial photograph set of Fort Ord. Photographs ABG-17F-87, -129, -131, -133, -193, and -195. August 17.
- _____, 1956. Aerial photograph of southeastern Inland Ranges. Photograph ABG-23R-85.
- _____, 1966. Aerial photograph set of Fort Ord. Photographs ABG-1GG-45-53, 128-133. June 2.
- U.S. Department of the Army (Army), 1940a. Fort Ord Locator Map. File Number 228-10.
- _____, 1940b. Camp Ord, Ultimate Layout of Concurrent Training Camps. June 20.
- _____, 1945. Map of Training Facilities, Fort Ord and Vicinity. August.
- _____, circa 1954. Map: Fort Ord. Inclosure [sic] 1 to Appendix A, to Annex 0.
- _____, 1956. Map of Fort Ord Training Areas and Facilities, Inclosure [sic] 1 to Annex 0. Revised December 20, 1956.
- _____, 1957. Map of Fort Ord Training Areas and Facilities, Enclosure 1 to Annex "H" July 15.
- _____, 1958. Map of Fort Ord Training Areas and Facilities, Inclosure [sic] 1 to Appendix 1 to Annex H. January 10.
- _____, 1964. *Fort Ord Regulation 350-70*. Appendix 2, Annex O: Field Training Areas and Range Map, Fort Ord. April 27.
- _____, 1967. *Fort Ord Regulation 350-72* Field Training Areas & Range Map, Appendix 2, Annex 0. January.
- _____, 1992. *Standard Operating Procedures, Leadership Reaction Course* Fort Ord Pamphlet No. 350-5. Fort Ord, California. October 7.
- _____, 1998a. *Finding of Suitability to Transfer (FOST), Fritzsche Army Airfield Phase II Parcels, Former Fort Ord, California*. August 13.
- _____, 1998b. *Finding of Suitability to Transfer (FOST), Reservation Road Parcels, Former Fort Ord, California*. May 5.
- _____, 2001a. Letter to U.S. EPA and California Department of Toxic Substances Control, August 8, regarding *Technical Memorandum Support Documentation, Potential OE Issues, Parcel E4 3 1, Finding of Suitability For Early Transfer, Housing Areas and Former Garrison parcels, Former Fort Ord*.
- _____, 2001b. Letter to U.S. EPA and California Department of Toxic Substances Control regarding EOD response at 1611 Chosin Court. November 27.
- _____, 2002. Letter to U.S. EPA and California Department of Toxic Substances Control regarding research write-ups on fifteen EOD responses and three additional incidental finds. June 3.
- UXB International Inc., (UXB), 1995. *Final Report for Ordnance and Explosives Removal Action, OE Cache, Fort Ord, California*. November 1.

TABLE

Table 1. Track 0 Parcel Groupings

Track 0 Parcel Groupings	Parcels	Description
Highway 1	S4 1 2 1 S4 1 2 2 S4 1 3 S4 1 4 S4 1 5	These parcels make up Highway 1 and the right of ways (ROW) Highway 1 was in place before the establishment of Fort Ord There is no evidence to suggest the use of ordnance on these parcels
Golf Course	F2 7 2	This parcel was developed at the time of the golf course construction in 1953 There is no evidence of ordnance use prior to construction of the golf course
Brostrom Park	L27	This parcel is adjacent to the City of Seaside Housing was built on the parcel in 1941 or 1942 The parcel was part of the 1940 land purchase There is no evidence to suggest the use of ordnance on these parcels
Patton/Abrams Park Housing	E2c 1 E4 1 1 E4 2 E4 3 1 1* E4 5 E5a (*portion)	Parcels include the Patton and Abrams Park Housing Areas constructed in 1962-1969 and 1978-1982, respectively Prior to construction of the housing areas, portions of the parcels were used for non-ordnance weapons training, set-up, and physical training (i e , Mortar Square, Wire Entanglement Area, and the Proficiency Test Area) Adjacent Area A landfill, including a portion of adjacent Site OE-13A were completely excavated The excavated area is not included in this ROD There is no evidence to suggest the use of ordnance on these parcels
Open Space Main Entrance	E15 1 L33 1 L33 2 S1 4	These parcels are mostly open space areas near the Fort Ord entrance Portions of these parcels were developed at the time of the 1940 land purchase (e g , Parade Ground/airfield) The parcels were used for physical training, and weapons training and set-up (i e , Machine Gun Square, Rifle Instruction Circle) Secondary development included some building and paving (L33 1 and L33 2) Large portions of the parcels were investigated for chemical contamination under the RI/FS program (IRP Sites 20, 23, and 24) and the UST program (e g , overexcavation of UST 3803) Numerous site walks under a variety of programs have been conducted on these parcels There is no evidence to suggest the use of ordnance on these parcels

Table 1. Track 0 Parcel Groupings

<p>Surplus II</p>	<p>L1.1 L19.2 L19.3 L19.4 L32.2.1 L32.2.2 L32.3 L32.4.1.1 L32.4.1.2 L32.4.2 L23.6 L36 L37 L15.1 L7.8 L7.9 L2.4.2 L2.4.3.1 L2.4.3.2 S1.3.1</p>	<p>This area was included in the 1940 property acquisition. The original property included physical training areas. The area later developed (large portion paved) to include troop housing and motor pools. A portion was investigated for chemical contamination under the RI/FS program (IRP Sites 22). There is no evidence to suggest ordnance training. Numerous site walks under a variety of programs have been conducted on these parcels.</p>
<p>Fritzsche Army Airfield</p>	<p>S2.1.3 S2.1.4.1 S2.1.4.2 L5.1.2 L5.1.3 L5.1.4 L5.1.5 L5.1.6 L5.1.7 L5.1.8 L5.1.9 L5.1.10 L5.2 L5.3 F7.1 F7.2</p>	<p>These parcels were included in the 1940 land purchase. Parcels include support buildings related to the FAAF, water supply wells, and a former sewage treatment plant. With the exception of the water supply wells and two airport transmission beacons, these parcels consist of areas investigated for chemical contamination under the RI/FS program (IRP Sites 34, 36, and 40) and the UST program. No specific training activities occurred on the parcels; however, some of the parcels do fall within larger non-firing or non-OE training areas (e.g., the Tank Ranging Area, a tank driving area, and a Basic Driving and Field Communication Course), which were in use prior to construction of the FAAF. There is no evidence to suggest the use of ordnance on these parcels.</p>

Table 1. Track 0 Parcel Groupings

<p>East Garrison</p>	<p>E11b.1 E11b.2 E11b.3 E11b.4 L20.14.1.2 L20.19.2 L20.20 L20.21.1 L20.21.2 L20.22 L23.3.1 L23.3.2.1 L35.3 L35.6 L35.7 L35.8</p>	<p>These parcels were included in the original land purchase in 1917 and include some of the earliest construction at Fort Ord. The area was used as an encampment for troops stationed at the Presidio of Monterey. Troops utilized nearby small arms ranges as well as Inland Ranges to the southwest. Later training at these parcels included use of a skeet range, physical training area (Leadership Reaction Course), and Heavy Vehicle Driver Training Course. Several areas within these parcels were investigated for chemical contamination under the RI/FS program (IRP Sites 29, 30, 32, and 39A). Numerous site walks under a variety of programs have been conducted on these parcels. No evidence suggests ordnance use.</p>
<p>OU 2 Landfill</p>	<p>E2e.1 E2e.2 S1.3.3 E8a.1.2 E8a.1.3 E8a.1.4 E8a.1.5 S2.5.1.1 S2.5.1.2 S2.5.2.1* S2.5.2.2* (*portion)</p>	<p>This area consists of open space excluding the OU 2 Landfill. Portions of these parcels were used for various nonordnance training activities including a Rifle Instruction Circle, Camouflage Area, and Obstacle Course. There is no evidence to suggest the use of ordnance on these parcels. The area of landfill disposal has been capped and is not included in this ROD.</p>

Table 1. Track 0 Parcel Groupings


Track 0 Parcel Groupings	Parcels	Description
Main Garrison	E2b 1 1 1 E2b 1 2 E2b 1 1 2 E2b 1 3 E2b 1 4 E2b 1 5 E2b 2 1 E2b 2 2 E2b 2 3 E2b 2 4 E2b 2 5 E2b 3 1 1 E2b 3 2 E2c 2 E2c 3 1 E2c 3 2 E2c 3 3 E2c 4 1 1 E2c 4 2 1 E2d 1 E2d 2 E17 L2 1 L12 2 2 L12 2 3 L12 3 L23 1 1 L23 1 2 L23 1 3 L23 1 4 L23 1 5 L35 1 L35 2 L20 16 1 L20 16 2 L20 16 3 S1 5 1 1 S1 5 1 2 S1 5 2 L23 4 L2 2 1 L5 8 1 L5 8 2 L20 17 1	These parcels include portions of Fort Ord acquired at the time of the original land purchase in 1917 and subsequent purchase in 1940. Construction began in this area in 1940 and included some of the oldest development and construction. The facilities included troop housing, support facilities, and physical training areas. There is no evidence to suggest ordnance use on these parcels. Large portions of this area are paved. Several investigations related to potential chemical contamination have taken place on these parcels (IRP Sites 12, 13, 14, 15, 16, 17, 18, 19, 25, 28, and 38, USTs 1483, 1685, 1697, 2253, 2754, 3004, and 3016). Numerous site walks under a variety of programs have been conducted on these parcels.

Table 1. Track 0 Parcel Groupings


Track 0 Parcel Groupings	Parcels	Description
Reservation Road	L5 10 L20 10 1 1 L20 10 1 2 L20 10 2 L20 10 3	Prior to the acquisition of the property by the Army in 1940, Reservation Road was an unimproved Monterey County Road extending from Highway 1 to the East Garrison. The road continued around the perimeter of Fort Ord to Salinas. There is no evidence of ordnance training occurring on or alongside Reservation Road.

FIGURE

Figure 1. Track 0 ROD Process and Track 0 Plug-in Process



PLATES



Base apr 5/3/02 trac10rod-plate1



Harding Lawson Associates
Engineering and
Environmental Services

DRAWN
TJH

JOB NUMBER
46310 001751

APPROVED


Location Map - Former Fort Ord
Track 0 Record of Decision
No Further Action Regarding
Ordinance-Related Investigation
Former Fort Ord, Monterey, California

DATE
7/00


PLATE

1

REVISED DATE




EXPLANATION
 S 1 TRACK/PARCE AND
 [] PARCEL NUMBER



EXPLANATION

- S4 13 TRACK 0 PARCEL WITH PARCEL NUMBER
- OE-22 OE SITE BOUNDARY AND SITE NAME
- MACHINE GUN SQUARE



3000 0 3000 Feet

Note This plate shows the Track 0 parcels for the parcel group described in the plate title Plate 2 shows all Track 0 parcels identified in the ROD

trackRod apr 7/25/00 - layout 7-3



Harding Lawson Associates
 Engineering and
 Environmental Services


DRAWN TJH
 JOB NUMBER 46310 001751

Highway 1 Parcels
 Track 0 Record of Decision
 No Further Action Regarding
 Ordnance-Related Investigation
 Former Fort Ord, Monterey, California

APPROVED
 DATE 7/00

PLATE
3

REVISED DATE



Note This plate shows the Track 0 parcels for the parcel group described in the plate title Plate 2 shows all Track 0 parcels identified in the ROD



Harding Lawson Associates
Engineering and Environmental Services

DRAWN TJH
JOB NUMBER 46310 001751

Brostrom Park and Golf Course Parcels
Track 0 Record of Decision
No Further Action Regarding
Ordinance-Related Investigation
Former Fort Ord, Monterey California


APPROVED DATE 7/00
REVISED DATE

PLATE

4

REVISED DATE


track0rod apr layout 2 4 7/25/00



EXPLANATION

- L5.6.1 TRACK 0 PARCEL WITH PARCEL NUMBER
- OE-13A OE SITE BOUNDARY AND SITE NAME
- EXTENT OF EXCAVATED AND GRADED LANDFILL AREA (AREA A)
- MORTAR SQUARE

Note: This plate shows the Track 0 parcels for the parcel group described in the plate title. Plate 2 shows all Track 0 parcels identified in the ROD.



Harding Lawson Associates
 Engineering and Environmental Services

DRAWN: TJH
 JOB NUMBER: 46310 001751

Patton/Abrams Park Housing Area Parcels


Track 0 Record of Decision
 No Further Action Regarding
 Ordnance-Related Investigation
 Former Fort Ord, Monterey, California

APPROVED: _____
 DATE: 7/00

PLATE

5


REVISED DATE: 5/02



EXPLANATION

- S4.1.3 TRACK 0 PARCEL WITH PARCEL NUMBER
- OE-20 OE SITE BOUNDARY AND SITE NAME
- RIFLE INSTRUCTION CIRCLE
- MACHINE GUN SQUARE
- IRP SITE
- OE GRIDS

Note: This plate shows the Track 0 parcels for the parcel group described in the plate title. Plate 2 shows all Track 0 parcels identified in the ROD.



Harding Lawson Associates
Engineering and
Environmental Services

DRAWN TJH
JOB NUMBER 46310 001751


Open Space - Main Entrance Parcels
Track 0 Record of Decision
No Further Action Regarding
Ordnance-Related Investigation
Former Fort Ord, Monterey, California

APPROVED
DATE 7/00

PLATE

6

REVISED DATE



Note: This plate shows the Track 0 parcels for the parcel group described in the plate title. Plate 2 shows all Track 0 parcels identified in the ROD.

Fort Ord GIS - track0rod.apr - Plate 9 East Garrison Parcels Layout - 5/29/02



Harding Lawson Associates
Engineering and
Environmental Services

East Garrison Parcels
Track 0 Record of Decision
No Further Action Regarding
Ordnance-Related Investigation
Former Fort Ord, Monterey, California

PLATE

9


DRAWN
JCB

JOB NUMBER
46310 001751

APPROVED

DATE
7/00

REVISED DATE
5/02



EXPLANATION

- L23.1.4 TRACK 0 PARCEL WITH PARCEL NUMBER
- OE-2 OE SITE BOUNDARY AND SITE NAME
- EXCAVATED LANDFILL AREAS
- RIFLE INSTRUCTION CIRCLE
- MORTAR SQUARE
- IRP SITE

Note: This plate shows the Track 0 parcels for the parcel group described in the plate title. Plate 2 shows all Track 0 parcels identified in the ROD.




Harding Lawson Associates
Engineering and Environmental Services

DRAWN: TJH
JOB NUMBER: 46310 001751

Main Garrison Parcels
Track 0 Record of Decision
No Further Action Regarding
Ordnance-Related Investigation
Former Fort Ord, Monterey, California

APPROVED: _____
DATE: 7/00


PLATE
10
REVISED DATE



EXPLANATION

- E2e.2 TRACK 0 PARCEL WITH PARCEL NUMBER
- OE-7 OE SITE BOUNDARY AND SITE NAME
- RIFLE INSTRUCTION CIRCLE

Note: This plate shows the Track 0 parcels for the parcel group described in the plate title. Plate 2 shows all Track 0 parcels identified in the ROD.



Harding Lawson Associates

Engineering and Environmental Services

DRAWN TJH
JOB NUMBER 46310 001751

OU2 Landfill Parcels

Track 0 Record of Decision
No Further Action Regarding
Ordnance-Related Investigation
Former Fort Ord, Monterey, California


APPROVED

DATE 7/00

PLATE

11

REVISED DATE



Note: This plate shows the Track 0 parcels for the parcel group described in the plate title. Plate 2 shows all Track 0 parcels identified in the ROD.

Fort Ord GIS TrackOrd apr - Plate 12 Reservation Road Layout - 5/29/02



Harding Lawson Associates
Engineering and
Environmental Services

Reservation Road Parcels
Track 0 Record of Decision
No Further Action Regarding
Ordnance-Related Investigation
Former Fort Ord, Monterey, California

PLATE

12

DRAWN JCB	JOB NUMBER 46310 001751	APPROVED	DATE 7/00	REVISED DATE 5/02
--------------	----------------------------	----------	--------------	----------------------

EXAMPLE TRACK 0 CHECKLIST

PARCEL	List of Reuse Parcel Numbers included in the parcel group
DESCRIPTION	Name of parcel group, size and plate reference for the location map.
HISTORICAL USE	Chronological listing of the use of the property list in the parcel group.
Supporting documents	List of documents reviewed to determine the historical use.
<u>Components</u>	
Aerial Photos	List of the aerial photos reviewed for the parcel group.
Real Estate Records	List of the real estate records reviewed for the parcel group.
Range Control Records/ Standard Operating Procedures	List of any records from the range control office or standard operating procedures or manuals, which may pertain to activities, conducted within the parcel group.
Range and Training Area Maps	List of title and date of maps showing ranges and training area which were reviewed.
Base Development Plans and Maps	List of the title and date of maps showing the chronology of development at Fort Ord.
SITE INVESTIGATION ACTIVITIES	
Site Walks	List of site walks conducted within the parcel group.
Geophysics	List of geophysical surveys conducted within the parcel group.
Excavations	List of any soil excavation conducted within the parcel group.
Soil Borings	List of the number and reference for soil borings conducted within the parcel group.

Wells List of water supply wells and groundwater monitoring wells located within the parcel group.

ADJACENT AREAS

CBR Training Areas List of Chemical, Biological and Radiological (CBR) Training Areas located adjacent to the parcel group.

CWM Training Areas List of Chemical Warfare Materiel (CWM) Training Areas located adjacent to the parcel group.

Small Arms Ranges List of Small Arms Ranges located adjacent to the parcel group.

OE INFORMATION

Known or Suspected Adjacent OE Sites List of Ordnance and Explosives (OE) Sites located adjacent to the parcel group.

**Incident Reports
UXO** List of incident reports where unexploded ordnance was found.

OE Scrap List of incident reports where OE scrap was found.

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	-------------

TRACK 0 CHECKLIST Highway 1 Parcels

PARCEL	S4.1.2.1, S4.1.2.2, S4.1.3, S4.1.4, and S4.1.5 – Highway 1 Area
DESCRIPTION	Approximately 161 acre portion of Highway 1 (Plate 3).
HISTORICAL USE	<p>History suggests no OE used</p> <p>Prior to Army purchase, the land included ranch land, Highway 1 and the Southern Pacific railway.</p> <p>1940: Army purchased the parcels with the exception of Parcel S4.1.3 which was included in land donated to the Army. Army begins establishment of the Beach Ranges (Site OE-22) adjacent to the parcels.</p> <p>1940s: Improvements made to Highway 1 including widening.</p> <p>1956: Machine Gun Square established on Parcel S4.1.2.1 in the approximate location of the future main entrance. Site OE-20, a recoilless rifle training area, is established adjacent to Parcel S4.1.2.1.</p> <p>1958: Machine Gun Square and recoilless rifle training area no longer shown on training facilities maps.</p> <p>About 1972: Highway 1 improvements including widening, relocation of portions of the Southern Pacific railway and the creation of an off ramp for a new Fort Ord main entrance.</p>
Supporting documents	Literature Review and Base Inventory Report, Volume 1; Community Environmental Response Facilitation Act (CERFA) Report; Archives Search Reports; OE RI/FS Literature Review; OEW Sampling and OEW Removal Action; Sampling/Characterization After Action Report, Site OE-22 (Beach Ranges).
<u>Components</u>	
Aerial Photos	Pre-1940, 7/25/41, 10/14/41, 8/17/49, 6/23/51, 7/3/51, 5/14/56, 58/59 (aerial contours), 1/11/65

	(mosaic), 6/3/66, 3/13/69, 12/17/75, 4/13/85, 10/22/85, 3/25/86, 11/4/88, 10/4/89, 7/6/92
Real Estate Records	1913 Department of the Interior, reprinted 1918 1915 Proposed Acreage Subdivisions 1922 Assessors Plats, Monterey County 3/18/88 Real Estate, Fort Ord
Range Control Records/ Standard Operating Procedures	Not applicable to this area
Range and Training Area Maps	8/45 Training Facilities Circa 1954 Training Areas that Cannot Be Used at the Same Time 7/3/56 Range Complex 12/20/56 Fort Ord Training Areas & Facilities 7/15/57 Training Areas & Facilities 1/10/58 Training Areas & Facilities 12/31/58 Ranges & Training Facilities 6/30/61 Training Facilities 4/27/64 Field Training Areas & Range Map 8/16/65 Close In Training Areas 1/67 Field Training Areas & Range Map 5/1/67 Close In Training Areas 3/13/68 Training Facilities Map 11/1/71 Training Facilities Plan 3/16/72 Training Ranges and General Road Map 7/1/72 Field Training Area and Range Map 2/23/73 Close In Training Areas 2/1/76 Ranges and Training Area Overlay 12/1/76 Future Development Plans, Training Facilities Plan 3/1/76 Close In Training Areas 6/1/77 Training Facilities Plan 1/78 Ranges and Training Area Overlay 7/15/78 Ranges and Training Area Overlay 3/80 Training Facilities Map 6/1/81 Ranges and Training Area Overlay 4/1/82 Ranges and Training Area Overlay 4/27/84 Field Training Areas and Range Map 6/84 Training Facilities Map 11/15/87 Ranges and Training Area Overlay
Base Development Plans and Maps	1922 Assessors Plats, Monterey Co 1934 War Department, Camp Ord and Vicinity 1940 Fort Ord Locator Map 1944 Army Map Service, Fort Ord Military Reservation 7/3/44 Fire Hydrants & Fire Telephones, Main Garrison

3/20/46 Fort Ord Master Plans
 4/5/46 Fort Ord Master Plans
 2/56 Main Garrison Layout
 1/15/69 Post Locator Map
 1972 Fort Ord and Vicinity (V895S)
 3/1/75 Master Plan, Reservation Map
 8/1/84 Fort Ord Military Installation Map
 (V795S)
 1985 Fort Ord Locator Map
 2/10/90 Fort Ord Locator Map, Main Garrison

SITE INVESTIGATION ACTIVITIES

Site Walks	None
Geophysics	None
Excavations	None
Soil Borings	None
Wells	Water supply wells: 1, Parcel S4.1.2.1 (Cal Trans well, status unknown)

ADJACENT AREAS

CBR Training Areas	None
CWM Training Areas	None
Small Arms Ranges	Small arms ranges to the west of the parcels (Beach Ranges). Firing was to the west away from the parcels.

OE INFORMATION

Known or Suspected Adjacent OE Sites

Site OE-20 – Sampling of this site (a recoilless rifle training area) was conducted and no evidence of OE was found (Plate 3). This site will undergo additional evaluation in the OE RI/FS.

Site OE-22 – Sampling of this site (Beach Ranges) was conducted and no OE was found. OE scrap items found during the sampling included an inert training grenade, an expended smoke grenade and an empty un-fuzed Japanese-made mortar. No further action was recommended for this site. This site will undergo additional evaluation in the OE RI/FS.

Incident Reports
UXO
OE Scrap

None
None

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	-------------

TRACK 0 CHECKLIST
Golf Course Maintenance Yard

PARCEL	F2.7.2 – Golf Course Maintenance Area
DESCRIPTION	Golf Course Maintenance Yard Approximately 2 acres (Plate 4).
HISTORICAL USE	No evidence to suggest OE use Ranch land (Noche Buena Rancho) prior to Army purchase 1940: Army acquired 1940-1952: Undeveloped 1953: Construction of golf course completed
Supporting documents	Literature Review and Base Inventory Report, Volume 1; Community Environmental Response Facilitation Act (CERFA) Report; Archives Search Reports; OE RI/FS Literature Review; Site Characterization, Site 33 – Golf Course; Site Investigation Report, Buildings 4107, 4110, and 4590 and Facility 2754; Field Investigation and Data Review, Solid Waste Management Units; Finding of Suitability To Transfer, Golf Course Parcel, Phase II
<u>Components</u>	
Aerial Photos	Pre-1940, 7/3/51, 5/14/56, 5/8/59 (aerial contours); 1/11/65 (mosaic), 6/3/66, 3/13/69, 12/17/75, 3/25/86, 11/4/88, 10/4/89, 7/6/92.
Real Estate Records	1913 Department of the Interior, reprinted 1918 1915 Proposed Acreage Subdivisions 1922 Assessors Plats, Monterey County 3/18/88 Real Estate, Fort Ord
Range Control Records/ Standard Operating Procedures	Not applicable to this area
Range and Training Area Maps	8/45 Training Facilities Circa 1954 Training Areas that Cannot Be Used at the Same Time 7/3/56 Range Complex 12/20/56 Training Areas & Facilities 7/15/57 Training Areas & Facilities

1/10/58 Training Areas & Facilities
 12/31/58 Ranges & Training Facilities
 4/27/64 Field Training Areas & Range Map
 1/67 Field Training Areas & Range Map
 3/13/68 Training Facilities Map
 11/1/71 Training Facilities Plan
 3/16/72 Training Ranges and General Road Map
 1/7/72 Field Training Area and Range Map
 2/23/73 Close In Training Areas
 2/1/76 Ranges and Training Area Overlay
 12/1/76 Future Development Plans, Training
 Facilities Plan
 6/1/77 Training Facilities Plan
 1/78 Ranges and Training Area Overlay
 7/15/78 Ranges and Training Area Overlay
 3/80 Training Facilities Map
 6/1/81 Ranges and Training Area Overlay
 4/1/82 Ranges and Training Area Overlay
 4/27/84 Field Training Areas and Range Map
 6/84 Training Facilities Map
 11/15/87 Ranges and Training Area Overlay

Base Development Plans and Maps

1922 Assessors Plats, Monterey Co.
 1934 War Department, Camp Ord and Vicinity
 1944 Army Map Service, Fort Ord Military
 Reservation
 3/20/46 Main Garrison Cantonment Land Use
 4/5/46 Fort Ord Master Plan, Reservation
 Boundary & Land Use Maps
 1972 Fort Ord and Vicinity Map
 3/1/75 Master Plan, Reservation Map
 8/1/84 Fort Ord Military Installation Map
 (V795S)
 2/10/90 Fort Ord Locator Map, Main Garrison

SITE INVESTIGATION ACTIVITIES

Site Walks

HTW program: Site walk completed in support
 of the IRP Site 33 (see cross-hatched area on
 Plate 4) investigation (see IRP Site 33
 characterization report)

UST Management Program: Oversight of UST
 4110.1 over excavation (see UST 4110
 investigation report)

SWMU investigation: Inspection of solid waste
 management unit FTO-071 (see Field

	Investigation and Data Review Solid Waste Management Units for location)
	EBS/FOST: Visual site inspection of parcel in support of property transfer
Geophysics	Borehole clearance, UST investigation (see IRP Site 33 and UST 4110 investigation reports)
Excavations	Building construction 1953 & 1962. UST 4110.1 removal and over excavation (see UST 4110 investigation report)
Soil Borings	HTW program: 8 borings (see IRP Site 33 characterization report for locations)
	UST Management Program: 11 soil borings (see UST 4110 investigation report for locations)
Wells	None

ADJACENT AREAS

CBR Training Areas	None
CWM Training Areas	None
Small Arms Ranges	None

OE INFORMATION

Known or Suspected Adjacent OE Sites	None
Incident Reports	
UXO	None
OE Scrap	None

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	-------------

TRACK 0 CHECKLIST
Brostrom Park

PARCEL	L27 – Brostrom Park Area
DESCRIPTION	Brostrom Park Approximately 52 acres (Plate 4).
HISTORICAL USE	No evidence to suggest OE use Prior to Army purchase this area was ranch land (Noche Buena Rancho) purchased by the Army after July 1 1940. 1941-42: Ord Village housing constructed. Two water supply wells installed in 1941. Housing constructed to the north (Hayes Park) in 1952. Early 1960s: Ord Village was demolished, Seaside High School constructed on land that contained the western half of Ord Village. Baseball field constructed between 1966 and 1969 on the parcel 1984: Brostrom Park housing area constructed.
Supporting documents	Literature Review and Base Inventory Report, Volume 1; Community Environmental Response Facilitation Act (CERFA) Report; Archives Search Reports; OE RI/FS Literature Review; Site Characterization, Site 37 – Trailer Park Maintenance Shop; Finding Of Suitability To Transfer, Brostrom Park
<u>Components</u>	
Aerial Photos	Pre-1940, 8/18/49, 7/3/51, 5/14/56, 5/8/59 (aerial contours), 1/11/65 (mosaic), 6/3/66, 3/13/69, 12/17/75, 6/16/78, 3/25/86, 11/4/88, 10/4/89, 7/6/92.
Real Estate Records	1913 Department of the Interior, reprinted 1918 1915 Proposed Acreage Subdivisions 1922 Assessors Plats, Monterey County 3/18/88 Real Estate, Fort Ord
Range Control Records/ Standard Operating Procedures	Not applicable to this area

Range and Training Area Maps

8/45 Training Facilities
 Circa 1954 Training Areas that Cannot Be Used at the Same Time
 7/3/56 Range Complex
 12/20/56 Fort Ord Training Areas & Facilities
 7/15/57 Training Areas & Facilities
 1/10/58 Training Areas & Facilities
 12/31/58 Ranges & Training Facilities
 4/27/64 Field Training Areas & Range Map
 1/67 Field Training Areas & Range Map
 3/13/68 Training Facilities Map
 11/1/71 Training Facilities Plan
 3/16/72 Training Ranges and General Road Map
 1/7/72 Field Training Area and Range Map
 2/23/73 Close In Training Areas
 2/1/76 Ranges and Training Area Overlay
 12/1/76 Future Development Plans, Training Facilities Plan
 6/1/77 Training Facilities Plan
 1/78 Ranges and Training Area Overlay
 7/15/78 Ranges and Training Area Overlay
 3/80 Training Facilities Map
 6/1/81 Ranges and Training Area Overlay
 4/1/82 Ranges and Training Area Overlay
 4/27/84 Field Training Areas and Range Map
 6/84 Training Facilities Map
 11/15/87 Ranges and Training Area Overlay

Base Development Plans and Maps

1922 Assessors Plats, Monterey Co.
 1934 War Department, Camp Ord and Vicinity
 1944 Army Map Service, Fort Ord Military Reservation
 3/20/46 Ord Village, General Road Map
 4/5/46 Fort Ord Master Plan, Reservation Boundary & Land Use Maps
 1972 Fort Ord and Vicinity (V895S)
 3/1/75 Master Plan, Reservation Map
 8/1/84 Fort Ord Military Installation Map (V795S)
 2/10/90 Fort Ord Locator Map, Main Garrison

SITE INVESTIGATION ACTIVITIES

Site Walks

HTW program: Site walk completed in support of the IRP Site 37 investigation (see cross-hatched area on Plate 4)

EBS/FOST: Visual site inspection of parcel in support of property transfer

Geophysics	In support of borehole clearance (see Site 37 characterization report)
Excavations	Development/housing construction (Ord Village) adjacent to the parcel beginning in 1941. Demolition of Ord Village and the construction of Seaside High School on that location in the early 1960s. Construction of baseball field between 1966 and 1969. Construction of the Brostrom Park housing in 1984.
Soil Borings	HTW: 3 borings (see Site 37 Characterization Report for locations)
Wells	Water supply wells: 2 (one destroyed in 1989; one sealed, date unknown) HTW monitoring wells: 2 (see Brostrom Park FOST for locations).

ADJACENT AREAS

CBR Training Areas	None
CWM Training Areas	None
Small Arms Ranges	None

OE INFORMATION

Known or Suspected Adjacent OE Sites	None
Incident Reports:	
UXO	None
OE Scrap	None

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	-------------

TRACK 0 CHECKLIST

Patton/Abrams

PARCEL	E2c.1, E4.1.1, E4.2, E4.5, E5a and a portion of E4.3.1.1 – Patton/Abrams Park Housing Area
DESCRIPTION	Approximately 460 acre housing area (Plate 5).
HISTORICAL USE	<p>History suggests no OE used.</p> <p>Prior to Army purchase this area was ranch land (David Jacks Corporation) purchased by the Army after July 1, 1940.</p> <p>Water supply well drilling and installation began in 1940 (Parcel E4.1.1) and continued in the mid 1940s and 1950s (Parcel E4.2, E4.5 and E4.3.1.1) and the 1960s (Parcel E4.3.1.1)</p> <p>1944: North Parade Ground constructed (Parcel E2c.1)</p> <p>1945: Wire Entanglement training area established (Parcel E4.2)</p> <p>1952-1954: Mortar Square 3 training area (Parcel E4.1.1) and Proficiency Test Area #2 (Parcel E4.1.1) established</p> <p>About 1954: Practice Mortar Range, OE Site 13A established (Parcels L5.6.1 and L5.6.2)</p> <p>About 1955: Water tank and water treatment facility constructed (Parcel E4.5)</p> <p>1956-1966: Area A Landfill in use (Parcels L5.6.1 and L5.6.2)</p> <p>1962-1969: Patton Park Housing constructed (Parcels E4.1.1 and E4.2)</p> <p>1964-1972: Light vehicle driving course (Parcel E5a)</p> <p>1978-1982: Abrams Park Housing constructed (Parcels E4.3.1.1 and L5.6.2)</p>
Supporting documents	<p>Literature Review and Base Inventory Report, Volume 1; Community Environmental Response Facilitation Act (CERFA) Report; Archives Search Reports; OE RI/FS Literature Review; Destruction Record, Fort Ord Water Supply Wells; After Action Report, OE Gridstats Sampling, Site OE-13A; OE Sampling After Action Report, Site OE-1; OEW Sampling and OEW Removal Action; Predesign Technical Memorandum, Operable Unit 2, Fort Ord</p>

Landfills; Remedial Action Confirmation Report, Area A, Operable Unit 2 Landfills;

Components

Aerial Photos

Pre-1940, 7/25/41, 10/14/41, 8/17/49, 6/23/51, 7/3/51, 5/14/56, 58/59 (aerial contours), 1/11/65 (mosaic), 5/2/66, 12/17/75, 6/16/78, 4/13/85, 10/22/85, 3/25/86, 11/12/86, 11/4/88, 10/4/89, 7/6/92

Real Estate Records

1913 Department of the Interior, reprinted 1918
1915 Proposed Acreage Subdivisions
1922 Assessors Plats, Monterey County
3/18/88 Real Estate, Fort Ord

**Range Control Records/
Standard Operating Procedures**

Not applicable to this area

Range and Training Area Maps

8/45 Training Facilities
Circa 1954 Training Areas that Cannot Be Used at the Same Time
7/3/56 Range Complex
12/20/56 Fort Ord Training Areas & Facilities
7/15/57 Training Areas & Facilities
1/10/58 Training Areas & Facilities
12/31/58 Ranges & Training Facilities
4/27/64 Field Training Areas & Range Map
8/16/65 Close In Training Areas
1/67 Field Training Areas & Range Map
5/1/67 Close In Training Areas
3/13/68 Training Facilities Map
11/1/71 Training Facilities Plan
3/16/72 Training Ranges and General Road Map
7/1/72 Field Training Area and Range Map
2/23/73 Close In Training Areas
2/1/76 Ranges and Training Area Overlay
12/1/76 Future Development Plans, Training Facilities Plan
3/1/76 Close In Training Areas
6/1/77 Training Facilities Plan
1/78 Ranges and Training Area Overlay
7/15/78 Ranges and Training Area Overlay
3/80 Training Facilities Map
6/1/81 Ranges and Training Area Overlay
4/1/82 Ranges and Training Area Overlay
4/27/84 Field Training Areas and Range Map
6/84 Training Facilities Map
11/15/87 Ranges and Training Area Overlay

Base Development Plans and Maps

1922 Assessors Plats, Monterey Co.
 1934 War Department, Camp Ord and Vicinity
 1944 Army Map Service, Fort Ord Military
 Reservation
 1944 Fire Hydrant Map
 3/20/46 Fort Ord Master Plans
 4/5/46 Fort Ord Master Plans
 2/56 Main Garrison Layout
 1/15/69 Post Locator Map
 1972 Fort Ord and Vicinity (V895S)
 3/1/75 Master Plan, Reservation Map
 8/1/84 Fort Ord Military Installation Map
 (V795S)
 2/10/90 Fort Ord Locator Map, Main Garrison

SITE INVESTIGATION ACTIVITIES**Site Walks**

OE program: Parcel E5a walked by USACE
 UXO Safety Specialist. No UXO or OE scrap
 was found.

EBS/FOST: Portions of the parcels were walked
 in support of property transfer.

Geophysics

Delineation of Area A landfill using GPR, EM-
 31, and Geometrics G856AX (Parcel E4.3.1.1)
 (see OU 2 pre-design technical memorandum for
 locations).

Excavations

Major earthwork and re-contouring during
 construction of the Patton and Abrams housing
 areas (Parcels E4.1.1, E4.2, and E4.3.1.1).

Excavation of the adjacent landfill Area A (see
 Area A remedial action confirmation report).

Excavation of 8 Area A landfill delineation
 trenches (Parcel E4.3.1.1) (see OU 2 pre-design
 technical memorandum for locations).

Soil Borings

None

Wells

Water supply wells: 14 (FO-11 and -14
 destroyed in 1951 or 1952; FO-16 and -17
 destroyed in 1988; FO-18, -19, -21, -22, -23, and
 -25 destroyed in 1989; FO-24, -26, -27, and -28
 destroyed in 1999).

HTW monitoring wells: 26 (see Report of
 Quarterly Monitoring for locations).

ADJACENT AREAS

CBR Training Areas	None
CWM Training Areas	None
Small Arms Ranges	None

OE INFORMATION

Known or Suspected Adjacent OE Sites

Site OE-1 and Site OE- 6 – OE sampling of the sites was conducted. Site OE-1 was a former flame thrower range and Site OE-6 was formerly a mine and booby trap training area (Plate 5). No UXO was found during the sampling at either site. OE scrap items found during the sampling of the sites included practice mines, expended practice mine fuzes and a expended flame thrower ignition cartridge. No further action was recommended for these sites. A buffer of approximately 100 feet and 200 feet lies between Sites OE-1 and OE-6 and Parcel E4.1.1, respectively. These sites will undergo additional evaluation in the OE RI/FS.

Site OE-2 – Identified as a potential chemical training area and landfill (Plate 10). Hundreds of 2.36-inch practice rockets have been removed from disposal pits located in former landfill areas within the site. OE sampling of this site was conducted and two OE scrap items were found. This site will undergo additional evaluation in the OE RI/FS.

Site OE-13A: Sampling of Site OE-13A was conducted and no evidence of OE use was found. Confirmatory sample grids were completed outside of the OE site boundary on the eastern end of the site and two OE scrap items were found (expended grenade fuze and an expended illuminating signal). No further action was recommended for this site. Site will undergo additional evaluation in the OE RI/FS.

A variety of OE scrap items were found during the excavation and removal of the landfill disposal area (Area A). It has been determined that the presence of these items was related to disposal and not OE use in this area. The disposal area has been completely excavated.

**Incident Reports
UXO**

Incident location Parcel L4.3.1.1
 On February 11, 1993 20mm ammunition was found at 1611 Chosin Court. The ammunition was confiscated by the Military police. The military police report states that the occurrence of the 20mm ammunition at 1611 Chosin Court was the result of theft of government property and subsequent storage of the stolen items on the premises. A detailed report on this incident was submitted to the DTSC and US EPA on November 27, 2001.

OE Scrap

Incident location Parcel L4.3.1.1
 Small blue rockets were found during housing construction at Abrams Park Housing near the Area A landfill. The small blue rockets found during housing construction are attributed to disposal in the Area A Landfill. A detailed report on this incident was submitted to the DTSC and US EPA on August 8, 2001.

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	-------------

TRACK 0 CHECKLIST
Open Space/Main Entrance

PARCELS	E15.1, L33.1, L33.2 and S1.4 – Open Space, Main Entrance Area
DESCRIPTION	Open Space/Main Entrance Approximately 201 acres (Plate 6).
HISTORICAL USE	No evidence to suggest OE use Prior to Army purchase this area was ranch land (owned by the David Jacks Corporation and T.A. Work) purchased by the Army after July 1, 1940. 1940: Parade ground/Air strip constructed (Parcel L33.2). 1941: Post engineers facility and Camp Pacific are established (Parcels L33.1 and S1.4). 3700 Motor Pool Complex established including installation of USTs (Parcel S1.4) 1942: USTs installed at the Post Engineers Facility (L33.1) 1940s: Training facilities established and utilized through the 1990s including Rifle Instruction Circles, Machine Gun Squares and physical training areas (Parcels E15.1 and S1.4). About 1972 Main entrance constructed (Parcel E15.1)
Supporting documents	Literature Review and Base Inventory Report, Volume 1; Community Environmental Response Facilitation Act (CERFA) Report; Archives Search Reports; Environmental Baseline Survey, Surplus II Parcels; Volume I, OEW Sampling and OEW Removal Action; OE RI/FS Literature Review; Interim Action Confirmation Report, Site 20 – South Parade Ground; Site Characterization, Site 23 – 3700 Motor Pool Complex; Interim Action Confirmation Report, Site 24 – Old DEH Yard; Site Investigation Report, Buildings 2253, 3803, 4363, and 4534; Field Investigation and Data Review, Solid Waste Management Units.

Components

Aerial Photos	Pre-1940, 7/25/41, 10/14/41, 8/17/49, 7/3/51, 5/14/56, 58/59 (aerial contours), 1/11/65 (mosaic), 5/2/66, 12/17/75, 4/13/85, 10/22/85, 3/25/86, 11/4/88, 10/4/89, 7/6/92.
Real Estate Records	1913 Department of the Interior, reprinted 1918 1915 Proposed Acreage Subdivisions 1922 Assessors Plats, Monterey County 3/18/88 Real Estate, Fort Ord
Range Control Records/ Standard Operating Procedures	Not applicable to this area
Range and Training Area Maps	8/45 Training Facilities Circa 1954 Training Areas that Cannot Be Used at the Same Time 7/3/56 Range Complex 12/20/56 Fort Ord Training Areas & Facilities 7/15/57 Training Areas & Facilities 1/10/58 Training Areas & Facilities 12/31/58 Ranges & Training Facilities 4/27/64 Field Training Areas & Range Map 8/16/65 Close In Training Areas 1/67 Field Training Areas & Range Map 5/1/67 Close In Training Areas 3/13/68 Training Facilities Map 11/1/71 Training Facilities Plan 3/16/72 Training Ranges and General Road Map 7/1/72 Field Training Area and Range Map 2/23/73 Close In Training Areas 2/1/76 Ranges and Training Area Overlay 12/1/76 Future Development Plans, Training Facilities Plan 3/1/76 Close In Training Areas 6/1/77 Training Facilities Plan 1/78 Ranges and Training Area Overlay 7/15/78 Ranges and Training Area Overlay 3/80 Training Facilities Map 6/1/81 Ranges and Training Area Overlay 4/1/82 Ranges and Training Area Overlay 4/27/84 Field Training Areas and Range Map 6/84 Training Facilities Map 11/15/87 Ranges and Training Area Overlay
Base Development Plans and Maps	1922 Assessors Plats, Monterey Co. 1934 War Department, Camp Ord and Vicinity 1944 Army Map Service, Fort Ord Military Reservation

3/20/46 Fort Ord Master Plans
 4/5/46 Fort Ord Master Plans
 2/56 Main Garrison Layout
 1/15/69 Post Locator Map
 1972 Fort Ord and Vicinity (V895S)
 3/1/75 Master Plan, Reservation Map
 8/1/84 Fort Ord Military Installation Map
 (V795S)
 2/10/90 Fort Ord Locator Map, Main Garrison

SITE INVESTIGATION ACTIVITIES

Site Walks

OE program: Portions of Parcel S1.4 walked by OE the contractor during the establishment of 9 OE sample grids (see the OEW sampling and removal action report)

HTW program: Visual survey of IRP Sites 20, 23, and 24 (see cross-hatched area on Plate 6 and IRP Site 20, 23 and 24 characterization reports).

UST Management Program: Oversight of UST 3803.1/3803.2 over-excavation (see UST 3803 investigation report).

SWMU investigation: Inspection of solid waste management units FTO-024, -054, -066, -067, and -069 (see the Field Investigation and Data Review Solid Waste Management Units for locations).

EBS/FOST: Visual site inspection of the parcels.

Geophysics

OE grids (9) geophysically surveyed by OE contractor using hand held magnetometers.

Geophysical survey (GPR and EM-31) of IRP Sites 20 and 24. All geophysical anomalies excavated (20 trenches) by UXO specialists. Borehole clearance (see IRP Site 20 and 24 characterization and interim action reports for locations).

UST investigation (see UST 3803 investigation report).

Excavations

Development of parcels beginning in 1940. Building and facilities construction throughout

the parcels in the 1940's, 1950's, 1960's, 1970's and 1980's; Excavation of 11 exploratory trenches (Parcel E15.1); Excavation of 9 exploratory trenches (Parcels L33.1 and S1.4); Excavation of Interim Action Areas 24A, 24B, and 24C (Parcels L33.1 and S1.4); UST 3803.1 and 3803.2 removal and over-excavation (Parcel L33.1); UST 3803.3, 3766.1, 7766.2, 3771.1, 3771.2, 3775.1, 3775.2, 3855.1, and 3855.2 removals (Parcels L33.1 and S1.4)

Soil Borings

HTW: 39 borings (see IRP Site 20, 23, and 24 characterization reports for locations)

UST Management Program: 6 soil borings (see UST 3803 investigation report for locations)

Wells

HTW monitoring wells: 9 (see IRP Site 20, 23, and 24 characterization reports for locations)

ADJACENT AREAS

CBR Training Areas	None
CWM Training Areas	None
Small Arms Ranges	None

OE INFORMATION

Known or Suspected Adjacent OE Sites None

Incident Reports	
UXO	None
OE Scrap	None

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	-------------

TRACK 0 CHECKLIST

Surplus II Area

PARCELS	L1.1, L19.2, L19.3, L19.4, L32.2.1, L32.2.2, L32.3, L32.4.1.1, L32.4.1.2, L32.4.2, L23.6, L36, L37, L15.1, L7.8, L7.9, L2.4.2, L2.4.3.1, L2.4.3.2, S1.3.1 – Surplus II Area
DESCRIPTION	South eastern portion of the main garrison. Includes installation support facilities and former barracks. Approximately 175 acres (Plate 7).
HISTORICAL USE	<p>No evidence to suggest OE use</p> <p>Prior to Army purchase this area was ranch land (owned by the David Jacks Corporation and T.A Work) purchased by the Army after July 1 1940.</p> <p>1946: Large above ground water storage tank constructed (Parcel L32.2.2).</p> <p>1950s: Training areas established, including machine gun squares, rifle instruction circles and physical training areas.</p> <p>1954: Barracks and support structures constructed (Parcels L2.4.3.1, L32.2.2, L32.4.1.1, L32.4.1.2, L7.8 and L7.9) including the installation of USTs. 4400/4500 Motor Pool (IRP Site 22) present on Parcel S1.3.1.</p> <p>1966: Additional physical training areas established (Parcels L32.2, L32.4.2 and L2.4.2).</p> <p>1968: Additional barracks constructed (Parcels L1.1, L19.4, L23.6 and L32.4.1).</p> <p>About 1984: AST 4441 installed (210,000 gallon diesel) on Parcel L2.4.2.</p>
Supporting documents	Literature Review and Base Inventory Report, Volume 1; Community Environmental Response Facilitation Act (CERFA) Report; Archives Search Reports; Sampling and Removal After Action Report Site OE-4A; OE Removal After Action Report, Site OE-13B; Final Report for Ordnance and Explosive Removal Action, Site CSU; After Action Report, Sitestats/Gridstats OE Sampling, Site 24B-E and OE-39; OE RI/FS Literature Review; Environmental Baseline Survey, Surplus II Parcels; Interim Action Confirmation Report, Site 22 – 4400/4500

Motor Pool, West Block; Site Investigation Report, Buildings 2253, 3803, 4363, and 4534; Field Investigation and Data Review, Solid Waste Management Units.

Components

Aerial Photos

Pre-1940, 7/25/41, 10/14/41, 8/17/49, 6/23/51, 7/3/51, 5/14/56, 58/59 (aerial contours), 1/11/65 (mosaic), 5/2/66, 5/10-10/18/74, 12/17/75, 4/13/85, 10/22/85, 3/25/86, 11/12/86, 11/4/88, 10/4/89, 7/6/92.

Real Estate Records

1913 Department of the Interior, reprinted 1918
1915 Proposed Acreage Subdivisions
1922 Assessors Plats, Monterey County
3/18/88 Real Estate, Fort Ord

Range Control Records/ Standard Operating Procedures

Not applicable to this area

Range and Training Area Maps

8/45 Training Facilities
Circa 1954 Training Areas that Cannot Be Used at the Same Time
7/3/56 Range Complex
12/20/56 Fort Ord Training Areas & Facilities
7/15/57 Training Areas & Facilities
1/10/58 Training Areas & Facilities
12/31/58 Ranges & Training Facilities
6/30/61 Training Facilities, Basic Information
4/27/64 Field Training Areas & Range Map
8/16/65 Close In Training Areas
1/67 Field Training Areas & Range Map
5/1/67 Close In Training Areas
3/13/68 Training Facilities Map
11/1/71 Training Facilities Plan
3/16/72 Training Ranges and General Road Map
7/1/72 Field Training Area and Range Map
2/23/73 Close In Training Areas
2/1/76 Ranges and Training Area Overlay
12/1/76 Future Development Plans, Training Facilities Plan
3/1/76 Close In Training Areas
6/1/77 Training Facilities Plan
9/77 Close In Training Areas
1/78 Ranges and Training Area Overlay
7/15/78 Ranges and Training Area Overlay
3/80 Training Facilities Map
6/1/81 Ranges and Training Area Overlay
4/1/82 Ranges and Training Area Overlay

	4/27/84 Field Training Areas and Range Map
	6/84 Training Facilities Map
	11/15/87 Ranges and Training Area Overlay
Base Development Plans and Maps	1922 Assessors Plats, Monterey Co.
	1934 War Department, Camp Ord and Vicinity
	1944 Army Map Service, Fort Ord Military Reservation
	3/20/46 Fort Ord Master Plans
	4/5/46 Fort Ord Master Plans
	4/5/46 Reservation Boundary and Land Use
	2/56 Main Garrison Layout
	1/15/69 Post Locator Map
	1972 Fort Ord and Vicinity (V895S)
	3/1/75 Master Plan, Reservation Map
	8/1/84 Fort Ord Military Installation Map (V795S)
	1985 Fort Ord Locator Map
	2/10/90 Fort Ord Locator Map, Main Garrison

SITE INVESTIGATION ACTIVITIES

Site Walks

HTW program: Visual survey of IRP Site 22 (see cross-hatched area on Plate 7 and IRP Site 22 characterization report).

UST Management Program: Oversight of UST 4534.1 over-excavation (see UST 4534 investigation report).

SWMU investigation: Inspection of solid waste management units FTO-005, -025, -026, -035, and -068 (see the Field Investigation and Data Review Solid Waste Management Units for locations).

EBS/FOST: Visual site inspection of the parcels.

Geophysics

Borehole clearance (see IRP Site 22 characterization report).
UST investigations (see UST 4534 investigation report).

Excavations

Excavation and installation of a water storage tank in about 1946 (Parcel L32.2.2).
Construction of barracks and motor pool and installation of underground storage tanks and oil/water separators in 1954 (Parcels L2.4.3.1, L7.8, L7.9, L32.2.2, L32.4.1.1, L32.4.1.2,

S1 3.1). Additional construction of facilities on all parcels in the 1960s, 1970s and 1980s, including the installation of additional USTs and oil/water separators. Excavation of Interim Action Area 22A (Parcel S1.3.1); Excavation of oil/water separator adjacent to Building 4538 (Parcel S1.3.1). UST 4534.1 removal and over-excavation (Parcel S1.3.1); Excavation and removal of 24 USTs (Parcels S1 3.1, L32.2.1, L32.2.2, L32.4.1.1, L32.4.1.2, L32.4.2, and L2.4.2).

Soil Borings

HTW: 17 borings (see IRP Site 22 characterization report for locations).

Wells

HTW monitoring wells: 3 (see IRP Site 22 characterization report for locations).

ADJACENT AREAS

CBR Training Areas

Site OE-4A – A removal action was conducted at this site and no chemical OE-related items were found. This site will undergo additional evaluation in the OE RI/FS.

**CWM Training Areas
Small Arms Ranges**

None
None

OE INFORMATION

Known or Suspected Adjacent OE Sites

Site OE-4A – An OE removal action over the entire site was conducted. Site OE-4A is located approximately 400 feet south of the Track 0 parcels. This site will undergo additional evaluation in the OE RI/FS (Plate 7)

Site OE-13B – An OE removal action over the entire site was conducted. Site OE-13B is separated from the adjacent Track 0 parcels by a road. This site will undergo additional evaluation in the OE RI/FS

Site OE-31 – An OE removal action over the entire site (Site CSU) was conducted. Site OE-31 encompasses Sites OE-7, OE-8, OE-4C, OE-18 and a portion of OE-13B. Site OE-31 is separated from the adjacent Track 0 parcels by a road. This site will undergo additional evaluation in the OE RI/FS

Site OE-39 – Sampling of this site (mine and booby trap training area) was conducted and no evidence of OE was found. Site OE-39 is located approximately 800 feet south of the Track 0 parcels. This site will undergo additional evaluation in the OE RI/FS.

**Incident Reports
UXO**

None

OE Scrap

Incidental Location Parcel L2.4.2
On March 13, 2001 a portion of an expended pyrotechnic signal was found near former AST 4441. The piece of OE scrap was removed by the USACE UXO Safety Specialist. It was determined that the flare casing was a discarded item and was not related to ordnance training at this location. A detailed report on this incident was submitted to the DTSC and the US EPA on June 3, 2002.

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	-------------

TRACK 0 CHECKLIST

Fritzsche Army Airfield

PARCEL	S2.1.3, S2.1.4.1, S2.1.4.2, L5.1.2, L5.1.3, L5.1.4, L5.1.5, L5.1.6, L5.1.7, L5.1.8, L5.1.9, L5.1.10, L5.2, L5.3, F7.1, and F7.2 – Fritzsche Army Airfield (FAAF) Area
DESCRIPTION	These parcels have a combined area of approximately 48 acres (Plate 8). With the exception of Parcel L5.3, the parcels lie in the northeastern portion of the former Fort Ord, north of Reservation Road and in and around the former FAAF. These parcels were used as support facilities for the airfield. Parcel L5.3 is offsite about 2 and 1/4 miles east of the eastern boundary of the East Garrison and included a navigational beacon.
HISTORICAL USE	<p>History suggests no OE used</p> <p>Prior to Army purchase this area was ranch land and was purchased from several individuals.</p> <p>1945: "Practice Bazooka & Rifle Grenades" training area indicated on a 1945 training facilities map. This training area became Site OE-34 and lies near Parcels L5.1.4 and L5.1.8.</p> <p>1956: "Ranging Area" indicated on 1956 map (Parcels L5.1.2, L5.1.3, L5.1.4, L5.1.6, L5.1.7 and L5.1.8). "Tank Driving Area 2," Parcels L5.1.10 and S2.1.4.1.</p> <p>1957: Area used as a basic driving area and a field communications crewmans course (all parcels except F7.2 and L5.3).</p> <p>1958: Construction of the Fritzsche Army Airfield begins.</p> <p>1961: Construction continues with the addition of support facilities and the installation of underground storage tanks. 1968: Parcel S2.1.3 being used as an aviation training area (IRP Site 35)</p> <p>1984: Water supply wells installed (Parcels F7.1 and F7.2).</p>
Supporting documents	Literature Review and Base Inventory Report, Volume 1; Community Environmental Response Facilitation Act (CERFA) Report;

Environmental Baseline Survey, Fritzsche Army Airfield; Archives Search Reports, OE RI/FS Literature Review, Ordnance and Explosive Removal Action, Fritzsche Army Airfield, Support for Geophysical Survey, OE Sampling after Action Report Site OE-34 (FAAF); Site Characterization, Site 35 – Fritzsche Army Airfield Aircraft Cannibalization Yard; Interim Action Confirmation Report, Site 36 – Fritzsche Army Airfield Sewage Treatment Plant, Interim action Confirmation Report Site 40 – Fritzsche Army Airfield Defueling Area, Field Investigation and Data Review, Solid Waste Management Units, Interim Action Confirmation Report, Site 34 – Fritzsche Army Airfield Fueling Facility

Components

Aerial Photos

7/25/41, 8/17/49, 6/23/51, 5/14/56, 8/1/56, 58/59 (aerial contours), 1/11/65 (mosaic), 5/2/66, 12/17/75, 6/16/78, 4/13/85, 10/22/85, 3/25/86, 11/12/86, 11/4/88, 10/4/89, 7/6/92.

Real Estate Records

1913 Department of the Interior, reprinted 1918
1915 Proposed Acreage Subdivisions
1922 Assessors Plats, Monterey County
3/18/88 Real Estate, Fort Ord

Range Control Records/ Standard Operating Procedures

Not applicable to this area

Range and Training Area Maps

8/45 Training Facilities
Circa 1954 Training Areas that Cannot Be Used at the Same Time
7/3/56 Range Complex
12/20/56 Fort Ord Training Areas & Facilities
7/15/57 Training Areas & Facilities
1/10/58 Training Areas & Facilities
12/31/58 Ranges & Training Facilities
6/30/61 Basic Information, Training Facilities
4/27/64 Field Training Areas & Range Map
1/67 Field Training Areas & Range Map
3/13/68 Training Facilities Map
11/1/71 Training Facilities Plan
3/16/72 Training Ranges and General Road Map
7/1/72 Field Training Area and Range Map
2/1/76 Ranges and Training Area Overlay
12/1/76 Future Development Plans, Training Facilities Plan

6/1/77 Training Facilities Plan
 1/78 Ranges and Training Area Overlay
 7/15/78 Ranges and Training Area Overlay
 3/80 Training Facilities Map
 6/1/81 Ranges and Training Area Overlay
 4/1/82 Ranges and Training Area Overlay
 4/27/84 Field Training Areas and Range Map
 6/84 Training Facilities Map
 11/15/87 Ranges and Training Area Overlay

Base Development Plans and Maps

1922 Assessors Plats, Monterey Co.
 1934 War Department, Camp Ord and Vicinity
 1944 Army Map Service, Fort Ord Military
 Reservation
 4/5/46 Reservation Boundary & Land Use Map
 1972 Fort Ord and Vicinity (V895S)
 3/1/75 Master Plan, Reservation Map
 6/1/77 Future Development Plans, Reservation
 Plan
 8/1/84 Fort Ord Military Installation Map
 (V795S)
 2/10/90 Fort Ord Locator Map, Main Garrison

SITE INVESTIGATION ACTIVITIES

Site Walks

HTW program: Site walks completed in support of the IRP investigations at Sites 34, 35, 36, and 40 (see cross-hatched area on Plate 8 and IRP Site 34, 35, 36 and 40 characterization reports).

SWMU investigation: Inspection of solid waste management unit FTO-042 on Parcel S2.1.4.2 (see the Field Investigation and Data Review Solid Waste Management Units).

EBS/FOST: Portions of the parcels were walked in support of property transfer.

Geophysics

Geophysical survey (GPR and EM-31) of Interim Action Area 40C (Parcel L5.1.4). All geophysical anomalies excavated (6 trenches) by UXO specialists (see IRP Site 40 Interim Action Report).

Borehole clearance (Parcels S2.1.3, L5.1.8, L5.1.5 and L5.1.3) (see IRP Site 34, 35, 36 and 40 characterization reports).

Excavations

Development and construction of the airfield and support buildings beginning in 1958.

Installation of underground storage tanks (USTs) in the 1960s, 1970s and 1980s. Excavation of Interim Action Areas 34A, 36A, 36B, 40A, and 40C (see Interim Action reports for locations). Excavation of UST 509 site (Parcel S2.1.4.2).

Soil Borings

HTW: 33 borings (see IRP Site 34, 35, 36 and 40 characterization reports for locations).

Wells

HTW monitoring wells: 4 (see IRP Site 34, 36 and 40 characterization reports for locations).

Water supply wells: 2 (active)

ADJACENT AREAS

CBR Training Areas
CWM Training Areas
Small Arms Ranges

None
 None
 None

OE INFORMATION

Known or Suspected Adjacent OE Sites

Site OE-34 – This site was identified on a 1945 Fort Ord training map as a bazooka and rifle grenade training area. The site lies approximately 100 feet from the nearest parcel L5.1.8. An OE removal action was conducted. OE related-items found at this site included 2.36-inch rockets, a rocket motor, demolition charges and small arms. Based on the completion of the removal action no further action was recommended. The U.S. EPA reexamined 10% of Site OE-34 and identified a 2.36-inch inert training rocket (OE scrap). Additional investigation over the entire site was performed and no UXO was found. OE scrap found included fragments of 2.36-inch inert practice rockets. This site will undergo additional evaluation in the OE RI/FS (Plate 8).

Incident Reports
UXO
OE Scrap

None
 None

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	-------------

TRACK 0 CHECKLIST East Garrison Area

PARCEL	E11b.1, E11b.2, E11b.3, E11b.4, L20.14.1.2, L20.19.2, L20.20, L20.21.1, L20.21.2, L20.22, L23.3.1, L23.3.2.1, L35.3, L35.6, L35.7, and L35.8 – East Garrison Area
DESCRIPTION	Approximately 226 acre area including the East Garrison Historic District, a former sewage treatment facility, a former skeet range, a small family cemetery, and some undeveloped land (Plate 9).
HISTORICAL USE	<p>History suggests no OE used</p> <p>Prior to Army purchase was ranch land (David Jacks Corporation). Purchased by the Army in 1917 and used as an encampment for artillery and cavalry units stationed at the Presidio of Monterey.</p> <p>1934: Camp Ord established (Parcels L20.21, L20.22, L23.3.1, L23.3.2.1 and L35.3) and water supply well installed (Parcel L23.3.2.1). Small arms ranges established south of the parcels.</p> <p>1939: Water supply well installed (Parcel L23.3.2.1).</p> <p>1940: Construction of permanent mess halls, latrines, sewage treatment facility (IRP Site 32) and mule corral (Parcels L23.3.2.1, E11b.3, and E11b.2). A drill area was established in the north portion of Parcel L23.3.1 and later used as a truck and gun park (IRP Site 30).</p> <p>1943: Water supply well installed (Parcel L23.3.2.1).</p> <p>1960s: Leadership Reaction Course established in the southern portion on Parcel L23.3.2.1.</p> <p>1964-1968: Skeet Range established on Parcel L23.3.1 (IRP Site 39A).</p> <p>1971: Heavy vehicle driving course established in the former location of the drill area (Parcel L23.3.1).</p> <p>1970s: Establishment of the Defense Reutilization and Marketing Office (DRMO) within Parcel L23.3.2.1 (IRP Site 29).</p>

Supporting documents

Literature Review and Base Inventory Report, Volume 1; Community Environmental Response Facilitation Act (CERFA) Report; Archives Search Reports; Volume I, OEW Sampling and OEW Removal Action; OE RI/FS Literature Review; Destruction Record, Fort Ord Water Supply Wells; Site Characterization, Site 30 – Driver Training Area; Interim Action Confirmation Report, Site 32 – East Garrison Sewage Treatment Plant; Interim Action Confirmation Report, Site 39A – East Garrison Ranges; Data Summary Report, Investigation of Magnetic Anomalies, East Garrison Area; Field Investigation and Data Review, Solid Waste Management Units; Underground and Aboveground Storage Tank Management Plan Update.

Components**Aerial Photos**

Pre-1940, 7/25/41, 8/17/49, 6/23/51, 8/1/56, 58/59 (aerial contours), 1/11/65 (mosaic), 5/2/66, 12/17/75, 6/16/78, 4/13/85, 10/22/85, 3/25/86, 11/4/88, 10/4/89, 7/6/92.

Real Estate Records

1912 Salmas Quadrangle
1915 Proposed Acreage Subdivisions
1922 Assessors Plats, Monterey County
3/18/88 Real Estate, Fort Ord

**Range Control Records/
Standard Operating Procedures**

Fort Ord Pam 350-5: Standard Operating Procedures, Leadership Reaction Course (Parcel L23.3.2.1).

Range and Training Area Maps

6/20/40 Camp Ord, Ultimate Layout of Concurrent Training Camps
8/45 Training Facilities
Circa 1954 Training Areas that Cannot Be Used at the Same Time
7/3/56 Range Complex
12/20/56 Fort Ord Training Areas & Facilities
7/15/57 Training Areas & Facilities
1/10/58 Training Areas & Facilities
12/31/58 Ranges & Training Facilities
6/30/61 Basic Information, Training Facilities
4/27/64 Field Training Areas & Range Map
1/67 Field Training Areas & Range Map
3/13/68 Training Facilities Map
1/11/71 Training Facilities Plan

3/16/72 Training Ranges and General Road Map
 7/1/72 Field Training Area and Range Map
 2/1/76 Ranges and Training Area Overlay
 12/1/76 Future Development Plans, Training
 Facilities Plan
 6/1/77 Training Facilities Plan
 1/78 Ranges and Training Area Overlay
 7/15/78 Ranges and Training Area Overlay
 3/80 Training Facilities Map
 6/1/81 Ranges and Training Area Overlay
 4/1/82 Ranges and Training Area Overlay
 4/27/84 Field Training Areas and Range Map
 6/84 Training Facilities Map
 11/15/87 Ranges and Training Area Overlay

Base Development Plans and Maps

1922 Assessors Plats, Monterey Co.
 1934 War Department, Camp Ord and Vicinity
 1940 Salinas Quadrangle, Grid Zone "G", U.S.
 Army Tactical Map
 11/28/41 East Garrison Topographical &
 Temporary Housing Layout
 1/28/42 East Garrison, Layout of Buildings &
 Roads
 1944 Army Map Service, Fort Ord Military
 Reservation
 4/5/46 East Garrison Cantonment and Use Map
 4/5/46 Reservation Boundary & Land Use Map
 1972 Fort Ord and Vicinity (V895S)
 3/1/75 Master Plan, Reservation Map
 6/1/77 Future Development Plans, Reservation
 Plan
 8/1/84 Fort Ord Military Installation Map
 (V795S)

SITE INVESTIGATION ACTIVITIES

Site Walks

OE program: Parcel E11b.1 walked by a
 USACE UXO Safety Specialist. No UXO or
 OE scrap was found.

HTW program: Visual survey of IRP Sites 29,
 30, 32, and 39A (see cross-hatched area on
 Plate 9 and IRP Site 29, 30, 32 and 39A
 characterization reports).

SWMU investigation: Inspection of solid waste
 management units FTO-008 and -009 on Parcel
 L23.3.2.1 (see the Field Investigation and Data
 Review Solid Waste Management Units).

	EBS/FOST: Portions of the parcels were walked in support of property transfer.
Geophysics	HTW program: Identification of 7 magnetic anomalies using magnetometer and GPR adjacent to IRP Site 29 (see the investigation of magnetic anomalies work plan).
	Borehole clearance (see IRP Site characterization reports)
Excavations	HTW program: Excavation of 6 trenches from 2 to 5 feet to investigate identified magnetic anomalies adjacent to IRP Site 29. Excavations performed by UXO specialists (see magnetic Anomaly Data Summary Report for locations).
	Excavation of Interim Action (IA) areas 32A and 32B (Parcel E11b.3, see IRP Site 32 IA confirmation report for locations).
	Excavation of 9 test pits at IRP Site 39A (Parcels L23.3.1 and L35.3; see IRP Site 39A IA confirmation report for locations).
	Excavation of 7 IA areas at Site 39A (Parcel L23.3.1; see IRP Site 39A IA confirmation report for locations).
	Removal of USTs 93.1, 93.2, 128, 139.1 and 139.2 (Parcel L23.3.1 and L23.3.2.1) (see UST Management Plan for update).
Soil Borings	HTW program: 48 borings (see IRP Site 29, 30, and 32 characterization reports for locations).
Wells	HTW monitoring wells: 4 (see IRP Site 30 and 32 characterization reports for locations).
	Water supply wells: 2 (destroyed in 1995).

ADJACENT AREAS

CBR Training Areas	None
CWM Training Areas	None
Small Arms Ranges	Small arms ranges located to the south of Parcels L23.3.2.1, L23.3.1, L35.6 and E11b.1. Firing was to the south away from the parcels,

based on the documented locations of firing points and target locations (see IRP Site 39A interim action confirmation report).

OE INFORMATION

Known or Suspected Adjacent OE Sites

Site OE-5 – Approximately 200 feet south of Parcel L23.3.2.1 (Plate 9). Sampling was conducted, no evidence of OE found. Site will undergo additional evaluation in the OE RI/FS.

Site OE-59 – Approximately 800 feet south of Parcel L23.3.2.1. OE-related items found during site walk included expended pyrotechnics, expended smoke grenade, and 60mm mortar fragments. Site will undergo additional evaluation in the OE RI/FS.

Incident Reports UXO

Incidental location Parcel L23.3.2.1
On three occasions (March 29, April 22, and May 12, 1993), the 49th EOD was called to the Non-Commissioned Officers (NCO) Academy located at Building T-14 to remove UXO and OE scrap found by NCO's during training activities conducted at other locations. The EOD was called to the building to remove the items in preparation for base closure. The UXO items removed included hand grenade and booby trap simulators, flares, signals and smoke grenades. OE scrap items removed included empty projectiles and casings, and drill rounds (rubber and brass). It was determined that the ordnance items recovered at Building T-14 were found items brought to the building by NCO academy members after returning from training. A detailed report on these incidents was submitted to the DTSC and the US EPA on June 3, 2002.

OE Scrap

Incidental location Parcel L23.3.2.1
On May 30, 1993, the 49th EOD was called to the Nuclear, Biological, and Chemical (NBC) School located at Building T-21. As part of the preparation for demobilization and base closure, members of the 49th EOD were asked inspect and to provide certification that two training devices (105mm illumination round and a practice mine) were in fact inert training items.

Certification was given by the 49th EOD and the items were returned to the NBC School's inventory of training items. A detailed report on this incident was submitted to the DTSC and the US EPA on June 3, 2002.

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	------

TRACK 0 CHECKLIST

Main Garrison

PARCELS	E2b.1.1.1, E2b.1.2, E2b.1.1.2, E2b.1.3, E2b.1.4, E2b.1.5, E2b.2.1, E2b.2.2, E2b.2.3, E2b.2.4, E2b.2.5, E2b.3.1.1, E2b.3.2, E2c.2, E2c.3.1, E2c.3.2, E2c.3.3, E2c.4.1.1, E2c.4.2.1, E2d.1, E2d.2, E17, L2.1, L12.2.2, L12.2.3, L12.3, L23.1.1, L23.1.2, L23.1.3, L23.1.4, L23.1.5, L35.1, L35.2, L20.16.1, L20.16.2, L20.16.3, S1.5.1.1, S1.5.1.2, S1.5.2, L23.4, L2.2.1, L5.8.1, L5.8.2 and L20.17.1 – Main Garrison Area
DESCRIPTION	These parcels lie within the Main Garrison and include some of the earliest and most heavily developed portions of the former Fort Ord. The combined area includes 44 parcels encompassing approximately 568 acres (Plate 10). Includes Special Case Track 0 area of Site OE-2.
HISTORICAL USE	<p>No evidence to suggest OE use</p> <p>Prior to Army purchase this area was ranch land (David Jacks Corporation and Rancho Noche Buena).</p> <p>A portion of the area (200 acres) was purchased by the Army in 1917 (Camp Clayton). The remaining property was purchased by the Army after July, 1940. No permanent structures were built on the property until 1940.</p> <p>1940: Construction of support facilities including motor pools (Parcels S1.5.1.1, E2b.2.1), a hospital complex (Parcels L23.1.4, E2c.3.2, E2c.3.3, E2d.1), barracks (Parcels E2b.2.1, E2b.2.3, E2b.3.1.1), warehouses (Parcels L20.16.1, L20.16.2), horse stables (Parcels S1.5.1.1, S1.5.1.2), theaters (Parcels E2b.1.2, E2b.1.3), chapels (Parcel E2b.3.1.1, L23.1.3) and water supply wells (Parcels E2b.3.1.1). This development included the installation of underground storage tanks, oil-water separators and sumps</p> <p>1941: Additional water supply wells installed (Parcels E2c.3.2, E2c.3.3).</p> <p>1944: POW camp in place (Parcel E2c.4.2.1).</p> <p>1951: Horse corrals have been replaced by a</p>

baseball field, a driving range and rifle instruction circles (Parcels S1.5.1.1, S1.5.1.2, S1.5.2).

1956: Motor pool constructed (Parcel S1.5.2). Several training areas are also established including physical training areas (Parcels E2b.1.3, E2b.2.4, E2b.3.1.1), and a mortar square (Parcel S1.5.1.1).

1965: Engineer field maintenance shop (Parcel L20.17.1). Additional buildings constructed in this area in 1967 and 1969.

1980 : Motor pool constructed (Parcels S1.5.1.1, S1.5.1.2).

Supporting documents

Literature Review and Base Inventory Report, Volume 1; Community Environmental Response Facilitation Act (CERFA) Report; Environmental Baseline Survey, Main Garrison Parcels; Archives Search Reports; OE RI/FS Literature Review; Groundwater Well Management Plan Update; Report of Quarterly Monitoring, October through December 1999; Remedial Investigation Sites 2 and 12; Remedial Investigation Sites 16 and 17; Site Characterization Site 13 – Railroad Right-of-Way; Site Characterization Site 14 – 707th Maintenance Facility; Confirmation Report Site 14 – 707th Maintenance Facility; Site Characterization Site 15 – DEH Yard; Confirmation Report Site 15 – Directorate of Engineering and Housing Yard; Site 18 – 1600 Block Facility; Site Characterization Site 19 – 2200 Block Facility; Site Characterization Report, Site 28 – Barracks And Main Garrison Area; Site Characterization Site 38 – Army and Air Force Exchange Service Dry Cleaners; Site Investigation Report Buildings 4107, 4110, and 4590 and Facility 2754; Site Investigation Report, Buildings 2253, 3803, 4363, and 4534; Investigation Report Buildings 3016A and 4493; Site Investigation Report Buildings 1483, 1697, 4518 and 6160; Site Investigation Report Former Buildings 1685 and 2070; Field Investigation and Data Review, Solid Waste Management Units;

Components

Aerial Photos

Pre-1940, 7/25/41, 10/14/41, 8/17/49, 6/23/61, 7/3/51, 5/14/56, 58/59 (aerial contours), 1/11/65

	(mosaic), 5/2/66, 6/3/66, 10/18/74, 12/17/75, 4/13/85, 10/22/85, 3/25/86, 11/12/86, 11/4/88, 10/4/89, 7/6/92.
Real Estate Records	1913 Department of the Interior, reprinted 1918 1915 Proposed Acreage Subdivisions 1922 Assessors Plats, Monterey County 3/18/88 Real Estate, Fort Ord
Range Control Records/ Standard Operating Procedures	Not applicable to this area
Range and Training Area Maps	8/45 Training Facilities Circa 1954 Training Areas that Cannot Be Used at the Same Time 7/3/56 Range Complex 12/20/56 Fort Ord Training Areas & Facilities 7/15/57 Training Areas & Facilities 1/10/58 Training Areas & Facilities 12/31/58 Ranges & Training Facilities 6/30/61 Basic Information, Training Facilities 4/27/64 Field Training Areas & Range Map 8/16/65 Close In Training Areas 1/67 Field Training Areas & Range Map 5/1/67 Close In Training Areas 3/13/68 Training Facilities Map 11/1/71 Training Facilities Plan 3/16/72 Training Ranges and General Road Map 7/1/72 Field Training Area and Range Map 2/23/73 Close In Training Areas 2/1/76 Ranges and Training Area Overlay 12/1/76 Future Development Plans, Training Facilities Plan 3/1/76 Close In Training Areas 6/1/77 Training Facilities Plan 9/77 Close In Training Areas 1/78 Ranges and Training Area Overlay 7/15/78 Ranges and Training Area Overlay 3/80 Training Facilities Map 6/1/81 Ranges and Training Area Overlay 4/1/82 Ranges and Training Area Overlay 4/27/84 Field Training Areas and Range Map 6/84 Training Facilities Map 11/15/87 Ranges and Training Area Overlay
Base Development Plans and Maps	1922 Assessors Plats, Monterey Co. 1934 War Department, Camp Ord and Vicinity 1940 Fort Ord Locator Map 1944 Army Map Service, Fort Ord Military Reservation

7/3/44 Fire Hydrants & Fire Telephones
 3/20/46 Fort Ord Master Plans
 4/5/46 Fort Ord Master Plans
 2/56 Main Garrison Layout
 8/17/63 Main Garrison Layout
 1/15/69 Post Locator Map
 1972 Fort Ord and Vicinity (V895S)
 3/1/75 Master Plan, Reservation Map
 6/1/77 Reservation Plan, Future Development
 Plans
 8/1/84 Fort Ord Military Installation Map
 (V795S)
 1985 Fort Ord Locator Map
 2/10/90 Fort Ord Locator Map, Main Garrison

SITE INVESTIGATION ACTIVITIES

Site Walks

OE program: Portion of Parcel E2b.3.1.1 walked by USACE UXO Safety Specialist. No UXO or OE scrap was found.

HTW program: Visual survey of IRP Sites 12, 13, 14, 15, 16, 17, 18, 19, 28, and 38 (see cross-hatched area on Plate 10)

UST Management Program: Oversight of over-excavation of USTs 1483, 1685, 1697, 2253, 2754, 3004, and 3016 (see UST 1483, 1689, 1697, 2253, 2754, 3004, and 3016 investigation reports).

SWMU investigation: Inspection of solid waste management units FTO-015, -017, -018, -019, -023, -036, -037A, -37B, -38, -040, -041, -044, -049, -050, -051, -053, -056, -057, -058, -061, and -064 (see the Field Investigation and Data Review Solid Waste Management Units for locations)

EBS/FOST: Visual site inspection of the parcels.

Geophysics

Geophysical survey (GPR and EM-31) of IRP Sites 12, 16 and 17 All geophysical anomalies excavated by UXO specialists (see RI reports for IRP Sites 12, 16, and 17).

Borehole clearance (see IRP Sites 12, 13, 14, 15, 16, 17, 18, 19, 28, and 38 characterization

reports, interim action and RI reports for locations).

UST investigation (see UST 1483, 1685, 1697, 2253, 2754, 3004A, and 3016A investigation reports).

Excavations

Development of parcels beginning in 1940. Building and facilities construction throughout the parcels in the 1940's, 1950's, 1960's, 1970's and 1980's; Excavation of exploratory trenches at IRP Sites 12, 16, and 17 (Parcels E2b.2.1, S1.5.1.2, L5.8.2, and L20.17.1); Excavation of remedial areas at IRP Sites 12, 16, and 17; Excavation of Interim Action Areas 14B and 15A (Parcels 5.8.1, L20.17.1 and S1.5.1.1); UST 1483 (Parcel S1.5.1.2), 1689 and 1697 (Parcel S1.5.1.1), 2253.1 (Parcel E2b.1.5), 2754.1 (Parcel E2b.2.1), 3004A (Parcel E2d.1), 3016A.1 (Parcel L23.1.4) removal and over-excavation.

Soil Borings

HTW: 177 borings (see Site 12, 13, 14, 15, 16, 17, 18, 19, 28, and 38 characterization reports, interim action and RI reports for locations)

UST management program: 10 soil borings (see Site Investigation Report for Building 2754 and former Building 1685 for locations).

Wells

HTW monitoring wells: 38 (see Report of Quarterly Monitoring for locations).

Water supply wells: 4 (destroyed).

ADJACENT AREAS

CBR Training Areas	None
CWM Training Areas	None
Small Arms Ranges	None

OE INFORMATION

Known or Suspected Adjacent OE Sites

Site OE-1 – OE sampling of this site was conducted. Site OE-1 was a former flame thrower range and no UXO was found during the sampling of this site (Plate 10). OE scrap items found during the sampling included

practice mines, expended practice mine fuzes and a expended flame thrower ignition cartridge. No further action was recommended for this site. Site OE-1 lies approximately 400 feet from Parcel E2b.1.1.1. This site will undergo additional evaluation in the OE RI/FS.

Site OE-2 – Identified as a potential chemical training area and landfill (Plate 10). Hundreds of 2.36-inch practice rockets have been removed from disposal pits located in former landfill areas within the site. OE sampling of this site was conducted and two OE scrap items were found. This site will undergo additional evaluation in the OE RI/FS.

Incident Reports UXO

Incidental location E2b.1.1.1

On February 20, 2002, a 75mm projectile (partially detonated) was found during a site inspection near Building 2882. The USACE UXO Safety Specialist transferred the UXO item to the OE removal contractor for disposal. It was concluded that the 75mm round was most likely a discarded item and is not related to past ordnance training in this area. A detailed report was submitted to the DTSC and US EPA on June 3, 2002.

Incidental location Parcel E2b.3.1.1

On November 12, 1992 members of the 49th Explosive Ordnance Detachment (EOD) removed a grenade simulator and two airburst simulators from military police investigation (MPI) Building 1025. The items were brought to Building 1025 and were being held as evidence during a criminal investigation conducted by the Fort Ord military police. A detailed report was submitted to the DTSC and US EPA on June 3, 2002.

On February 11, 1993 members of the 49th EOD removed 100 5.56mm blank rounds and one 20 round clip from MPI Building 1025. The items were brought to Building 1025 and were being held as evidence during a criminal investigation conducted by the Fort Ord military police. A detailed report was submitted to the DTSC and US EPA on June 3, 2002.

OE Scrap

Incident Location Parcels L5.8.1/L23.4

On March 4, 1996, the Fort Ord Federal police were notified of the presence of a 37mm projectile lying behind Building 4885. The responding EOD personnel identified the projectile as an inert 37mm armor piercing (AP) projectile and disposed of the item as OE scrap. It was determined that the 37mm projectile was a discarded item and its presence at Building 4885 was not a result of ordnance training in that area. A detailed report was submitted to the DTSC and US EPA on June 3, 2002.

Incident location Parcel L35.1

On September 8, 1993 a practice antitank mine was removed by the 49th EOD from Building 3107 (Thrift Shop). It was determined that the practice antitank mine was brought to Building 3107 to be sold in a garage sale-type event and was not related to ordnance training in the area. The inert training device (OE scrap) was returned to inventory for training. A detailed report was submitted to the DTSC and US EPA on June 3, 2002.

Incident location Parcel L35.1

Inert practice mine found in a recreational vehicle storage yard. Fort Ord Range Control questioned the responding EOD personnel and found that the item was an inert training device. Because no ordnance training took place in this area, it is likely that the practice mine was a discarded item (*HLA, 1994b*).

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	-------------

TRACK 0 CHECKLIST

OU2 Landfill

PARCEL	E2e.1, E2e.2, E8a.1.2, E8a.1.3, E8a.1.4, E8a.1.5, S1.3.3, S2.5.1.1, S2.5.1.2, and portions of Parcels S2.5.2.1 and S2.5.2.2 – OU 2 Landfill Area.
DESCRIPTION	The parcels lie in the north central portion of the former Fort Ord, adjacent to the former Fort Ord landfill. The area is open space with a combined parcel acreage of approximately 156 acres (Plate 11).
HISTORICAL USE	<p>History suggests no OE used.</p> <p>Prior to Army purchase this area was ranch land (David Jacks Corporation) and was purchased by the Army in 1940.</p> <p>About 1954: Area designated as camouflage area (Parcels S2.5.1.1 and S2.5.2.1). Practice Mortar Range, OE Site 13A established to the north of Parcels E8a.1.2 and E8a.1.3.</p> <p>1954: Barracks and support facilities constructed to the south, adjacent to Parcels E2e.1 and E2e.2.</p> <p>1956: The area was designated as a surveying training area and a camouflage area (Parcels S2.5.1.1 and S2.5.2.1). A rifle instruction circle and two buildings were constructed on land adjacent (to the west). Additionally, a proficiency test area was established to the east (Plate 11). Landfill (Area A) was in use (north).</p> <p>1958: PG&E gas line is shown running east/west across the Parcels E2e.1, S2.5.2.1, S2.5.2.2 and E8a.1.4 and toward the East Garrison. PG&E 12 KV electrical transmission line is noted running along Parcel E2e.1.</p> <p>1960: Land-filling begins in Parcel E8a.1.</p> <p>1962-1969: Patton Park Housing constructed (north).</p> <p>1964: Obstacle course constructed (Parcel S2.5.2.1).</p> <p>Late 1970s: Athletic fields constructed to the north of the parcels (Area A).</p> <p>1981: Construction of housing to the east of the OU 2 Landfill.</p>

Supporting documents

Literature Review and Base Inventory Report, Volume 1; Community Environmental Response Facilitation Act (CERFA) Report; Archives Search Reports; OE RI/FS Literature Review; After Action Report, OE Gridstats Sampling, Site OE-13A; Final Report for Ordnance and Explosive Removal Action, Site CSU; OEW Sampling and OEW Removal Action; Remedial Action Confirmation Report, Area A, Operable Unit 2 Landfills; Remedial Action Confirmation Report and Post-Remediation Health Risk Assessment, Sites 16 and 17; Predesign Technical Memorandum, Operable Unit 2, Fort Ord Landfills; Report of Quarterly Monitoring, October through December 1999.

Components**Aerial Photos**

Pre-1940, 7/25/41, 8/17/49, 6/23/51, 7/3/51, 5/14/56, 58/59 (aerial contours), 1/11/65 (mosaic), 5/2/66, 1/18/74, 12/17/75, 6/16/78, 4/13/85, 10/22/85, 3/25/86, 11/12/86, 11/4/88, 10/4/89, 7/6/92

Real Estate Records

1913 Department of the Interior, reprinted 1918
1915 Proposed Acreage Subdivisions
1922 Assessors Plats, Monterey County
3/18/88 Real Estate, Fort Ord

**Range Control Records/
Standard Operating Procedures**

Not applicable to this area

Range and Training Area Maps

8/45 Training Facilities
Circa 1954 Training Areas that Cannot Be Used at the Same Time
7/3/56 Range Complex
12/20/56 Fort Ord Training Areas & Facilities
7/15/57 Training Areas & Facilities
1/10/58 Training Areas & Facilities
12/31/58 Ranges & Training Facilities
6/30/61 Basic Information, Training Facilities
4/27/64 Field Training Areas & Range Map
8/16/65 Close In Training Areas
1/67 Field Training Areas & Range Map
5/1/67 Close In Training Areas
3/13/68 Training Facilities Map
11/1/71 Training Facilities Plan
3/16/72 Training Ranges and General Road Map
7/1/72 Field Training Area and Range Map

2/23/73 Close In Training Areas
 2/1/76 Ranges and Training Area Overlay
 12/1/76 Future Development Plans, Training
 Facilities Plan
 3/1/76 Close In Training Areas
 6/1/77 Training Facilities Plan
 1/78 Ranges and Training Area Overlay
 7/15/78 Ranges and Training Area Overlay
 3/80 Training Facilities Map
 6/1/81 Ranges and Training Area Overlay
 4/1/82 Ranges and Training Area Overlay
 4/27/84 Field Training Areas and Range Map
 6/84 Training Facilities Map
 11/15/87 Ranges and Training Area Overlay

Base Development Plans and Maps

1922 Assessors Plats, Monterey Co.
 1934 War Department, Camp Ord and Vicinity
 1944 Army Map Service, Fort Ord Military
 Reservation
 3/20/46 Fort Ord Master Plans
 4/5/46 Fort Ord Master Plans
 1/15/69 Post Locator Map
 1972 Fort Ord and Vicinity (V895S)
 3/1/75 Master Plan, Reservation Map
 8/1/84 Fort Ord Military Installation Map
 (V795S)
 1985 Fort Ord Locator Map
 2/10/90 Fort Ord Locator Map, Main Garrison

SITE INVESTIGATION ACTIVITIES

Site Walks

OE program: Parcels S2.5.1.1 and S2.5.2.1 were
 walked by a USACE UXO Safety Specialist.
 No UXO or OE scrap was found.

Geophysics

Borehole clearance completed prior to
 monitoring well installation.

Excavations

None

Soil Borings

None

Wells

HTW monitoring wells: 7 (see Report of
 Quarterly Monitoring for locations).

ADJACENT AREAS

CBR Training Areas	Site OE-4C – A removal action was conducted at this site and no chemical related OE items were found. This site will undergo additional evaluation in the OE RI/FS.
CWM Training Areas	None
Small Arms Ranges	None

OE INFORMATION

Known or Suspected Adjacent OE Sites	<p>Site OE-2 – Identified as a potential chemical training area and landfill (Plate 11). Hundreds of 2.36-inch practice rockets have been removed from disposal pits located in former landfill areas within the site. OE sampling of this site was conducted and two OE scrap items were found. This site will undergo additional evaluation in the OE RI/FS.</p> <p>Site OE-13A – Sampling of Site OE-13A was conducted and no evidence of OE use was found. Confirmatory sample grids were completed outside of the OE site boundary on the eastern end of the site and two OE scrap items were found (expended grenade fuze and an expended illuminating signal). No further action was recommended for this site. Site will undergo additional evaluation in the OE RI/FS.</p> <p>OE-related items were found during the excavation and removal of the landfill disposal area (Area A). It has been determined that the presence of these items was related to disposal and not OE use in this area. The disposal area has been completely excavated.</p> <p>Site OE-31 – An OE removal action over the entire site (Site CSU) was conducted. Site OE-31 encompasses Sites OE-7, OE-8, OE-4C, OE-18 and a portion of OE-13B. Site OE-31 is immediately adjacent to the Track 0 parcels. This Site will undergo additional evaluation in the OE RI/FS.</p>
---------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

**Incident Reports
UXO**

None

OE Scrap

Incident location Parcel E8a.1.4
 On July 1, 2001 an expended 3.5-inch practice rocket was discovered during a horseback ride, adjacent to a trail near the OU 2 landfill. The USACE UXO Safety Specialist removed and disposed of the OE scrap item. It was concluded that the 3.5-inch rocket was discarded and was not related to ordnance training in this area. A detailed report was submitted to the DTSC and the US EPA on June 3, 2002.

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	-------------

TRACK 0 CHECKLIST
Reservation Road

PARCEL	L5.10, L20.10.1.1, L20.10.1.2, L20.10.2, and L20.10.3 – Reservation Road Area
DESCRIPTION	Approximately 55 acre portion of Reservation Road. Portions of the road between these parcels are not included because they are not on Fort Ord property (Plate 12).
HISTORICAL USE	<p>History suggests no OE used</p> <p>Prior to Army purchase this area was ranch land (David Jacks Corporation). Portions of the land (Parcels L20.10.1.2, L20.10.2, L20.10.3, and a portion of L20.10.1.1) were purchased by the Army in 1917.</p> <p>1934: Portions of the road (unimproved) are in place (Parcel L5.10, L20.10.2 and L20.10.3).</p> <p>1941: New County Road established (Parcels L5.10, L20.10.1.1, L20.10.1.2, L20.10.2, and L20.10.3).</p> <p>By 1951 the road has been widened to 4 lanes (Parcels L5.10, L20.10.1.1, and L20.10.1.2 only).</p>
Supporting documents	Literature Review and Base Inventory Report, Volume 1; Community Environmental Response Facilitation Act (CERFA) Report; Archives Search Reports; OE RI/FS Literature Review; Ordnance and Explosive Removal Action, OE Cache (Site OE-33).
<u>Components</u>	
Aerial Photos	7/25/41, 8/17/49, 6/23/51, 5/14/56, 8/1/56, 58/59 (aerial contours), 1/11/65 (mosaic), 5/2/66, 12/17/75, 6/16/78, 4/13/85, 10/22/85, 3/25/86, 11/12/86, 11/4/88, 10/4/89, 7/6/92.
Real Estate Records	<p>1912 Salinas Quadrangle</p> <p>1913 Department of the Interior, reprinted 1918</p> <p>1915 Proposed Acreage Subdivisions</p> <p>1922 Assessors Plats, Monterey County</p> <p>3/18/88 Real Estate, Fort Ord</p>

**Range Control Records/
Standard Operating Procedures**

Not applicable to this area.

Range and Training Area Maps

6/20/40 Camp Ord, Ultimate Layout of
Concurrent Training Camps
8/45 Training Facilities
Circa 1954 Training Areas that Cannot Be Used
at the Same Time
7/3/56 Range Complex
12/20/56 Fort Ord Training Areas & Facilities
7/15/57 Training Areas & Facilities
1/10/58 Training Areas & Facilities
12/31/58 Ranges & Training Facilities
4/27/64 Field Training Areas & Range Map
1/67 Field Training Areas & Range Map
3/13/68 Training Facilities Map
11/1/71 Training Facilities Plan
3/16/72 Training Ranges and General Road Map
7/1/72 Field Training Area and Range Map
2/1/76 Ranges and Training Area Overlay
12/1/76 Future Development Plans, Training
Facilities Plan
6/1/77 Training Facilities Plan
1/78 Ranges and Training Area Overlay
7/15/78 Ranges and Training Area Overlay
3/80 Training Facilities Map
6/1/81 Ranges and Training Area Overlay
4/1/82 Ranges and Training Area Overlay
4/27/84 Field Training Areas and Range Map
6/84 Training Facilities Map
11/15/87 Ranges and Training Area Overlay

Base Development Plans and Maps

1922 Assessors Plats, Monterey Co.
1934 War Department, Camp Ord and Vicinity
1940 Salinas Quadrangle, Grid Zone "G",
U.S Army Tactical Map
11/28/41 East Garrison Topographical &
Temporary Housing Layout
1/28/42 East Garrison, Layout of Buildings &
Roads
1944 Army Map Service, Fort Ord Military
Reservation
4/5/46 East Garrison Cantonment and Use Map
4/5/46 Reservation Boundary & Land Use Map
1972 Fort Ord and Vicinity (V895S)
3/1/75 Master Plan, Reservation Map
6/1/77 Future Development Plans, Reservation
Plan

8/1/84 Fort Ord Military Installation Map
(V795S)
2/10/90 Fort Ord Locator Map, Main Garrison

SITE INVESTIGATION ACTIVITIES

Site Walks	EBS/FOST: Portions of the parcels were walked in support of property transfer.
Geophysics	None
Excavations	None
Soil Borings	None
Wells	None

ADJACENT AREAS

CBR Training Areas	None
CWM Training Areas	None
Small Arms Ranges	None

OE INFORMATION

Known or Suspected Adjacent OE Sites	Site OE-33 – This site (a fox hole) lies on a bluff to the south of Parcel L20.10.3. The site was identified by the Fort Ord Federal Police. An OE removal action was conducted. UXO items removed included a practice 40mm cartridge, five 40mm smoke cartridges and small arms ammunition. This site will undergo additional evaluation in the OE RI/FS (Plate 12).
---------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Incident Reports	
UXO	None
OE Scrap	None

EVIDENCE OF PAST OE USE:	NONE
---------------------------------	-------------