

**Table 11**

**Summary of Pumping Well Flow Rates During the Combined Well Aquifer Test**

<b>Pumping Test</b>	<b>Pumping Well(s)</b>	<b>Average Flow Rate (gpm)</b>
<b>Combined Well (Phase I)</b>	EW-1	1,250
	EW-2	1,260
	EW-3	1,700
	EW-4	1,340
	EW-5	1,300
	EW-108 <sup>(1)</sup>	2,200
	EW112	2,230
	Perris Street	1,350
	<i>Combined-Well Flow Rate</i>	<i>12,630</i>
<b>Combined Well (Phase II)</b>	EW-1	1,250
	EW-2	1,360
	EW-3	1,670
	EW-4	1,400
	EW-5	1,430
	EW-108	2,190
	EW112	2,220
	Perris Street	2,240
	9th Street	2,240
	10th & J	2,340
	<i>Combined-Well Flow Rate</i>	<i>18,340</i>

**NOTE:**

(1) Flow sensor malfunctioned between 3/24/03 and 4/1/03; flow rate indicated in table is based on measurements recorded between 4/1/03 and 4/7/03